

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+05.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	15 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
0010	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	175 TON		
0011	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	205 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
0013	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0014	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0015	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0016	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0017	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
002C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	225 LF		
0022	3030000000-E	862	STEEL BM GUARDRAIL	437.5 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
002E	3649000000-E	876	RIP RAP, CLASS B	15 TON		
0027	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	230 SY		
002E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
002E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	372 SF		
003C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	96 SF		
0031	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0032	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,000 LF		
0033	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10 EA		
0034	5325800000-E	1510	8" WATER LINE	444 LF		
003E	5546000000-E	1515	8" VALVE	2 EA		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	6000000000-E	1605	TEMPORARY SILT FENCE	1,175	LF	
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	15	TON	
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	125	TON	
004C	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
004E	6029000000-E	SP	SAFETY FENCE	1,250	LF	
0044	6030000000-E	1630	SILT EXCAVATION	40	CY	
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	360	SY	
004E	6037000000-E	SP	COIR FIBER MAT	10	SY	
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	375	LF	
004E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	125	SY	
004E	6071010000-E	SP	WATTLE	75	LF	
005C	6071020000-E	SP	POLYACRYLAMIDE (PAM)	24	LB	
0051	6071030000-E	SP	COIR FIBER BAFFLES	30	LF	
0052	6071050000-E	SP	*** SKIMMER (1-1/2")	1	EA	
005E	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0054	6087000000-E	1660	MOWING	1	ACR	

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
005E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
006C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0061	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+05.00-L-)	Lump Sum	L.S.	
0062	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0063	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+05.00-L-)	Lump Sum	L.S.	
0064	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	34.8 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+05.00-L-)	Lump Sum	L.S.	
006E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,944 LB		
0067	8364000000-E	450	HP12X53 STEEL PILES	805 LF		
006E	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	455 LF		
006E	8393000000-N	450	PILE REDRIVES	15 EA		
007C	8503000000-E	460	CONCRETE BARRIER RAIL	155.43 LF		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8590000000-E	876	RIP RAP, CLASS ** (I)	181 TON		
0072	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	200 SY		
0073	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0074	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	853.42 LF		

1357/Feb26/Q20655.15/D351411750000/E74

Total Amount Of Bid For Entire Project :

Contract No **C202091**

County (ies): **Bertie**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General