

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (39+60)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,950 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	18,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	30 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	2,500 CY		
0010	0199000000-E	SP	TEMPORARY SHORING	3,200 SF		
0011	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	960 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	710 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,132 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	712 LF		
0015	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	300 LF		
0016	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	24 LF		
0017	0420000000-E	310	66" RC PIPE CULVERTS, CLASS III	4 LF		
0018	0995000000-E	340	PIPE REMOVAL	1,291 LF		
0019	0996000000-N	350	PIPE CLEAN-OUT	1 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1121000000-E	520	AGGREGATE BASE COURSE	330 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0022	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,490 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,120 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,370 TON		
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	550 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	425 TON		
0028	1891000000-E	SP	GENERIC PAVING ITEM 7" TINTED PORTLAND CONCRETE APRON	230 SY		
0029	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0030	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0031	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0032	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0033	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0034	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0035	2220000000-E	838	REINFORCED ENDWALLS	7 CY		
0036	2253000000-E	840	PIPE COLLARS	1.5 CY		
0037	2275000000-E	SP	FLOWABLE FILL	17 CY		
0038	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	61 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	33 LF		
0040	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	5 EA		
0041	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0042	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	13 EA		
0043	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	19 EA		
0044	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	20 EA		
0045	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0046	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	340 LF		
0047	2535000000-E	846	***X *** CONCRETE CURB (9" X 18")	250 LF		
0048	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	680 LF		
0049	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	7,650 LF		
0050	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	60 LF		
0051	2591000000-E	848	4" CONCRETE SIDEWALK	2,960 SY		
0052	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	39 EA		
0053	2612000000-E	848	6" CONCRETE DRIVEWAY	2,130 SY		
0054	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	470 SY		
0055	2738000000-E	SP	GENERIC PAVING ITEM BRICK SIDEWALK	310 SY		
0056	3030000000-E	862	STEEL BM GUARDRAIL	525 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0058	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0059	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	3 EA		
0060	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0061	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0062	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC (72")	172 LF		
0063	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (72")	14 EA		
0064	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (72")	8 EA		
0065	3563000000-E	SP	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (60")	175 LF		
0066	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,200 SY		
0067	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0068	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	1 CY		
0069	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	548 LB		
0070	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,953 LF		
0071	4096000000-N	904	SIGN ERECTION, TYPE D	9 EA		
0072	4102000000-N	904	SIGN ERECTION, TYPE E	80 EA		
0073	4108000000-N	904	SIGN ERECTION, TYPE F	19 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	1 EA		
0075	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	2 EA		
0076	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0077	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	66 EA		
0078	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	13 EA		
0079	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	4 EA		
0080	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	704 SF		
0081	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	160 SF		
0082	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	171 SF		
0083	4430000000-N	1130	DRUMS	46 EA		
0084	4435000000-N	1135	CONES	50 EA		
0085	4445000000-E	1145	BARRICADES (TYPE III)	328 LF		
0086	4450000000-N	1150	FLAGGER	640 HR		
0087	4480000000-N	1165	TMIA	1 EA		
0088	4507000000-E	SP	WATER FILLED BARRIER	130 LF		
0089	4510000000-N	SP	POLICE	80 HR		
0090	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	213 EA		
0091	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	75 EA		

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	49,638	LF	
0093	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	150	LF	
0094	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,746	LF	
0095	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	56	EA	
0096	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4" *****) (STANDARD GLASS BEADS)	13,181	LF	
0097	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8" *****) (STANDARD GLASS BEADS)	202	LF	
0098	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24" *****) (STANDARD GLASS BEADS)	1,492	LF	
0099	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,000	LF	
0100	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	137	EA	
0101	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	80	LF	
0102	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	2	EA	
0103	5325200000-E	1510	2" WATER LINE	695	LF	
0104	5325600000-E	1510	6" WATER LINE	1,180	LF	
0105	5325800000-E	1510	8" WATER LINE	296	LF	
0106	5326000000-E	1510	10" WATER LINE	130	LF	
0107	5326200000-E	1510	12" WATER LINE	2,668	LF	
0108	5536000000-E	1515	2" VALVE	4	EA	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	5540000000-E	1515	6" VALVE	7 EA		
0110	5558000000-E	1515	12" VALVE	5 EA		
0111	5572000000-E	1515	10" TAPPING VALVE	1 EA		
0112	5648000000-N	1515	RELOCATE WATER METER	16 EA		
0113	5649000000-N	1515	RECONNECT WATER METER	8 EA		
0114	5672000000-N	1515	RELOCATE FIRE HYDRANT	4 EA		
0115	5691400000-E	1520	10" SANITARY GRAVITY SEWER	60 LF		
0116	5709300000-E	1520	6" FORCE MAIN SEWER	264 LF		
0117	5776000000-E	1525	5' DIA UTILITY MANHOLE	1 EA		
0118	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	2 LF		
0119	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,100 LF		
0120	5801000000-E	1530	ABANDON 8" UTILITY PIPE	285 LF		
0121	5804000000-E	1530	ABANDON 12" UTILITY PIPE	2,932 LF		
0122	5882000000-N	SP	GENERIC UTILITY ITEM 8" WATER METER AND METER VAULT	1 EA		
0123	5882000000-N	SP	GENERIC UTILITY ITEM ABANDON WATER METER VAULT	1 EA		
0124	5912000000-N	SP	GENERIC UTILITY ITEM TEMPORARY 10" WATER LINE	Lump Sum	L.S.	
0125	6000000000-E	1605	TEMPORARY SILT FENCE	12,500 LF		
0126	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	600 TON		
0127	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	820 TON		
0128	6012000000-E	1610	SEDIMENT CONTROL STONE	930 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0129	6015000000-E	1615	TEMPORARY MULCHING	19 ACR		
0130	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	500 LB		
0131	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	3 TON		
0132	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0133	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0134	6029000000-E	SP	SAFETY FENCE	700 LF		
0135	6030000000-E	1630	SILT EXCAVATION	2,300 CY		
0136	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,400 SY		
0137	6037000000-E	SP	COIR FIBER MAT	30 SY		
0138	6042000000-E	1632	1/4" HARDWARE CLOTH	2,400 LF		
0139	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	620 SY		
0140	6071030000-E	SP	COIR FIBER BAFFLES	300 LF		
0141	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0142	6084000000-E	1660	SEEDING & MULCHING	21 ACR		
0143	6087000000-E	1660	MOWING	12.5 ACR		
0144	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0145	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0146	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	350 LB		
0147	6108000000-E	1665	FERTILIZER TOPDRESSING	10 TON		
0148	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		

County : Edgcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0149	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
0150	6123000000-E	1670	REFORESTATION	1 ACR		
0151	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION WITH COUNT- DOWN)	8 EA		
0152	7060000000-E	1705	SIGNAL CABLE	3,400 LF		
0153	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	22 EA		
0154	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0155	7264000000-E	1710	MESSENGER CABLE (3/8")	1,330 LF		
0156	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2"))	260 LF		
0157	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	4 EA		
0158	7360000000-N	1720	WOOD POLE	8 EA		
0159	7372000000-N	1721	GUY ASSEMBLY	16 EA		
0160	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2 EA		
0161	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0162	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,580 LF		
0163	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	3,000 LF		
0164	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	2 EA		
0165	7576000000-N	SP	METAL STRAIN SIGNAL POLE	4 EA		
0166	7613000000-N	SP	SOIL TEST	4 EA		
0167	7614100000-E	SP	DRILLED PIER FOUNDATION	24 CY		

County : Edgemcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0168	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	
0169	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1	EA	
0170	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1	EA	
0171	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	8	EA	
0172	7901000000-N	1753	CABINET BASE EXTENDER	1	EA	
0173	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	1	EA	
0174	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	4	EA	
0175	7972000000-N	SP	METAL POLE REMOVAL	4	EA	

WALL ITEMS

0176	8847000000-E	SP	GENERIC RETAINING WALL ITEM 18" STEEL SHEET PILES (27+59.40-L-)	1,367	SF	
------	--------------	----	---	-------	----	--

STRUCTURE ITEMS

0177	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (39+59.00-L-)	Lump Sum	L.S.	
0178	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (39+59.00-L-)	Lump Sum	L.S.	
0179	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,39+59.00-L-)	Lump Sum	L.S.	
0180	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2,39+59.00-L-)	Lump Sum	L.S.	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0181	8112730000-N	SP	PDA TESTING	2 EA		
0182	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0183	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (39+59.00-L-)	Lump Sum	L.S.	
0184	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	23,674 SF		
0185	8161000000-E	420	GROOVING BRIDGE FLOORS	17,100 SF		
0186	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	311.3 CY		
0187	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (39+59.00-L-)	Lump Sum	L.S.	
0188	8217000000-E	425	REINFORCING STEEL (BRIDGE)	46,677 LB		
0189	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,462 LB		
0190	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	1,640,500 LS		
0191	8333000000-E	450	16" PRESTRESSED CONC PILES	2,160 LF		
0192	8364000000-E	450	HP12X53 STEEL PILES	1,075 LF		
0193	8393000000-N	450	PILE REDRIVES	40 EA		
0194	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	870 TON		
0195	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	964 SY		
0196	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0197	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
0198	8860000000-N	SP	GENERIC STRUCTURE ITEM 10" WATER MAIN	Lump Sum	L.S.	
0199	8860000000-N	SP	GENERIC STRUCTURE ITEM 6" SEWER FORCE MAIN	Lump Sum	L.S.	

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0200	8860000000-N	SP	GENERIC STRUCTURE ITEM TELEPHONE CONDUITS	Lump Sum	L.S.	
0201	8867000000-E	SP	GENERIC STRUCTURE ITEM CLASSIC CONCRETE BRIDGE RAIL	1,006.42 LF		
0202	8867000000-E	SP	GENERIC STRUCTURE ITEM MESSENGER CABLE SYSTEM	500 LF		
0203	8897000000-N	SP	GENERIC STRUCTURE ITEM LIGHT STANDARD LUMINAIRES (TYPE RDW, 250W, HPS)	4 EA		
0204	8897000000-N	SP	GENERIC STRUCTURE ITEM RELOCATE LIGHT STANDARD	4 EA		
0714/Apr09/Q1921848.72/D993680700000/E203			Total Amount Of Bid For Entire Project :			

Contract No **C202039**

County (ies): **Edgecombe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General