

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	190 LF		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	0.5 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	40,000 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	7,000 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (2-1/2" TO 4")	67,000 SY		
0007	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	15,248 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	15,550 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,650 TON		
0010	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	210 TON		
0011	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0012	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0013	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	400 LF		
0014	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	22 EA		
0015	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	4 EA		
0016	2612000000-E	848	6" CONCRETE DRIVEWAY	40 SY		
0017	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	2 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2830000000-N	858	ADJUSTMENT OF MANHOLES	27 EA		
0019	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	30 EA		
0020	3883000000-N	SP	GENERIC TRACKWORK ITEM REMOVAL & DISPOSAL OF RAILROAD SPUR TRACK	Lump Sum	L.S.	
0021	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0022	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0023	4430000000-N	1130	DRUMS	500 EA		
0024	4435000000-N	1135	CONES	500 EA		
0025	4480000000-N	1165	TMIA	2 EA		
0026	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	272,500 LF		
0027	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	300 LF		
0028	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	2,000 LF		
0029	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	161 EA		
0030	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,652 EA		
0031	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0032	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	20,000 LF		
1448/Mar19/Q445001.5/D98272100000/E32			Total Amount Of Bid For Entire Project :			

Contract No **C202213**

County (ies): **Henderson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General