

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	2 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	68,500 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (94+15.00)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	18,100 CY		
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	500 TON		
0010	0106000000-E	230	BORROW EXCAVATION	50,000 CY		
0011	0134000000-E	240	DRAINAGE DITCH EXCAVATION	480 CY		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,560 SY		
0013	0192000000-N	260	PROOF ROLLING	10 HR		
0014	0195000000-E	265	SELECT GRANULAR MATERIAL	1,500 CY		
0015	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,500 SY		
0016	0234000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS III	500 CY		
0017	0314000000-E	300	SELECT MATERIAL, CLASS ***** (VI)	365 TON		
0018	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	310 TON		
0019	0344000000-E	310	18" SIDE DRAIN PIPE	352 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	248 LF		
0021	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	220 LF		
0022	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	576 LF		
0023	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	196 LF		
0024	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	40 LF		
0025	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0026	0995000000-E	340	PIPE REMOVAL	463 LF		
0027	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0028	1121000000-E	520	AGGREGATE BASE COURSE	16,000 TON		
0029	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0030	1275000000-E	600	PRIME COAT	950 GAL		
0031	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,000 TON		
0032	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	8,700 TON		
0033	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,100 TON		
0034	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,145 TON		
0035	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0036	2000000000-N	806	RIGHT OF WAY MARKERS	82 EA		
0037	2022000000-E	815	SUBDRAIN EXCAVATION	168 CY		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0039	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0040	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0041	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0042	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0043	2209000000-E	838	ENDWALLS	36 CY		
0044	2253000000-E	840	PIPE COLLARS	2 CY		
0045	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	12 EA		
0046	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.68 LF		
0047	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	9 EA		
0048	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0049	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	2 EA		
0050	2474000000-N	SP	GENERIC DRAINAGE ITEM HAZARDOUS SPILL BASINS	Lump Sum	L.S.	
0051	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
0052	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	20 SY		
0053	3030000000-E	862	STEEL BM GUARDRAIL	1,800 LF		
0054	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0055	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0056	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0058	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	7 EA		
0059	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	25,440 LF		
0060	3506000000-E	866	4" TIMBER FENCE POSTS, ***** LONG (7'-6")	1,600 EA		
0061	3512000000-E	866	5" TIMBER FENCE POSTS, ***** LONG (8')	410 EA		
0062	3557000000-E	866	ADDITIONAL BARBED WIRE	1,000 LF		
0063	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (48", 12', 24')	2 EA		
0064	3649000000-E	876	RIP RAP, CLASS B	330 TON		
0065	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	8,575 SY		
0066	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		
0067	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,170 LF		
0068	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		
0069	4102000000-N	904	SIGN ERECTION, TYPE E	65 EA		
0070	4108000000-N	904	SIGN ERECTION, TYPE F	4 EA		
0071	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE ***** (GROUND MOUNTED) (E)	5 EA		
0072	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	31 EA		
0073	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	5 EA		
0074	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	288 SF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	480	SF	
0076	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	80	SF	
0077	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0078	4430000000-N	1130	DRUMS	175	EA	
0079	4435000000-N	1135	CONES	100	EA	
0080	4445000000-E	1145	BARRICADES (TYPE III)	275	LF	
0081	4450000000-N	1150	FLAGGER	1,440	HR	
0082	4480000000-N	1165	TMIA	2	EA	
0083	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	119	EA	
0084	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	28,448	LF	
0085	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	18,255	LF	
0086	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	100	LF	
0087	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	670	LF	
0088	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	67	EA	
0089	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	52,840	LF	
0090	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	226	LF	
0091	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	11	EA	
0092	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	12,148	LF	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	375 EA		
0094	4915000000-E	1264	7' U-CHANNEL POSTS	6 EA		
0095	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	6 EA		
0096	5325200000-E	1510	2" WATER LINE	266 LF		
0097	5325600000-E	1510	6" WATER LINE	240 LF		
0098	5325800000-E	1510	8" WATER LINE	2,526 LF		
0099	5536000000-E	1515	2" VALVE	1 EA		
0100	5546000000-E	1515	8" VALVE	2 EA		
0101	5648000000-N	1515	RELOCATE WATER METER	11 EA		
0102	5649000000-N	1515	RECONNECT WATER METER	3 EA		
0103	5672000000-N	1515	RELOCATE FIRE HYDRANT	5 EA		
0104	5691400000-E	1520	10" SANITARY GRAVITY SEWER	198 LF		
0105	5800000000-E	1530	ABANDON 6" UTILITY PIPE	643 LF		
0106	5801000000-E	1530	ABANDON 8" UTILITY PIPE	2,289 LF		
0107	5815000000-N	1530	REMOVE WATER METER	3 EA		
0108	5882000000-N	SP	GENERIC UTILITY ITEM ANTI-SEEPAGE COLLAR	2 EA		
0109	6000000000-E	1605	TEMPORARY SILT FENCE	9,900 LF		
0110	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	2,325 TON		
0111	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,150 TON		
0112	6012000000-E	1610	SEDIMENT CONTROL STONE	2,150 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0113	6015000000-E	1615	TEMPORARY MULCHING	45.5	ACR	
0114	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	850	LB	
0115	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	5.25	TON	
0116	6024000000-E	1622	TEMPORARY SLOPE DRAINS	375	LF	
0117	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5	EA	
0118	6029000000-E	SP	SAFETY FENCE	8,050	LF	
0119	6030000000-E	1630	SILT EXCAVATION	9,350	CY	
0120	6036000000-E	1631	MATTING FOR EROSION CONTROL	13,100	SY	
0121	6037000000-E	SP	COIR FIBER MAT	100	SY	
0122	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,375	SY	
0123	6042000000-E	1632	1/4" HARDWARE CLOTH	175	LF	
0124	6070000000-N	SP	SPECIAL STILLING BASINS	50	EA	
0125	6071030000-E	SP	COIR FIBER BAFFLES	1,400	LF	
0126	6071050000-E	SP	*** SKIMMER (1-1/2")	8	EA	
0127	6084000000-E	1660	SEEDING & MULCHING	55.5	ACR	
0128	6087000000-E	1660	MOWING	33.5	ACR	
0129	6090000000-E	1661	SEED FOR REPAIR SEEDING	400	LB	
0130	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.25	TON	
0131	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	675	LB	
0132	6108000000-E	1665	FERTILIZER TOPDRESSING	20	TON	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0133	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0134	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
0135	6123000000-E	1670	REFORESTATION	0.25 ACR		
0136	7060000000-E	1705	SIGNAL CABLE	2,650 LF		
0137	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	26 EA		
0138	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	5 EA		
0139	7264000000-E	1710	MESSENGER CABLE (3/8")	2,135 LF		
0140	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	20 LF		
0141	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	3,100 LF		
0142	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	26 EA		
0143	7360000000-N	1720	WOOD POLE	3 EA		
0144	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0145	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0146	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0147	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,300 LF		
0148	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	10,377 LF		
0149	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	2 EA		
0150	7576000000-N	SP	METAL STRAIN SIGNAL POLE	12 EA		
0151	7613000000-N	SP	SOIL TEST	12 EA		
0152	7614100000-E	SP	DRILLED PIER FOUNDATION	84 CY		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0153	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0154	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
0155	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	20 EA		
0156	7901000000-N	1753	CABINET BASE EXTENDER	3 EA		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0157 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	744 LF		
0158 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	876 LF		
*** OR ***						
0159 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	172 LF		
0160 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	324 LF		
0161 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	572 LF		
0162 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	552 LF		
*** OR ***						
0163 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	172 LF		
0164 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	324 LF		
0165 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	572 LF		
0166 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	552 LF		
***** END SCHEDULE AA *****						

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0167	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (94+15.00-L-)	Lump Sum	L.S.	
0168	8105500000-E	SP	***-*** DIA DRILLED PIERS IN SOIL (4'-6")	388.6 LF		
0169	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	309.3 LF		
0170	8105600000-E	SP	***-*** DIA DRILLED PIERS NOT IN SOIL (4'-6")	204 LF		
0171	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	210 LF		
0172	8111000000-E	SP	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (4'-6")	299.8 LF		
0173	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	263.9 LF		
0174	8113000000-N	SP	SID INSPECTION	4 EA		
0175	8115000000-N	SP	CROSSHOLE SONIC LOGGING	4 EA		
0176	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	102,790 SF		
0177	8161000000-E	420	GROOVING BRIDGE FLOORS	87,153.7 SF		
0178	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	1,097.1 CY		
0179	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (94+15.00-L-)	Lump Sum	L.S.	
0180	8217000000-E	425	REINFORCING STEEL (BRIDGE)	394,679 LB		
0181	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	54,272 LB		
0182	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	11,819.1 LF		
0183	8364000000-E	450	HP12X53 STEEL PILES	440 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0184	8475000000-E	460	TWO BAR METAL RAIL	5,927.8 LF		
0185	8517000000-E	460	1'-**"X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	5,944.5 LF		
0186	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	345 TON		
0187	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	330 SY		
0188	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0189	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0190	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (94+15.00-L-)	Lump Sum	L.S.	

0812/Apr09/Q1096116.73/D831809300000/E189

Total Amount Of Bid For Entire Project :

Contract No **C201300**

County (ies): **Johnston**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General