

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	300 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+21.00)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0008	0106000000-E	230	BORROW EXCAVATION	4,300 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	80 CY		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	170 SY		
0011	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	690 SY		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0013	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0014	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	25 TON		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	20 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0017	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0018	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	425 TON		
0020	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	250 TON		
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	300 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	50 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0026	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0028	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0029	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0030	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0033	2556000000-E	846	SHOULDER BERM GUTTER	28 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	362.5 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
0038	3360000000-E	863	REMOVE EXISTING GUARDRAIL	460	LF	
0039	3649000000-E	876	RIP RAP, CLASS B	205	TON	
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	920	SY	
0041	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	16	LF	
0042	4102000000-N	904	SIGN ERECTION, TYPE E	2	EA	
0043	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	7	EA	
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	394	SF	
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	107	SF	
0046	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,200	LF	
0048	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	11	EA	
0049	5326000000-E	1510	10" WATER LINE	366	LF	
0050	5648000000-N	1515	RELOCATE WATER METER	1	EA	
0051	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	
0052	6000000000-E	1605	TEMPORARY SILT FENCE	475	LF	
0053	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	250	TON	
0055	6012000000-E	1610	SEDIMENT CONTROL STONE	125	TON	

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0058	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
0059	6024000000-E	1622	TEMPORARY SLOPE DRAINS	550	LF	
0060	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0061	6029000000-E	SP	SAFETY FENCE	500	LF	
0062	6030000000-E	1630	SILT EXCAVATION	560	CY	
0063	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,050	SY	
0064	6037000000-E	SP	COIR FIBER MAT	25	SY	
0065	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	450	SY	
0066	6042000000-E	1632	1/4" HARDWARE CLOTH	175	LF	
0067	6071010000-E	SP	WATTLE	200	LF	
0068	6071020000-E	SP	POLYACRYLAMIDE (PAM)	64	LB	
0069	6071030000-E	SP	COIR FIBER BAFFLES	225	LF	
0070	6071050000-E	SP	*** SKIMMER (1-1/2")	4	EA	
0071	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0072	6087000000-E	1660	MOWING	1.5	ACR	
0073	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0074	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0075	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0077	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0078	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0079	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0080	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+21.00-L-)	Lump Sum	L.S.	
0081	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+21.00-L-)	Lump Sum	L.S.	
0082	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+21.00-L-)	Lump Sum	L.S.	
0083	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,870 SF		
0084	8161000000-E	420	GROOVING BRIDGE FLOORS	3,750 SF		
0085	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	47 CY		
0086	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+21.00-L-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,381 LB		
0088	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	468.08 LF		
0089	8364000000-E	450	HP12X53 STEEL PILES	175 LF		
0090	8503000000-E	460	CONCRETE BARRIER RAIL	236.55 LF		
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	522 TON		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	580 SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1428/Feb27/Q42468.43/D404119610000/E94			Total Amount Of Bid For Entire Project :			

Contract No **C202103**

County (ies): **Warren**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General