

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001010000-N	200	SELECT TREE REMOVAL	7 EA		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	111 TON		
0008	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	584 LF		
0009	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	144 LF		
0010	0974000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, (UNDER RR) (36", 0.500")	32 LF		
0011	0995000000-E	340	PIPE REMOVAL	201.3 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	270 SY		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,040 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	760 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	530 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	113 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	130 TON		
001E	2264000000-E	840	PIPE PLUGS	0.686 CY		
002C	2275000000-E	SP	FLOWABLE FILL	8.8 CY		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	21 EA		
0022	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	5.36 LF		
0023	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	2 EA		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	7 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	8 EA		
0027	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
002E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,580 LF		
002E	2591000000-E	848	4" CONCRETE SIDEWALK	320 SY		
003C	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	8 EA		
0031	2612000000-E	848	6" CONCRETE DRIVEWAY	136 SY		
0032	2830000000-N	858	ADJUSTMENT OF MANHOLES	4 EA		
0033	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0034	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	1	EA	
0037	3435000000-N	SP	GENERIC GUARDRAIL ITEM IMPACT ATTENUATOR UNIT, TYPE 350, TL-2	1	EA	
003E	3554000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, DOUBLE GATE (72")	2	EA	
003E	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (72", 8', 16' )	1	EA	
004C	3628000000-E	876	RIP RAP, CLASS I	12	TON	
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	794	SY	
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	353	SF	
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	165	SF	
004E	4430000000-N	1130	DRUMS	40	EA	
004E	4445000000-E	1145	BARRICADES (TYPE III)	112	LF	
0047	4455000000-N	1150	FLAGGER	180	MD	
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,014	LF	
004E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	464	LF	
005C	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	200	LF	
0051	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	272	LF	
0052	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	4	EA	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	20 EA		
0054	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	48 EA		
005E	5325600000-E	1510	6" WATER LINE	50 LF		
005E	5326000000-E	1510	10" WATER LINE	40 LF		
0057	5326200000-E	1510	12" WATER LINE	170 LF		
005E	5552000000-E	1515	10" VALVE	2 EA		
005E	5800000000-E	1530	ABANDON 6" UTILITY PIPE	40 LF		
006C	5802000000-E	1530	ABANDON 10" UTILITY PIPE	200 LF		
0061	5836000000-E	1540	24" ENCASEMENT PIPE	94 LF		
0062	5872200000-E	1550	TRENCHLESS INSTALLATION OF 24" IN SOIL	94 LF		
0063	6000000000-E	1605	TEMPORARY SILT FENCE	1,485 LF		
0064	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
006E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75 TON		
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	345 TON		
0067	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
007C	6029000000-E	SP	SAFETY FENCE	200 LF		
0071	6030000000-E	1630	SILT EXCAVATION	115 CY		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	960 SY		
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	480 LF		
0074	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
007E	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
007E	6087000000-E	1660	MOWING	0.5 ACR		
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
008C	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0081	6114000000-N	SP	SPECIALIZED HAND MOWING	0.5 HR		
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

---

**STRUCTURE ITEMS**


---

0083	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+68.00 -L-)	Lump Sum	L.S.	
0084	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	258.5 LF		
008E	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	4 LF		
008E	8113000000-N	SP	SID INSPECTION	4 EA		
0087	8115000000-N	SP	CROSSHOLE SONIC LOGGING	4 EA		
008E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (13+68.00 -L-)	Lump Sum	L.S.	

---

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	26.1 CY		
009C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	49.6 CY		
0091	8217000000-E	425	REINFORCING STEEL (BRIDGE)	40,741 LB		
009Z	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,069 LB		
009E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,854 LB		
0094	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	625 LF		
009E	8391000000-N	450	STEEL PILE POINTS	10 EA		
009E	8430000000-E	452	SHEET PILE RETAINING WALLS	4,100 SF		
0097	8482000000-E	460	THREE BAR METAL RAIL	104.604 LF		
009E	8594000000-E	876	RIP RAP, CLASS B	1 TON		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	80 TON		
010C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	60 SY		
0101	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
010Z	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	840 LF		
010E	8860000000-N	SP	GENERIC STRUCTURE ITEM END BENT DRAINAGE SYSTEM	Lump Sum	L.S.	

1606/Apr14/Q78586.45/D479540730000/E103

Total Amount Of Bid For Entire Project :

**Contract No**     **C202141**

**County (ies):**   **Henderson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General