

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+92.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	147 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	15 TON		
0007	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40 LF		
0008	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	68 LF		
0009	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0010	1121000000-E	520	AGGREGATE BASE COURSE	1,593 TON		
0011	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0012	1275000000-E	600	PRIME COAT	930 GAL		
0013	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	270 TON		
0014	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	260 TON		
0015	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	830 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
0017	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	50 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	1,350 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0031	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0032	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	787.5 LF		
0033	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0034	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6 EA		
0035	3649000000-E	876	RIP RAP, CLASS B	55 TON		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,015 SY		
0037	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	79 LF		
0039	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0040	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6 EA		
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	90 SF		
0042	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	100 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	56 SF		
0044	4430000000-N	1130	DRUMS	50 EA		
0045	4435000000-N	1135	CONES	25 EA		
0046	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
0047	4455000000-N	1150	FLAGGER	80 MD		
0048	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	70 EA		
0049	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,470 LF		
0050	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,470 LF		
0051	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	900 LF		
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,900 LF		
0053	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3 EA		
0054	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	13 EA		
0055	6000000000-E	1605	TEMPORARY SILT FENCE	3,820 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120 TON		
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	320 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	300 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	6.5 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.75 TON		
0062	6024000000-E	1622	TEMPORARY SLOPE DRAINS	430 LF		
0063	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	6 EA		
0064	6029000000-E	SP	SAFETY FENCE	500 LF		
0065	6030000000-E	1630	SILT EXCAVATION	1,100 CY		
0066	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,650 SY		
0067	6037000000-E	SP	COIR FIBER MAT	50 SY		
0068	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	160 SY		
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	70 LF		
0070	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0071	6071010000-E	SP	WATTLE	50 LF		
0072	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
0073	6071030000-E	SP	COIR FIBER BAFFLES	310 LF		
0074	6071050000-E	SP	*** SKIMMER (1-1/2")	7 EA		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6084000000-E	1660	SEEDING & MULCHING	15 ACR		
0076	6087000000-E	1660	MOWING	5.5 ACR		
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0078	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0079	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150 LB		
0080	6108000000-E	1665	FERTILIZER TOPDRESSING	4.5 TON		
0081	6114000000-N	SP	SPECIALIZED HAND MOWING	10 HR		
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0083	6123000000-E	1670	REFORESTATION	0.25 ACR		

***** BEGIN SCHEDULE AA *****
 ***** (2 ALTERNATES) *****

0084 AA1	0036000000-E	225	UNDERCUT EXCAVATION	600 CY		
0085 AA1	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	650 TON		
0086 AA1	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
*** OR ***						
0087 AA2	0036000000-E	225	UNDERCUT EXCAVATION	1,250 CY		
0088 AA2	0195000000-E	265	SELECT GRANULAR MATERIAL	1,250 CY		

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0089	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (14+92.00-L-)	Lump Sum	L.S.	
------	--------------	----	--	----------	------	--

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14+92.00-L-)	Lump Sum	L.S.	
0091	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+92.00-L-)	Lump Sum	L.S.	
0092	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	37.5 LF		
0093	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	26 LF		
0094	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	21 LF		
0095	8113000000-N	SP	SID INSPECTION	2 EA		
0096	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0097	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	564 CY		
0098	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	7,569 SF		
0099	8161000000-E	420	GROOVING BRIDGE FLOORS	8,055 SF		
0100	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	116.7 CY		
0101	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+92.00-L-)	Lump Sum	L.S.	
0102	8217000000-E	425	REINFORCING STEEL (BRIDGE)	24,362 LB		
0103	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,950 LB		
0104	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	853.85 LF		
0105	8364000000-E	450	HP12X53 STEEL PILES	440 LF		
0106	8503000000-E	460	CONCRETE BARRIER RAIL	346.45 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	500 TON		
0108	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	556 SY		
0109	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0110	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1033/Apr15/Q84150.75/D503558890000/E110			Total Amount Of Bid For Entire Project :			

Contract No **C202112**

County (ies): **Moore**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General