

County : Union, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	110 CY		
0003	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	30 TON		
0004	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	24 LF		
0005	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	20 LF		
0006	1220000000-E	545	INCIDENTAL STONE BASE	1,500 TON		
0007	1245000000-E	SP	SHOULDER RECONSTRUCTION	12 SMI		
0008	1264000000-E	SP	DITCHING	2,000 LF		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 4-1/2")	1,600 SY		
0010	1330000000-E	607	INCIDENTAL MILLING	516 SY		
0011	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	20 TON		
0012	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	17,570 TON		
0013	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	8,145 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	827 TON		
0015	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	489 TON		
0016	1704000000-E	SP	PATCHING EXISTING PAVEMENT	2,100 TON		
0017	2253000000-E	840	PIPE COLLARS	5.5 CY		

County : Union, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2612000000-E	848	6" CONCRETE DRIVEWAY	275 SY		
001E	2752000000-E	SP	GENERIC PAVING ITEM REMOVE & REPLACE 2'-6" CONC- RETE CURB & GUTTER	150 LF		
002C	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0021	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0022	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
002E	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, MOD)	4 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
002E	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
002E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	60,700 LF		
0027	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	59,050 LF		
002E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	300 LF		
002E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	200 LF		
003C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	2 EA		
0031	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	60,000 LF		
0032	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	385 EA		
003E	6000000000-E	1605	TEMPORARY SILT FENCE	425 LF		

County : Union, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	225 TON		
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	70 TON		
003E	6036000000-E	1631	MATTING FOR EROSION CONTROL	350 SY		
0037	6071010000-E	SP	WATTLE	750 LF		
003E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	5 LB		
003E	6084000000-E	1660	SEEDING & MULCHING	6 ACR		

1448/Mar31/Q218476.5/D119742130000/E39

Total Amount Of Bid For Entire Project :

Contract No **C202294**

County (ies): **Mecklenburg, Union**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General