



PROJECT SPECIAL PROVISIONS
Utility Construction

All proposed utility construction shall meet the applicable requirements of the NC Department of Transportation's "Standard Specifications for Roads and Structures" dated July 2006.

Page 15-1 Section 1500-2

Provide access for Department personnel and the owner's representatives to all phases of construction. Notify Department personnel and the utility owner two weeks prior to commencement of any work and one week prior to service interruption. Keep utility owner's representatives informed of work progress and provide opportunity for inspection of construction and testing. *The water and sewer lines on this project belong to the Town of Fuquay-Varina. The contact person for the Town of Fuquay-Varina is Mr. Tracy Stephenson, PE, and he can be reached by phone at 919-753-1039. Any work on these lines, especially operation of water valves, must be coordinated through the Engineer and the utility owner before beginning.*

Page 15-9 Section 1515-2

In addition to the water line materials specified under Section 1036, the water line can be High Density Polyethylene (HDPE) pipe conforming to AWWA C906 with an SDR of 9 and a pressure rating of 200 psi.

PROVIDED BY THE OWNER:

The Town of Fuquay-Varina will provide the Contractor with new fire hydrants for installation where utility construction plans call for "fire hydrant" or "relocate fire hydrant". The Contractor shall notify the owner's representative prior to removal or relocation of existing fire hydrants and arrange for the owner to take possession of the existing hydrant and remove it from the project site.

The connection to the existing water line will need to be made during the hours of 12:01 am to 5:00 am on a Saturday and be coordinated by the engineer and the contractor. The Contractor shall coordinate with the Town of Fuquay-Varina Public Utilities Staff, Town of Fuquay-Varina Fire Department, and Wake County Public Schools at least two weeks in advance of the connection switch over.

February 6, 2009

County: Wake
Project : B-4302

PROJECT SPECIAL PROVISIONS
Utility

UTILITIES BY OTHERS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) Progress Energy
- B) Time Warner Cable
- C) Embarq
- D) PSNC Energy

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be performed by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105-8 of the Standard Specifications for Roads and Structures.

Utilities Requiring Adjustments:

- A) Progress Energy Company
 - 1. See "Utilities By Others Plans" for utility conflicts
 - 2. Progress Energy will remain in place during the construction of the temporary detour. Once detour is complete Progress Energy will require two weeks notice and two weeks construction time to complete temporary installation. When the new bridge is complete Progress Energy will require two weeks notice and two weeks construction time to complete their construction to permanent location.

- B) Time Warner Cable
 - 1. See "Utilities By Others Plans" for utility conflicts

2. Time Warner will relocate on to Progress Energy's temporary and permanent pole locations. They will require two weeks notice and two weeks construction time from Progress Energy's completion time to complete temporary location work. Time Warner will need two weeks notice and two weeks construction time from Progress Energy's completion time to relocate to their permanent location.

C) Embarq

1. See "Utilities By Others Plans" for utility conflicts

D) PSNC Energy

1. See "Utilities By Others Plans" for utility conflicts