

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	75,000 LB		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	3.3 SMI		
0004	1891000000-E	SP	GENERIC PAVING ITEM MILLING CONCRETE BONDED OVER- LAY, 3" DEPTH	30,634 SY		
0005	1891000000-E	SP	GENERIC PAVING ITEM MILLING CONCRETE BONDED OVER- LAY, 4" DEPTH	68,679 SY		
0006	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	9,787 TON		
0007	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	10,916 TON		
0008	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	460 TON		
0009	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	655 TON		
0010	1567000000-E	SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28	323 TON		
0011	1839110000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE B	6,204 TON		
0012	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	127,248 SY		
0013	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	9,824 LF		
0014	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	375 SF		
0015	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	407 SF		
0016	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	15 SF		
0017	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	6 EA		
0019	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	14 DAY		
0020	4430000000-N	1130	DRUMS	410 EA		
0021	4445000000-E	1145	BARRICADES (TYPE III)	40 LF		
0022	4480000000-N	1165	TMIA	4 EA		
0023	4605000000-N	SP	GENERIC TRAFFIC CONTROL ITEM POLICE	2,000 HR		
0024	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	73,340 LF		
0025	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	22,376 LF		
0026	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	300 LF		
0027	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	7,950 LF		
0028	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	60 EA		
0029	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	43 EA		
0030	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	2,056 LF		
0031	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	43,428 LF		
0032	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	7,363 LF		
0033	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	44 EA		
0034	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	17 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	2,056 LF		
0036	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,527 EA		
0037	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0038	6084000000-E	1660	SEEDING & MULCHING	2.4 ACR		
0039	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	900 LF		

1012/May13/Q504471.7/D144579410000/E39

Total Amount Of Bid For Entire Project :

**Contract No**     **C202305**

**County (ies):**   **Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**