

PROJECT SPECIAL PROVISIONS  
Utility Construction

Revise the *2006 Standard Specifications* as follows:

Utility Owners' Contact Information:

**Page 15-1, Subarticle 1500-2, Cooperation with the Utility Owner**, paragraph 2, add the following sentence:

The Town of Windsor is owner of water and sewer facilities. The contact person is William Coburn (telephone: 252-794-3121).

Contractor shall provide Town of Windsor two weeks notice prior to proceeding with any work inside the Town's park property. Contractor shall provide Town of Windsor two weeks notice prior to disconnection of any existing sanitary sewer components and will coordinate work with Town for hookup and operation of new gravity and force main sewer system. The Town of Windsor is responsible for testing all components associated with the pump station prior to the Contractor making final connections for the force main and gravity sewer lines.

**Page 15-20, Subarticle 1530-3, Construction Requirements**, add the following subarticle:

Contractor shall submit to Owner a schedule indicating demolition and removal sequence of pump station and record drawings showing locations of capped utilities, subsurface obstructions and other pertinent items uncovered during demolition. Before demolition, contractor shall identify, disconnect, remove and cap designated utilities within demolition areas. Demolish in an orderly and careful manner. Demolition of structures shall include the complete removal of foundations two (2) feet below existing grade. Cap all pipes entering existing wetwell. Fill in wetwell with suitable fill and compact fill in lifts sufficient to maintain proper compaction.

The existing generator and pumps and lift station shall be turned over to Owner after removal from existing facility. The equipment shall be stored at a location on site as designated by Owner.

The quantity of sanitary sewer pump station removed, and accepted, will be measured and paid for at contract unit price per each for "Abandon Pump Station". Such price and payment will be full compensation for all labor, excavation, removal, stockpiling and incidentals necessary to complete work as required.

**Page 15-16, Subarticle 1520-4, Measurement and Payment,** add the following subarticle:

**Restoration of Town of Windsor park property**

Contractor will remove and replace all existing items within park property required for completion of sanitary sewer work as part of this contract. These items include, but are not limited to: 6' wood stockade fence, brick pavers, flag poles, flag pole foundations, flag pole lights, underground electric cables, shrubs, mulch, and turf. Contractor will also construct 12' wide access road as shown on Sheet UC-4. These items will be considered incidental to the installation of the gravity and force main sewer lines.

March 16, 2009

PROJECT: B-4434  
COUNTY: Bertie

PROJECT SPECIAL PROVISIONS  
Utility

UTILITIES BY OTHERS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A. Town of Windsor (Power)
- B. Town of Windsor (Water)
- C. Embarq (Telephone/Communications)
- D. Town of Windsor (Sewer)

The conflicting facilities will be adjusted prior to the date of availability except where noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A. Town of Windsor (Power)
  - 1. See "Utilities by Others Plans" for Utility Conflicts.
- B. Town of Windsor (Water)
  - 1. See "Utilities by Others Plans" for Utility Conflicts.
- C. Embarq (Telephone/Communications)
  - 1. See "Utilities by Others Plans" for Utility Conflicts.
- D. Town of Windsor (Sanitary Sewer)

All Sewer Piping and Components installed between and including both meter vault designated as "new meter vault" and manhole designated as "SSMH #1" as shown on sheet UC-4 will be installed by the Town of Windsor". See Sheet UC-4 for limits of Town of Windsor. All work will be done by the date of availability