

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (17+29.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	23 TON		
0010	0342000000-E	310	**" SIDE DRAIN PIPE (15")	156 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	36 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0014	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	600 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	330 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	48 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	11 EA		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3		EA
0020	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3		EA
0021	2556000000-E	846	SHOULDER BERM GUTTER	180		LF
0022	3030000000-E	862	STEEL BM GUARDRAIL	275		LF
0023	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25		LF
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0025	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1		EA
0026	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3		EA
0027	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4		EA
0028	3628000000-E	876	RIP RAP, CLASS I	5		TON
0029	3649000000-E	876	RIP RAP, CLASS B	195		TON
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	750		SY
0031	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	28		LF
0032	4102000000-N	904	SIGN ERECTION, TYPE E	2		EA
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	10		EA
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	341		SF
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94		SF
0036	4430000000-N	1130	DRUMS	10		EA
0037	4445000000-E	1145	BARRICADES (TYPE III)	96		LF

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,800	LF	
0039	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	30	EA	
0040	6000000000-E	1605	TEMPORARY SILT FENCE	880	LF	
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	190	TON	
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	140	TON	
0044	6015000000-E	1615	TEMPORARY MULCHING	5	ACR	
0045	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150	LB	
0046	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5	TON	
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50	LF	
0048	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1	EA	
0049	6029000000-E	SP	SAFETY FENCE	550	LF	
0050	6030000000-E	1630	SILT EXCAVATION	400	CY	
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,600	SY	
0052	6037000000-E	SP	COIR FIBER MAT	30	SY	
0053	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	760	SY	
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	460	LF	
0055	6071030000-E	SP	COIR FIBER BAFFLES	200	LF	
0056	6071050000-E	SP	**" SKIMMER (1-1/2")	4	EA	

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
0058	6087000000-E	1660	MOWING	2.5 ACR		
0059	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0060	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	2.75 TON		
0063	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0065	6123000000-E	1670	REFORESTATION	0.25 ACR		

STRUCTURE ITEMS

0066	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+29.50-L-)	Lump Sum	L.S.	
0067	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+29.50-L-)	Lump Sum	L.S.	
0068	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,683 SF		
0069	8161000000-E	420	GROOVING BRIDGE FLOORS	3,446 SF		
0070	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	56.1 CY		
0071	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+29.50-L-)	Lump Sum	L.S.	
0072	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,852 LB		
0073	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	137,500 LS		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8364000000-E	450	HP12X53 STEEL PILES	300 LF		
0075	8503000000-E	460	CONCRETE BARRIER RAIL	235.69 LF		
0076	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	462 TON		
0077	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	513 SY		
0078	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0079	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1611/May04/Q172729.04/D361975580000/E79			Total Amount Of Bid For Entire Project :			

Contract No C202126

County (ies): Granville

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General