

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	283 TON		
000E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,766 LF		
000E	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	658 LF		
0007	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	212 LF		
000E	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	8 LF		
000E	0995000000-E	340	PIPE REMOVAL	2,105 LF		
001C	1220000000-E	545	INCIDENTAL STONE BASE	540 TON		
0011	1330000000-E	607	INCIDENTAL MILLING	310 SY		
0012	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	5,050 TON		
0013	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	3,590 TON		
0014	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	6,235 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	386 TON		
001E	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	375 TON		
0017	2253000000-E	840	PIPE COLLARS	4 CY		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
001E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
002C	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0021	3649000000-E	876	RIP RAP, CLASS B	37 TON		
0022	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	104 SY		
0023	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0024	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	29,775 LF		
002E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	30,065 LF		
002E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	625 LF		
0027	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	100 LF		
002E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	140 LF		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	87 EA		
003C	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	900 LF		
0031	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	57,500 LF		
0032	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	800 LF		
0033	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	664 EA		
0034	6000000000-E	1605	TEMPORARY SILT FENCE	7,680 LF		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	440 TON		
0037	6012000000-E	1610	SEDIMENT CONTROL STONE	200 TON		
003E	6015000000-E	1615	TEMPORARY MULCHING	5.9 ACR		
003E	6036000000-E	1631	MATTING FOR EROSION CONTROL	16,340 SY		
004C	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,375 SY		
0041	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0042	6071010000-E	SP	WATTLE	730 LF		
0043	6071020000-E	SP	POLYACRYLAMIDE (PAM)	33 LB		
0044	6071030000-E	SP	COIR FIBER BAFFLES	800 LF		
004E	6084000000-E	1660	SEEDING & MULCHING	6.06 ACR		

1633/May04/Q170006.96/D154280160000/E45

Total Amount Of Bid For Entire Project :

Contract No **C202302**

County (ies): **Lee**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General