

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0003	0106000000-E	230	BORROW EXCAVATION	300 CY		
0004	1220000000-E	545	INCIDENTAL STONE BASE	600 TON		
0005	1243000000-E	SP	SHOULDER CONSTRUCTION	0.8 SMI		
0006	1245000000-E	SP	SHOULDER RECONSTRUCTION	17.99 SMI		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	274,248 SY		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	14,667 SY		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	10,285 SY		
0010	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 4")	1,250 SY		
0011	1330000000-E	607	INCIDENTAL MILLING	885 SY		
0012	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	622 TON		
0013	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	2,213 TON		
0014	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	39,505 TON		
0015	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	5,009 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	132 TON		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,696 TON		
001E	1704000000-E	SP	PATCHING EXISTING PAVEMENT	11,230 TON		
001E	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	4 EA		
002C	2830000000-N	858	ADJUSTMENT OF MANHOLES	86 EA		
0021	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	57 EA		
0022	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0023	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	154,415 LF		
0024	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	226,650 LF		
002E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,920 LF		
002E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	21,530 LF		
0027	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,722 LF		
002E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	52 EA		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	262 EA		
003C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	168,070 LF		
0031	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,112 LF		
0032	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3,661 EA		
003E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	264 EA		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0035	6000000000-E	1605	TEMPORARY SILT FENCE	1,600 LF		
0036	6084000000-E	1660	SEEDING & MULCHING	7.4 ACR		

1033/May13/Q946376.19/D104053100000/E36

Total Amount Of Bid For Entire Project :

Contract No **C202245**

County (ies): **Mecklenburg**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General