

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+21.87)	Lump Sum	L.S.	
0004	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (20+31.37)	Lump Sum	L.S.	
0005	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
0006	0043000000-N	226	GRADING	Lump Sum	L.S.	
0007	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	2 ACR		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	687 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	37 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	40 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	176 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	8 EA		
0015	0995000000-E	340	PIPE REMOVAL	57 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0017	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	75 SY		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,320 TON		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	940 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	119 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	150 TON		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	90 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	68 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	400 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	12 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0029	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3.1 LF		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	770 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	1,437.5 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0035	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0036	3628000000-E	876	RIP RAP, CLASS I	284 TON		
0037	3649000000-E	876	RIP RAP, CLASS B	8 TON		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,088 SY		
0039	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	81 LF		
0040	4102000000-N	904	SIGN ERECTION, TYPE E	9 EA		
0041	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	11 EA		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	428 SF		
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	208 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	219 SF		
0045	4430000000-N	1130	DRUMS	40 EA		
0046	4445000000-E	1145	BARRICADES (TYPE III)	128 LF		
0047	4455000000-N	1150	FLAGGER	16 MD		
0048	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	1,668 LF		
0049	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	16,072 LF		
0050	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	96 LF		
0051	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	40 EA		
0057	6000000000-E	1605	TEMPORARY SILT FENCE	3,980 LF		
0058	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	360 TON		
0059	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	515 TON		
0060	6012000000-E	1610	SEDIMENT CONTROL STONE	245 TON		
0061	6015000000-E	1615	TEMPORARY MULCHING	8.5 ACR		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0062	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0063	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3 TON		
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	865 LF		
0065	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7 EA		
0066	6030000000-E	1630	SILT EXCAVATION	1,090 CY		
0067	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,150 SY		
0068	6037000000-E	SP	COIR FIBER MAT	35 SY		
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	240 LF		
0070	6071030000-E	SP	COIR FIBER BAFFLES	600 LF		
0071	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0072	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
0073	6087000000-E	1660	MOWING	4.5 ACR		
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175 LB		
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	4.75 TON		
0078	6114000000-N	SP	SPECIALIZED HAND MOWING	10 HR		
0079	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	24 EA		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA *****						
***** ( 3 ALTERNATES ) *****						
0080 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	124 LF		
*** OR ***						
0081 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	68 LF		
0082 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	56 LF		
*** OR ***						
0083 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	68 LF		
0084 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	56 LF		
***** END SCHEDULE AA *****						
<b>STRUCTURE ITEMS</b>						
0085	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+21.87-L-)	Lump Sum	L.S.	
0086	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+31.37-L-)	Lump Sum	L.S.	
0087	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	202.7 LF		
0088	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	40.8 LF		
0089	8113000000-N	SP	SID INSPECTION	2 EA		
0090	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0091	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	4,978 CY		
0092	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	12,859 SF		
0093	8161000000-E	420	GROOVING BRIDGE FLOORS	11,482.8 SF		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	276.9 CY		
0095	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+21.87-L-)	Lump Sum	L.S.	
0096	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+31.37-L-)	Lump Sum	L.S.	
0097	8217000000-E	425	REINFORCING STEEL (BRIDGE)	60,031 LB		
0098	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	9,417 LB		
0099	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	632 LF		
0100	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	220,100 LS		
0101	8364000000-E	450	HP12X53 STEEL PILES	880 LF		
0102	8503000000-E	460	CONCRETE BARRIER RAIL	822.97 LF		
0103	8524000000-E	SP	*** CHAIN LINK FENCE (96")	798 LF		
0104	8531000000-E	462	4" SLOPE PROTECTION	2,163 SY		
0105	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0106	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0937/Jul08/Q367292.02/D439562760000/E101			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202154**

**County (ies):**   **Anson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General