

May 21, 2009

PROJECT: Y-4806AA
COUNTY: Cumberland

REVISED PROJECT SPECIAL PROVISIONS

Utilities

UTILITY CONFLICTS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A. Deltacom
- B. Piedmont Natural Gas
- C. Fayetteville Public Works Commission (Water & Sewer)
- D. Fayetteville Public Works Commission (Power)
- E. Embarq
- F. Time Warner
- G. Level 3
- H. MCI

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105-8 of the Standard Specifications.

Utilities requiring Adjustment:

A. Deltacom

- 1. See "Utilities by Others Plans" for utility conflicts.
- 2. New facilities have been installed and conflicting facilities abandoned.

B. Piedmont Natural Gas

- 1. See "Utilities by Others Plans" for utility conflicts.
- 2. All facilities in conflict have been lowered according to Piedmont Gas.
- 3. Service Connections will be adjusted during construction were required.

C. Fayetteville Public Works Commission (Water & Sewer)

1. See "Utilities by Others Plans" for existing utility locations.
2. All facilities will be adjusted/lowered by availability date.
3. Service laterals will be adjusted during construction were required.

D. Fayetteville Public Works Commission (Electrical)

1. See "Utilities by Others Plans" for new underground power locations.
2. New underground longitudinal power ducts will be installed by availability date.
3. After Level 3, Time Warner and Embarq have removed their aerial facilities, PWC will remove the poles. These poles should be removed by November 15, 2009.

E. Embarq

1. See "Utility by Others Plans" for existing utility locations.
2. All conflicting utilities will be adjusted my October 15, 2009.
3. Embarq's aerial cables will be replaced with buried cables inside the new underground conduit that is to be installed by PWC (Electrical). This work will be completed by October 31, 2009. Embarq's work will not interfere or delay the roadway contractor's work on this project. Embarq will bore all railroad crossings and will be responsible for securing the required permits from the railroads.

F. Time Warner

1. Time Warner will replace its aerial cable with new buried cable inside the new underground conduit that is to be installed by PWC (Electrical).
2. All work is to be completed by October 15, 2009.

G. Level 3

1. Level 3 will replace its aerial cable with buried cable inside the new underground conduit that is to be installed by PWC (Electrical).
2. All work is to be completed by October 15, 2009.

H. MCI

1. MCI has buried conduit crossing Line "L" at approximate Survey Station 25+40 that will remain in place.

**THIS
PAGE
INTENTIONALLY
LEFT
BLANK**