

County : Franklin, Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (17 + 46.50)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
000E	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
000E	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	10 TON		
001C	0343000000-E	310	15" SIDE DRAIN PIPE	44 LF		
0011	0995000000-E	340	PIPE REMOVAL	22 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	335 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	370 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
001E	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		

County : Franklin, Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
002C	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0021	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0022	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	42 LF		
0027	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
002E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003C	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0032	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
003E	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,110 SY		
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	75 LF		
003E	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		

County : Franklin, Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE ***** (GROUND MOUNTED) (E)	2	EA	
003E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8	EA	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	248	SF	
004C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119	SF	
0041	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0042	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	29,900	LF	
0043	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	96	EA	
0044	6000000000-E	1605	TEMPORARY SILT FENCE	800	LF	
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	125	TON	
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	175	TON	
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	350	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	3	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
005C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	160	LF	
0052	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0053	6029000000-E	SP	SAFETY FENCE	570	LF	
0054	6030000000-E	1630	SILT EXCAVATION	485	CY	

County : Franklin, Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000 SY		
005E	6037000000-E	SP	COIR FIBER MAT	550 SY		
0057	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	80 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	140 LF		
005E	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
006C	6071010000-E	SP	WATTLE	75 LF		
0061	6071020000-E	SP	POLYACRYLAMIDE (PAM)	27 LB		
0062	6071030000-E	SP	COIR FIBER BAFFLES	230 LF		
006E	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0064	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
006E	6087000000-E	1660	MOWING	1.5 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
007C	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0072	6123000000-E	1670	REFORESTATION	0.15 ACR		

County : Franklin, Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
0073 AA1	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (15") CLASS III	36 LF		
*** OR ***						
0074 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	36 LF		
*** OR ***						
0075 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	36 LF		
***** END SCHEDULE AA *****						
<b>STRUCTURE ITEMS</b>						
0076	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+46.50-L-)	Lump Sum	L.S.	
0077	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+46.50-L-)	Lump Sum	L.S.	
0078	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	63.5 LF		
0079	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	40 LF		
0080	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	66.3 LF		
0081	8113000000-N	SP	SID INSPECTION	1 EA		
0082	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+46.50-L-)	Lump Sum	L.S.	
0083	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	72.8 CY		
0084	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+46.50-L-)	Lump Sum	L.S.	

County : Franklin, Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	19,475 LB		
008E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,444 LB		
0087	8364000000-E	450	HP12X53 STEEL PILES	210 LF		
008E	8503000000-E	460	CONCRETE BARRIER RAIL	245.21 LF		
008E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	120 TON		
009C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	133 SY		
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0092	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,468 LF		

1045/Jul10/Q63142.46/D415018650000/E92

Total Amount Of Bid For Entire Project :

**Contract No**     **C202160**

**Counties:**       **Nash-Franklin**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General