

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+50.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	340 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	48 LF		
0013	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (12", 0.064")	100 LF		
0014	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	12 LF		
0015	0995000000-E	340	PIPE REMOVAL	112 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	570 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0018	1275000000-E	600	PRIME COAT	535 GAL		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1330000000-E	607	INCIDENTAL MILLING	50 SY		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	380 TON		
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	530 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	50 TON		
0023	2253000000-E	840	PIPE COLLARS	0.76 CY		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0025	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2 EA		
0026	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		
0027	3030000000-E	862	STEEL BM GUARDRAIL	550 LF		
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0029	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0030	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0031	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	387.5 LF		
0032	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III MODIFIED)	1 EA		
0033	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0034	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6 EA		
0035	3628000000-E	876	RIP RAP, CLASS I	20 TON		
0036	3649000000-E	876	RIP RAP, CLASS B	50 TON		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	375 SY		
0038	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	128 SF		
0040	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0042	4430000000-N	1130	DRUMS	20 EA		
0043	4435000000-N	1135	CONES	15 EA		
0044	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0045	4450000000-N	1150	FLAGGER	1,920 HR		
0046	4480000000-N	1165	TMIA	2 EA		
0047	4516000000-N	1180	SKINNY DRUM	15 EA		
0048	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	63 EA		
0049	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,350 LF		
0050	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,350 LF		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,528 LF		
0052	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,000 LF		
0053	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	11 EA		
0054	6000000000-E	1605	TEMPORARY SILT FENCE	1,000 LF		
0055	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	225 TON		
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		
0058	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0059	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0060	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
0061	6024000000-E	1622	TEMPORARY SLOPE DRAINS	75 LF		
0062	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0063	6029000000-E	SP	SAFETY FENCE	425 LF		
0064	6030000000-E	1630	SILT EXCAVATION	350 CY		
0065	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0066	6037000000-E	SP	COIR FIBER MAT	30 SY		
0067	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200 SY		
0068	6042000000-E	1632	1/4" HARDWARE CLOTH	225 LF		
0069	6071030000-E	SP	COIR FIBER BAFFLES	500 LF		
0070	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0071	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0072	6087000000-E	1660	MOWING	1.5 ACR		
0073	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0074	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0075	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0077	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0078	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0079	6123000000-E	1670	REFORESTATION	0.7 ACR		
STRUCTURE ITEMS						
0080	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (17+50.50-L-)	Lump Sum	L.S.	
0081	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+50.50-L-)	Lump Sum	L.S.	
0082	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	870 CY		
0083	8156000000-E	SP	CONCRETE WEARING SURFACE	3,631 SF		
0084	8161000000-E	420	GROOVING BRIDGE FLOORS	4,859 SF		
0085	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	63.7 CY		
0086	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+50.50-L-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	10,284 LB		
0088	8364000000-E	450	HP12X53 STEEL PILES	280 LF		
0089	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	450 LF		
0090	8503000000-E	460	CONCRETE BARRIER RAIL	204.8 LF		
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	273 TON		
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	310 SY		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0095	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,327.49 LF		
0917/Jul13/Q55711.95/D423210680000/E95			Total Amount Of Bid For Entire Project :			

Contract No **C202092**

County (ies): **Harnett**

**ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION**

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General