

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (19+73.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	700 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	421 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	480 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	135 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	52 LF		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	32 LF		
0014	0453000000-E	310	*** PIPE END SECTION (15")	1 EA		
0015	0995000000-E	340	PIPE REMOVAL	100 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0017	1330000000-E	607	INCIDENTAL MILLING	150 SY		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	780 TON		
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	700 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	620 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	104 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	5 EA		
0030	2209000000-E	838	ENDWALLS	3.4 CY		
0031	2264000000-E	840	PIPE PLUGS	0.569 CY		
0032	2275000000-E	SP	FLOWABLE FILL	12 CY		
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0034	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1 LF		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
0036	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	5 EA		
0037	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	800 LF		
0039	2591000000-E	848	4" CONCRETE SIDEWALK	400 SY		
0040	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	1 EA		
0041	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0042	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXT TRAFFIC BEARING JUNCTION BOX TO CATCH BASIN	5 EA		
0043	3030000000-E	862	STEEL BM GUARDRAIL	187.5 LF		
0044	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0045	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0046	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0047	3628000000-E	876	RIP RAP, CLASS I	132 TON		
0048	3649000000-E	876	RIP RAP, CLASS B	106 TON		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,315 SY		
0050	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	127 LF		
0051	4102000000-N	904	SIGN ERECTION, TYPE E	7 EA		
0052	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
0053	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	9 EA		
0054	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2 EA		
0055	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48 SF		
0056	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	77 SF		
0058	4430000000-N	1130	DRUMS	30 EA		
0059	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0060	4450000000-N	1150	FLAGGER	480 HR		
0061	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0062	4485000000-E	1170	PORTABLE CONCRETE BARRIER	351 LF		
0063	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	249 LF		
0064	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	30 EA		
0065	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,915 LF		
0066	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,087 LF		
0067	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	180 LF		
0068	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	26,400 LF		
0069	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	300 LF		
0070	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	35 EA		
0071	5325800000-E	1510	8" WATER LINE	61 LF		
0072	5571800000-E	1515	8" TAPPING VALVE	1 EA		
0073	5648000000-N	1515	RELOCATE WATER METER	3 EA		
0074	5691200000-E	1520	6" SANITARY GRAVITY SEWER	112 LF		
0075	5691300000-E	1520	8" SANITARY GRAVITY SEWER	388 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	5692000000-E	1520	30" SANITARY GRAVITY SEWER	131		LF
0077	5775000000-E	1525	4' DIA UTILITY MANHOLE	3		EA
0078	5777000000-E	1525	6' DIA UTILITY MANHOLE	2		EA
0079	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	28		LF
0080	5783000000-E	1525	UTILITY MANHOLE WALL, 6' DIA	18		LF
0081	5801000000-E	1530	ABANDON 8" UTILITY PIPE	320		LF
0082	5814000000-E	1530	ABANDON 30" UTILITY PIPE	136		LF
0083	5828000000-N	1530	REMOVE UTILITY MANHOLE	2		EA
0084	5835000000-E	1540	*** ENCASEMENT PIPE (54")	56		LF
0085	5835800000-E	1540	18" ENCASEMENT PIPE	107		LF
0086	5871000000-E	1550	TRENCHLESS INSTALLATION OF *** IN SOIL (54")	28		LF
0087	5871010000-E	1550	TRENCHLESS INSTALLATION OF *** NOT IN SOIL (54")	28		LF
0088	5872000000-E	1550	TRENCHLESS INSTALLATION OF 18" IN SOIL	54		LF
0089	5872010000-E	1550	TRENCHLESS INSTALLATION OF 18" NOT IN SOIL	54		LF
0090	6000000000-E	1605	TEMPORARY SILT FENCE	450		LF
0091	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225		TON
0092	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	550		TON
0093	6012000000-E	1610	SEDIMENT CONTROL STONE	650		TON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0095	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0096	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0097	6024000000-E	1622	TEMPORARY SLOPE DRAINS	60 LF		
0098	6029000000-E	SP	SAFETY FENCE	500 LF		
0099	6030000000-E	1630	SILT EXCAVATION	1,600 CY		
0100	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500 SY		
0101	6037000000-E	SP	COIR FIBER MAT	25 SY		
0102	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,250 SY		
0103	6042000000-E	1632	1/4" HARDWARE CLOTH	225 LF		
0104	6070000000-N	SP	SPECIAL STILLING BASINS	20 EA		
0105	6071010000-E	SP	WATTLE	160 LF		
0106	6071020000-E	SP	POLYACRYLAMIDE (PAM)	59 LB		
0107	6071030000-E	SP	COIR FIBER BAFFLES	475 LF		
0108	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0109	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0110	6087000000-E	1660	MOWING	1 ACR		
0111	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0112	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0113	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0114	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0115	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0116	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0117	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	564 LF		
0118	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	336 LF		
*** OR ***						
0119	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	444 LF		
0120	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	300 LF		
0121	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	120 LF		
0122	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	36 LF		
*** OR ***						
0123	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	444 LF		
0124	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	300 LF		
0125	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	120 LF		
0126	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (36", 0.079")	36 LF		

***** END SCHEDULE AA *****

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0127	803500000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+72.50-L-)	Lump Sum	L.S.	
0128	809600000-E	SP	PILE EXCAVATION IN SOIL	100 LF		
0129	809700000-E	SP	PILE EXCAVATION NOT IN SOIL	35 LF		
0130	810552000-E	SP	3'-0" DIA DRILLED PIERS IN SOIL	79.67 LF		
0131	810562000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	100 LF		
0132	811120000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	79.38 LF		
0133	811300000-N	SP	SID INSPECTION	1 EA		
0134	811500000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0135	812100000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (19+72.50-L-)	Lump Sum	L.S.	
0136	815600000-E	SP	CONCRETE WEARING SURFACE	4,795 SF		
0137	816100000-E	420	GROOVING BRIDGE FLOORS	5,983 SF		
0138	817500000-E	420	CLASS AA CONCRETE (BRIDGE)	31.8 CY		
0139	818200000-E	420	CLASS A CONCRETE (BRIDGE)	115.9 CY		
0140	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+72.50-L-)	Lump Sum	L.S.	
0141	821700000-E	425	REINFORCING STEEL (BRIDGE)	31,925 LB		
0142	822400000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,324 LB		
0143	823800000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,420 LB		
0144	836400000-E	450	HP12X53 STEEL PILES	270 LF		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0145	8391000000-N	450	STEEL PILE POINTS	18 EA		
0146	8475000000-E	460	TWO BAR METAL RAIL	169.71 LF		
0147	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 3'-8")	185.34 LF		
0148	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	329 TON		
0149	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	366 SY		
0150	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0151	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0152	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,848.33 LF		
1032/Jul13/Q108545.799/D670495570000/E152			Total Amount Of Bid For Entire Project :			

Contract No **C201969**

County (ies): **Mecklenburg**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General