

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0199000000-E	SP	TEMPORARY SHORING	585 SF		
0003	0248000000-N	SP	GENERIC GRADING ITEM EXCAVATION & EMBANKMENT BRIDGE #31	Lump Sum	L.S.	
0004	0248000000-N	SP	GENERIC GRADING ITEM EXCAVATION & EMBANKMENT BRIDGE #35	Lump Sum	L.S.	
0005	0248000000-N	SP	GENERIC GRADING ITEM EXCAVATION & EMBANKMENT BRIDGE #40	Lump Sum	L.S.	
0006	0248000000-N	SP	GENERIC GRADING ITEM EXCAVATION & EMBANKMENT BRIDGE #42	Lump Sum	L.S.	
0007	0248000000-N	SP	GENERIC GRADING ITEM EXCAVATION & EMBANKMENT BRIDGE #44	Lump Sum	L.S.	
0008	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	710 TON		
0009	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	550 TON		
0010	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,240 TON		
0011	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	140 TON		
0012	2556000000-E	846	SHOULDER BERM GUTTER	87 LF		
0013	2570000000-N	SP	MODIFIED CONCRETE FLUME	8 EA		
0014	3030000000-E	862	STEEL BM GUARDRAIL	1,350 LF		
0015	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0016	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	20 EA		
0018	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	13 EA		
0019	3649000000-E	876	RIP RAP, CLASS B	1.4 TON		
0020	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0021	6000000000-E	1605	TEMPORARY SILT FENCE	5,500 LF		
0022	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	255 TON		
0023	6012000000-E	1610	SEDIMENT CONTROL STONE	225 TON		
0024	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0025	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0026	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0027	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,070 LF		
0028	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	20 EA		
0029	6029000000-E	SP	SAFETY FENCE	6,204 LF		
0030	6030000000-E	1630	SILT EXCAVATION	90 CY		
0031	6036000000-E	1631	MATTING FOR EROSION CONTROL	525 SY		
0032	6042000000-E	1632	1/4" HARDWARE CLOTH	465 LF		
0033	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	530 SY		
0034	6071010000-E	SP	WATTLE	65 LF		
0035	6071020000-E	SP	POLYACRYLAMIDE (PAM)	23 LB		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6084000000-E	1660	SEEDING & MULCHING	2.5	ACR	
0037	6090000000-E	1661	SEED FOR REPAIR SEEDING	250	LB	
0038	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.25	TON	
0039	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	250	LB	
0040	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
0041	6123000000-E	1670	REFORESTATION	0.5	ACR	
0064	0220000000-E	SP	ROCK EMBANKMENTS	50	TON	

STRUCTURE ITEMS

0042	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+29.77-L-)	Lump Sum	L.S.	
0043	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+56.00-L-)	Lump Sum	L.S.	
0044	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+65.09-L-)	Lump Sum	L.S.	
0045	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+69.00-L-)	Lump Sum	L.S.	
0046	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+05.00-L-)	Lump Sum	L.S.	
0047	8112730000-N	SP	PDA TESTING	9	EA	
0048	8112740000-N	SP	PDA ASSISTANCE	9	EA	
0049	8336000000-E	450	20" PRESTRESSED CONC PILES	3,325	LF	
0050	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	5,145	LF	

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0051	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,010 TON		
0052	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,135 SY		
0053	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUBSTRUCTURE AT STA 15+29.77-L-(BR#35)	Lump Sum	L.S.	
0054	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUBSTRUCTURE AT STA 15+56.00-L-(BR#40)	Lump Sum	L.S.	
0055	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUBSTRUCTURE AT STA 15+65.09-L-(BR#42)	Lump Sum	L.S.	
0056	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUBSTRUCTURE AT STA 15+69.00-L-(BR#31)	Lump Sum	L.S.	
0057	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUBSTRUCTURE AT STA 16+05.00-L-(BR#44)	Lump Sum	L.S.	
0058	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUPERSTRUCTURE AT ST A 15+29.77-L-(BR#35)	Lump Sum	L.S.	
0059	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUPERSTRUCTURE AT ST A 15+56.00-L-(BR#40)	Lump Sum	L.S.	
0060	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUPERSTRUCTURE AT ST A 15+65.09-L-(BR#42)	Lump Sum	L.S.	
0061	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUPERSTRUCTURE AT ST A 15+69.00-L-(BR#31)	Lump Sum	L.S.	
0062	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTR OF SUPERSTRUCTURE AT ST A 16+05.00-L-(BR#44)	Lump Sum	L.S.	

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0063	8867000000-E	SP	GENERIC STRUCTURE ITEM 16" COMPOSITE PRESTRESSED CONCRETE PILES	700 LF		

1021/Aug07/Q31880.15/D351689600000/E64

Total Amount Of Bid For Entire Project :

Contract No **C202322**

County (ies): **Pamlico**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General