

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1110000000-E	510	STABILIZER AGGREGATE	1,302 TON		
0003	1220000000-E	545	INCIDENTAL STONE BASE	667 TON		
0004	1243000000-E	SP	SHOULDER CONSTRUCTION	1.7 SMI		
0005	1245000000-E	SP	SHOULDER RECONSTRUCTION	26.2 SMI		
0006	1264000000-E	SP	DITCHING	2,097 LF		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	25,300 SY		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (5-1/2")	17,400 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	550 SY		
0010	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	590 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	5,804 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,800 TON		
0013	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	2,123 TON		
0014	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	13,085 TON		
0015	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	2,590 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	921 TON		
0017	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	954 TON		
0018	1704000000-E	SP	PATCHING EXISTING PAVEMENT	6,465 TON		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2612000000-E	848	6" CONCRETE DRIVEWAY	90 SY		
0020	2752000000-E	SP	GENERIC PAVING ITEM CONCRETE JOINT TREATMENT	4,000 LF		
0021	2830000000-N	858	ADJUSTMENT OF MANHOLES	13 EA		
0022	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	24 EA		
0023	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	150,932 LF		
0024	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	163,338 LF		
0025	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,066 LF		
0026	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	424 LF		
0027	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	21 EA		
0028	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	8 EA		
0029	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	20,000 LF		
0030	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	2,204 EA		
0031	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0032	6000000000-E	1605	TEMPORARY SILT FENCE	2,240 LF		
0033	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	295 TON		
0034	6012000000-E	1610	SEDIMENT CONTROL STONE	149 TON		
0035	6084000000-E	1660	SEEDING & MULCHING	13.7 ACR		

Contract No **C202413**

County (ies): **Union**

**ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION**

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General