

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	108 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	4.37 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	21,558 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	7,211 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	43,029 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2-1/2")	17,673 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	588 SY		
0009	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,233 TON		
0010	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	15,251 TON		
0011	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	2,851 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,157 TON		
0013	1704000000-E	SP	PATCHING EXISTING PAVEMENT	160 TON		
0014	1775000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	143,314 SY		
0015	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	82 EA		
0016	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	7 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	2815000000-N	858	ADJUSTMENT OF DROP INLETS	2 EA		
001E	2830000000-N	858	ADJUSTMENT OF MANHOLES	151 EA		
001S	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	125 EA		
002C	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0021	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	30,411 LF		
0022	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	63,166 LF		
0023	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	308 LF		
0024	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	440 LF		
002E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	7,008 LF		
0026	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	226 LF		
0027	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,938 LF		
002E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	46 EA		
002S	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	271 EA		
003C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,000 LF		
0031	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	800 LF		
0032	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0033	6084000000-E	1660	SEEDING & MULCHING	0.2 ACR		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	6110000000-E	SP	RESIDENTIAL SEEDING	1.39	ACR	
003E	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	60	LF	
003E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	520	LF	
0037	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	50	EA	
003E	7420000000-E	1722	2" RISER WITH WEATHERHEAD	38	EA	
003E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	10,630	LF	
004C	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	2,690	LF	

0755/Aug03/Q380110.96/D150510100000/E40

Total Amount Of Bid For Entire Project :

Contract No **C202416**

County (ies): **Alamance**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General