

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (25+43.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	24,500 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	250 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	51 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	112 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	128 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	40 LF		
0015	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	76 LF		
0016	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (15", 0.064")	40 LF		
0017	0564000000-E	310	*** CAA PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0018	0986000000-E	SP	GENERIC PIPE ITEM 16" DI PIPE	48 LF		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0995000000-E	340	PIPE REMOVAL	150 LF		
0020	1121000000-E	520	AGGREGATE BASE COURSE	190 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0022	1275000000-E	600	PRIME COAT	1,260 GAL		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,160 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	710 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	950 TON		
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	145 TON		
0027	2253000000-E	840	PIPE COLLARS	2 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	185 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	1,150 LF		
0032	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0037	3649000000-E	876	RIP RAP, CLASS B	15 TON		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	260 SY		
0039	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	44 LF		
0040	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0041	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	5 EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6 EA		
0043	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	526 SF		
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0046	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0047	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,400 LF		
0048	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,400 LF		
0049	4880000000-E	1205	CURING COMPOUND REMOVAL, LINES	572 LF		
0050	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	4 EA		
0051	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	20 EA		
0052	5325600000-E	1510	6" WATER LINE	12 LF		
0053	5540000000-E	1515	6" VALVE	1 EA		
0054	5648000000-N	1515	RELOCATE WATER METER	4 EA		
0055	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0056	5800000000-E	1530	ABANDON 6" UTILITY PIPE	208 LF		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6000000000-E	1605	TEMPORARY SILT FENCE	2,950 LF		
0058	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
0059	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	615 TON		
0060	6012000000-E	1610	SEDIMENT CONTROL STONE	260 TON		
0061	6015000000-E	1615	TEMPORARY MULCHING	6.5 ACR		
0062	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0063	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0065	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0066	6030000000-E	1630	SILT EXCAVATION	710 CY		
0067	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,900 SY		
0068	6042000000-E	1632	1/4" HARDWARE CLOTH	155 LF		
0069	6071010000-E	SP	WATTLE	110 LF		
0070	6071020000-E	SP	POLYACRYLAMIDE (PAM)	41 LB		
0071	6071030000-E	SP	COIR FIBER BAFFLES	360 LF		
0072	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
0073	6087000000-E	1660	MOWING	3.5 ACR		
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150 LB		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	4.25 TON		
0078	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0079	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
<b>WALL ITEMS</b>						
0080	8801000000-E	SP	MSE RETAINING WALLS	2,245 SF		
<b>STRUCTURE ITEMS</b>						
0081	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24+44.64-L-)	Lump Sum	L.S.	
0082	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (24+44.64-L-)	Lump Sum	L.S.	
0083	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,667 SF		
0084	8161000000-E	420	GROOVING BRIDGE FLOORS	4,466 SF		
0085	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	58.2 CY		
0086	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (24+44.64-L-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,822 LB		
0088	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	179,400 LS		
0089	8364000000-E	450	HP12X53 STEEL PILES	900 LF		
0090	8503000000-E	460	CONCRETE BARRIER RAIL	280.73 LF		
0091	8531000000-E	462	4" SLOPE PROTECTION	30 SY		

County : Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	212 SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0095	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (24+44.64-L-)	Lump Sum	L.S.	
0901/Aug14/Q253378.18/D410594260000/E95			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202153**

**County (ies):**   **Harnett**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**