

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1243000000-E	SP	SHOULDER CONSTRUCTION	18.1	SMI	
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	100,000	SY	
0004	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	18,700	TON	
0005	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	90,000	TON	
0006	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	879	TON	
0007	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	5,400	TON	
0008	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	191,136	LF	
0009	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	600	SF	
0010	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0011	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
0012	4430000000-N	1130	DRUMS	300	EA	
0013	4480000000-N	1165	TMIA	2	EA	
0014	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	191,136	LF	
0015	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	23,892	LF	
0016	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	3,000	LF	
0017	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	18	EA	

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	274,758	LF	
001S	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	18	EA	
002C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,358	EA	
0021	6084000000-E	1660	SEEDING & MULCHING	13.2	ACR	
1109/Oct08/Q901233.3/D7212810000/E21			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202486**

**County (ies):**   **WAYNE**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General