



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

October 9, 2009

Addendum No. 1

RE: Contract ID: C202446

WBS# 45225.3.ST1

F.A. # STM-0264(43)

Wilson County (R-5191)

US-264 From The Pavement Joint East Of NC-58 To
The Greene County Line

October 20, 2009 Letting

To Whom It May Concern:

Reference is made to the sketch maps and proposal form recently furnished to you on this project.

The following revisions have been made to the Sketch Maps:

On Sheet No. 3 the Summary of Quantities has been revised to add a column for Seeding and Mulching.

The following revisions have been made to the proposal:

On Page No. 1 the project special provision entitled "Specialty Items" has been revised. Please void Page No. 1 in your proposal and staple the revised Page No. 1 thereto.

On Page No. 20 the project special provision entitled "Shoulder Construction" has been revised. Please void Page No. 20 in your proposal and staple the revised Page No. 20 thereto.

MAILING ADDRESS:

NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128

FAX: 919-250-4119

WEBSITE: WWW.NCDOT.ORG

LOCATION:

CENTURY CENTER COMPLEX
ENTRANCE B-2
1020 BIRCH RIDGE DRIVE
RALEIGH NC 27610


On Page No. 2 of the item sheets by copy of this addendum the following pay item is hereby added:

<u>Item</u>	<u>Description</u>	<u>Quantity</u>
22-6084000000-E- 1660	Seeding and Mulching	20 ACR

The Contractor's bid must include this new pay item. The contract will be prepared accordingly.

The Expedite File has been updated to reflect this revision. Please download the Expedite Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,



R. A. Garris, PE
Contract Officer

RAG/jag
Attachments

cc: Mr. J. G. Nance, PE
Mr. Ron Hancock, PE
Mr. R. E. Greene, PE
Ms. D. M. Barbour, PE
Mr. J. V. Barbour, PE
Mr. Larry Strickland
Ms. Lori Strickland
Project File (2)

Mr. R. E. Davenport, Jr., PE
Ms. Marsha Sample
Ms. Norma Smith
Mr. Ronnie Higgins
Ms. Penny Higgins
Ms. Jaci Kincaid

PROJECT SPECIAL PROVISIONS

GENERAL

CONTRACT TIME AND LIQUIDATED DAMAGES:

(7-1-95)(Rev. 12-18-07)

RG 10

The date of availability for this contract is **November 30, 2009**.

The completion date for this contract is **November 1, 2010**.

Except where otherwise provided by the contract, observation periods required by the contract will not be a part of the work to be completed by the completion date and/or intermediate contract times stated in the contract. The acceptable completion of the observation periods that extend beyond the final completion date shall be a part of the work covered by the performance and payment bonds.

The liquidated damages for this contract are **Eight Hundred Dollars (\$800.00)** per calendar day.

RAILROAD GRADE CROSSING:

(7-1-95)

RG 17

The Contractor's attention is directed that should the use of slow moving or stopped equipment be required at railroad grade crossings, notify the railroad's local representative of their anticipated time of work at the grade crossing at least 48 hours prior to performing work in that grade crossing location.

MAJOR CONTRACT ITEMS:

(2-19-02)

RG 28

The following listed items are the major contract items for this contract (See Articles 101 and 104-5 of the *2006 Standard Specifications*):

Line #	Description
4	Asphalt Concrete Intermediate Course, Type I19.0B
5	Asphalt Concrete Surface Course, Type S9.5B
9	Open-Graded Asphalt Friction Course, Type FC-2 Modified

SPECIALTY ITEMS:

(7-1-95)

RG 37

Items listed below will be the specialty items for this contract (See Article 108-6 of the *2006 Standard Specifications*).

Line #	Description
17 and 19 thru 20	Long-Life Pavement Markings
21	Permanent Pavement Markers
22	Erosion Control

PROJECT SPECIAL PROVISIONS

ROADWAY

SHOULDER CONSTRUCTION:

(12-21-99) (Rev.7-18-06)

RI R04

Description

The work covered by this provision consists of performing shoulder construction in accordance with Section 560 of the 2006 Standard Specifications and the details of this provision. Construction of a new shoulder is required due to widening of the existing paved shoulder and resurfacing on the existing roadway. Place earth material along the completed edge of pavement and construct shoulders as shown on the sketch map and/or as directed by the Engineer. Backfill and compact the area to the satisfaction of the Engineer. Perform this work immediately after the resurfacing operations are completed as directed by the Engineer.

Materials

Use all suitable material generated from the widening operation to construct the shoulders. Furnish any other earth material necessary for the construction of the shoulders. Provide earth material meeting the approval of the Engineer. No testing will be necessary.

Measurement and Payment

Shoulder Construction will be measured and paid for as the actual number of shoulder miles that have been constructed. Measurement will be made along the surface of each shoulder and to the nearest 0.01 of a mile. Such price and payment will be full compensation for furnishing earth material, hauling, placing, compaction, and all incidentals necessary to complete construction of the shoulders. **Seeding and Mulching will be paid for as provided elsewhere in this contract.**

Payment will be made under:

Pay Item	Pay Unit
Shoulder Construction	Shoulder Mile

ASPHALT PAVEMENTS - SUPERPAVE:

(7-18-06)(Rev 10-20-09)

RR6R01

Revise the 2006 Standard Specifications as follows:

Page 6-2, Article 600-9 Measurement and Payment, delete the second paragraph.

Page 6-12, Subarticle 609-5(C)2, Required Sampling and Testing Frequencies, first partial paragraph at the top of the page, delete last sentence and add the following:

If the Engineer allows the mix to remain in place, payment will be made in accordance with Article 105-3.