

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1110000000-E	510	STABILIZER AGGREGATE	375	TON	
0003	1220000000-E	545	INCIDENTAL STONE BASE	333	TON	
0004	1243000000-E	SP	SHOULDER CONSTRUCTION	4.6	SMI	
000E	1245000000-E	SP	SHOULDER RECONSTRUCTION	5	SMI	
000E	1264000000-E	SP	DITCHING	1,065	LF	
0007	1330000000-E	607	INCIDENTAL MILLING	120	SY	
000E	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,675	TON	
000E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,670	TON	
001C	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	1,760	TON	
0011	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	570	TON	
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,875	TON	
0013	2612000000-E	848	6" CONCRETE DRIVEWAY	162	SY	
0014	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	51,148	LF	
001E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	46,920	LF	
001E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	24,748	LF	
0017	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	320	EA	
001E	6000000000-E	1605	TEMPORARY SILT FENCE	1,155	LF	

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120 TON		
002C	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
0021	6084000000-E	1660	SEEDING & MULCHING	5.4 ACR		
1552/Aug27/Q139092.0/D61004100000/E21			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202443**

**County (ies):**    **Union**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General