

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (49+65.00-L-)	Lump Sum	L.S.	
0005	0036000000-E	225	UNDERCUT EXCAVATION	1,900 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	9,600 CY		
0007	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,200 SY		
0008	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	700 SY		
0009	0192000000-N	260	PROOF ROLLING	10 HR		
0010	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	400 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	220 TON		
0013	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	670 SY		
0014	0344000000-E	310	18" SIDE DRAIN PIPE	140 LF		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	228 LF		
0016	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	232 LF		
0017	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	360 LF		
0018	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	100 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	116 LF		
0020	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	4 EA		
0021	0986000000-E	SP	GENERIC PIPE ITEM 16" DUCTILE IRON PIPE	72 LF		
0022	0995000000-E	340	PIPE REMOVAL	152 LF		
0023	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0024	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0025	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0026	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	5,100 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	6,150 TON		
0028	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	110 TON		
0029	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	55 TON		
0030	2000000000-N	806	RIGHT OF WAY MARKERS	63 EA		
0031	2022000000-E	815	SUBDRAIN EXCAVATION	67.2 CY		
0032	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0034	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0035	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0036	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0037	2209000000-E	838	ENDWALLS	13 CY		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2275000000-E	SP	FLOWABLE FILL	20 CY		
0039	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0040	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		
0041	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	3 EA		
0042	2462000000-E	SP	*** SLUIICE GATE (25")	2 EA		
0043	2473000000-N	SP	GENERIC DRAINAGE ITEM BICYCLE SAFE STEEL GRATE AND FRAME	4 EA		
0044	2474000000-N	SP	GENERIC DRAINAGE ITEM HAZARDOUS SPILL BASIN	Lump Sum	L.S.	
0045	2556000000-E	846	SHOULDER BERM GUTTER	210 LF		
0046	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	260 SY		
0047	3030000000-E	862	STEEL BM GUARDRAIL	3,212.5 LF		
0048	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	125 LF		
0049	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0050	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0051	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0052	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0053	3628000000-E	876	RIP RAP, CLASS I	35 TON		
0054	3649000000-E	876	RIP RAP, CLASS B	525 TON		
0055	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,960 SY		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	851 LF		
0057	4096000000-N	904	SIGN ERECTION, TYPE D	6 EA		
0058	4102000000-N	904	SIGN ERECTION, TYPE E	48 EA		
0059	4108000000-N	904	SIGN ERECTION, TYPE F	11 EA		
0060	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	2 EA		
0061	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	306 SF		
0062	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	288 SF		
0063	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	117 SF		
0064	4430000000-N	1130	DRUMS	50 EA		
0065	4445000000-E	1145	BARRICADES (TYPE III)	120 LF		
0066	4450000000-N	1150	FLAGGER	320 HR		
0067	4510000000-N	SP	LAW ENFORCEMENT	40 HR		
0068	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	30 EA		
0069	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	40 LF		
0070	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	14 EA		
0071	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	80,650 LF		
0072	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	60 LF		
0073	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	20 EA		
0074	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	39,888 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6000000000-E	1605	TEMPORARY SILT FENCE	13,000 LF		
0076	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,180 TON		
0077	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,810 TON		
0078	6012000000-E	1610	SEDIMENT CONTROL STONE	885 TON		
0079	6015000000-E	1615	TEMPORARY MULCHING	58 ACR		
0080	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,100 LB		
0081	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	5.25 TON		
0082	6024000000-E	1622	TEMPORARY SLOPE DRAINS	10,030 LF		
0083	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	29 EA		
0084	6029000000-E	SP	SAFETY FENCE	2,340 LF		
0085	6030000000-E	1630	SILT EXCAVATION	9,230 CY		
0086	6036000000-E	1631	MATTING FOR EROSION CONTROL	12,000 SY		
0087	6037000000-E	SP	COIR FIBER MAT	90 SY		
0088	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	400 SY		
0089	6042000000-E	1632	1/4" HARDWARE CLOTH	550 LF		
0090	6071010000-E	SP	WATTLE	230 LF		
0091	6071020000-E	SP	POLYACRYLAMIDE (PAM)	114 LB		
0092	6071030000-E	SP	COIR FIBER BAFFLES	2,470 LF		
0093	6071050000-E	SP	*** SKIMMER (1-1/2")	9 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0095	6084000000-E	1660	SEEDING & MULCHING	45 ACR		
0096	6087000000-E	1660	MOWING	49.5 ACR		
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	450 LB		
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.75 TON		
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,000 LB		
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	29.75 TON		
0101	6114500000-N	SP	SPECIALIZED HAND MOWING	100 MHR		
0102	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
0103	6123000000-E	1670	REFORESTATION	0.1 ACR		
0104	6129000000-E	1670	WETLAND REFORESTATION	0.864 ACR		
0105	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	0.864 ACR		
0106	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	0.864 ACR		
0107	6138000000-E	SP	GENERIC EROSION CONTROL ITEM BORROW PIT DEWATERING BASIN	1,500 CY		

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
 \*\*\*\*\* ( 2 ALTERNATES ) \*\*\*\*\*

0108	0022000000-E	225	UNCLASSIFIED EXCAVATION	28,300 CY		
<b>AA1</b>						
0109	0106000000-E	230	BORROW EXCAVATION	177,700 CY		
<b>AA1</b>						
0110	1121000000-E	520	AGGREGATE BASE COURSE	14,000 TON		
<b>AA1</b>						
0111	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,400 TON		
<b>AA1</b>						

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0112 AA1	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	763 TON		
*** OR ***						
0113 AA2	0022000000-E	225	UNCLASSIFIED EXCAVATION	27,100 CY		
0114 AA2	0106000000-E	230	BORROW EXCAVATION	180,700 CY		
0115 AA2	1121000000-E	520	AGGREGATE BASE COURSE	400 TON		
0116 AA2	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	10,100 TON		
0117 AA2	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,051 TON		
***** END SCHEDULE AA *****						
***** BEGIN SCHEDULE AB ***** ( 3 ALTERNATES ) *****						
0118 AB1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	736 LF		
*** OR ***						
0119 AB2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	580 LF		
0120 AB2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	156 LF		
*** OR ***						
0121 AB3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	580 LF		
0122 AB3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	156 LF		
***** END SCHEDULE AB *****						
<b>STRUCTURE ITEMS</b>						
0123	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (49+65.00-L-)	Lump Sum	L.S.	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (7, 49+65.00-L-)	Lump Sum	L.S.	
0125	8112730000-N	SP	PDA TESTING	2 EA		
0126	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0127	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	59,424 SF		
0128	8161000000-E	420	GROOVING BRIDGE FLOORS	52,380 SF		
0129	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	445.3 CY		
0130	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (49+65.00-L-)	Lump Sum	L.S.	
0131	8217000000-E	425	REINFORCING STEEL (BRIDGE)	73,019 LB		
0132	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,976 LB		
0133	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	6,113.33 LF		
0134	8364000000-E	SP	HP12X53 STEEL PILES	3,205 LF		
0135	8365000000-E	SP	HP12X53 GALVANIZED STEEL PILES	2,640 LF		
0136	8385200000-E	SP	PP ** X **** GALVANIZED STEEL PILES (24 X 0.50)	5,110 LF		
0137	8392000000-N	SP	PIPE PILE PLATES	70 EA		
0138	8393000000-N	SP	PILE REDRIVES	90 EA		
0139	8475000000-E	460	TWO BAR METAL RAIL	3,065.04 LF		
0140	8517000000-E	460	1'****X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	3,080.27 LF		
0141	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	895 TON		



Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0142	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	993 SY		
0143	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0144	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0145	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
0146	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (49+65.00-L-)	Lump Sum	L.S.	
<b>1523/Oct09/Q878153.182/D581974430000/E146</b>			<b>Total Amount Of Bid For Entire Project :</b>			

**Contract No**     **C202157**

**County (ies):**   **Edgecombe**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General