

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	39.87	SMI	
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	221,577	SY	
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	121,652	SY	
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	29,970	SY	
0006	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	280	TON	
0007	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	17,486	TON	
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	73,267	TON	
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	834	TON	
0010	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	4,396	TON	
0011	1704000000-E	SP	PATCHING EXISTING PAVEMENT	150	TON	
0012	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	247,528	LF	
0013	2815000000-N	858	ADJUSTMENT OF DROP INLETS	17	EA	
0014	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	17	EA	
0015	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	4,500	LF	
0016	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4 EA		
001E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
001E	4430000000-N	1130	DRUMS	620 EA		
002C	4480000000-N	1165	TMIA	2 EA		
0021	4510000000-N	SP	LAW ENFORCEMENT	1,200 HR		
0022	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	288,133 LF		
0023	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	34,068 LF		
0024	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	12,030 LF		
002E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	48 LF		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	10 EA		
0027	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	328,261 LF		
002E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,220 EA		
002E	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
003C	6084000000-E	1660	SEEDING & MULCHING	24.16 ACR		
0031	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	2 EA		
0032	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	980 LF		
003E	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	1,960 LF		

Contract No **C202399**

County (ies): **Buncombe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General