

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (18+77.15 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	30 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	60 TON		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	20 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	30 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	12 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	36 SY		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	108 LF		
0013	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0014	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.85 LF		
0015	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0016	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0017	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	50 LF		
0018	2591000000-E	848	4" CONCRETE SIDEWALK	40 SY		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	3030000000-E	862	STEEL BM GUARDRAIL	25 LF		
0020	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0021	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0022	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0023	3574000000-E	867	GENERIC FENCING ITEM REMOVE & RESET BLACK IRON FENCE	300 LF		
0024	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	400 SY		
0025	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,815 SF		
0026	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	328 SF		
0027	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0028	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	9 EA		
0029	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	120 DAY		
0030	4430000000-N	1130	DRUMS	100 EA		
0031	4445000000-E	1145	BARRICADES (TYPE III)	208 LF		
0032	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	532 LF		
0033	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	4 EA		
0034	6000000000-E	1605	TEMPORARY SILT FENCE	450 LF		
0035	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250 TON		
0036	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
0038	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0039	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	75 LB		
0040	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0041	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0042	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0043	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,500 SY		
0044	6042000000-E	1632	1/4" HARDWARE CLOTH	225 LF		
0045	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0046	6087000000-E	1660	MOWING	0.5 ACR		
0047	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0048	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0049	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0050	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0051	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0052	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	6 EA		

---

**STRUCTURE ITEMS**


---

0053	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+77.40-L-)	Lump Sum	L.S.	
------	--------------	-----	--	----------	------	--

---

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (18+77.40-L-)	Lump Sum	L.S.	
0055	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	6.5 CY		
0056	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	44.5 CY		
0057	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+77.40-L-)	Lump Sum	L.S.	
0058	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,609 LB		
0059	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	397 LB		
0060	8364000000-E	SP	HP12X53 STEEL PILES	400 LF		
0061	8391000000-N	SP	STEEL PILE POINTS	24 EA		
0062	8475000000-E	460	TWO BAR METAL RAIL	120.5 LF		
0063	8517000000-E	460	1'-****X ***** CONCRETE PARAPET (1'-2" X 2'-6")	135.5 LF		
0064	8531000000-E	462	4" SLOPE PROTECTION	139 SY		
0065	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0066	8860000000-N	SP	GENERIC STRUCTURE ITEM VIBRATION MONITORING	Lump Sum	L.S.	
0067	8867000000-E	SP	GENERIC STRUCTURE ITEM 3'-0" X 2'-2" PRESTRESSED CONC CORED SLABS	1,355 LF		
0068	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE DECK GRINDING	Lump Sum	L.S.	

0939/Dec04/Q21371.85/D326323000000/E68

Total Amount Of Bid For Entire Project :

**Contract No**     **C202427**

**County (ies):**   **Forsyth**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General