

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	4 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	6 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,565,000 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+79.82 -I9 FLY-)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (615+24.94 -L REV-)	Lump Sum	L.S.	
0009	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (615+41.08 -L REV-)	Lump Sum	L.S.	
0010	0036000000-E	225	UNDERCUT EXCAVATION	48,000 CY		
0011	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	15,000 TON		
0012	0106000000-E	230	BORROW EXCAVATION	198,000 CY		
0013	0134000000-E	240	DRAINAGE DITCH EXCAVATION	7,760 CY		
0014	0141000000-E	240	BERM DITCH CONSTRUCTION	2,080 LF		
0015	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	27,850 SY		
0016	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	2,700 SY		
0017	0192000000-N	260	PROOF ROLLING	42 HR		
0018	0195000000-E	265	SELECT GRANULAR MATERIAL	10,000 CY		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	22,000 SY		
0020	0199000000-E	SP	TEMPORARY SHORING	1,840 SF		
0021	0223000000-E	SP	ROCK PLATING	11,000 SY		
0022	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING, AND DISPOSAL OF CONTAMINATED SOIL	100 TON		
0023	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	3,175 TON		
0024	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	8,120 SY		
0025	0343000000-E	310	15" SIDE DRAIN PIPE	60 LF		
0026	0344000000-E	310	18" SIDE DRAIN PIPE	112 LF		
0027	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	208 LF		
0028	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	1,452 LF		
0029	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	300 LF		
0030	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	856 LF		
0031	0426000000-E	310	72" RC PIPE CULVERTS, CLASS III	476 LF		
0032	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (36")	688 LF		
0033	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (48")	220 LF		
0034	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (60")	1,040 LF		
0035	0706000000-E	310	12" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	172 LF		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	1,552 LF		
0037	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	352 LF		
0038	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	272 LF		
0039	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	376 LF		
0040	0732000000-E	310	36" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	320 LF		
0041	0738000000-E	310	42" BIT COAT CS PIPE CULVERTS, TYPE B 0.109" THICK	152 LF		
0042	0804000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE B ***** THICK (36", 0.079")	4 EA		
0043	0805000000-E	310	12" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0044	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	30 EA		
0045	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	5 EA		
0046	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	8 EA		
0047	0809000000-E	310	30" BIT COAT CS PIPE ELBOWS, T YPE B 0.079" THICK	6 EA		
0048	0995000000-E	340	PIPE REMOVAL	6,640 LF		
0049	1000000000-E	462	6" SLOPE PROTECTION	910 SY		
0050	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0051	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	61,407 SY		
0052	1066000000-E	501	LIME FOR LIME TREATED SOIL	614 TON		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	1077000000-E	SP	#57 STONE	50 TON		
0054	1121000000-E	520	AGGREGATE BASE COURSE	68,800 TON		
0055	1176000000-E	542	SOIL CEMENT BASE	61,407 SY		
0056	1187000000-E	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	1,689 TON		
0057	1209000000-E	543	ASPHALT CURING SEAL	18,430 GAL		
0058	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0059	1275000000-E	600	PRIME COAT	500 GAL		
0060	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	37,090 SY		
0061	1330000000-E	607	INCIDENTAL MILLING	5,570 SY		
0062	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	5,220 TON		
0063	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	11,980 TON		
0064	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	7,160 TON		
0065	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	29,380 TON		
0066	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	9,820 TON		
0067	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	35,120 TON		
0068	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,050 TON		
0069	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,110 TON		
0070	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	450 TON		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	47,510 LF		
0072	2000000000-N	806	RIGHT OF WAY MARKERS	92 EA		
0073	2022000000-E	815	SUBDRAIN EXCAVATION	1,512 CY		
0074	2033000000-E	815	SUBDRAIN FINE AGGREGATE	756 CY		
0075	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	4,500 LF		
0076	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	135 EA		
0077	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	9 EA		
0078	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	54 LF		
0079	2099000000-E	816	SHOULDER DRAIN	15,140 LF		
0080	2110000000-E	816	4" SHOULDER DRAIN PIPE	15,140 LF		
0081	2121000000-E	816	4" OUTLET PIPE FOR SHOULDER DRAINS	2,000 LF		
0082	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	25 EA		
0083	2143000000-E	818	BLOTTING SAND	15 TON		
0084	2209000000-E	838	ENDWALLS	33.6 CY		
0085	2220000000-E	838	REINFORCED ENDWALLS	56.3 CY		
0086	2253000000-E	840	PIPE COLLARS	1.285 CY		
0087	2264000000-E	840	PIPE PLUGS	1.152 CY		
0088	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	156 EA		
0089	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	32 CY		
0090	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	121 LF		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	12 EA		
0092	2354000000-N	840	FRAME WITH GRATE, STD 840.22	3 EA		
0093	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	34 EA		
0094	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	63 EA		
0095	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	6 EA		
0096	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0097	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0098	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	15 EA		
0099	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	12 EA		
0100	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0101	2418000000-E	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	45 LF		
0102	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	2 EA		
0103	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	6,300 LF		
0104	2556000000-E	846	SHOULDER BERM GUTTER	10,960 LF		
0105	2619000000-E	850	4" CONCRETE PAVED DITCH	75 SY		
0106	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	2,530 SY		
0107	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	410 LF		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	2830000000-N	858	ADJUSTMENT OF MANHOLES	22 EA		
0109	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	40 EA		
0110	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	4 EA		
0111	3030000000-E	862	STEEL BM GUARDRAIL	15,675 LF		
0112	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	200 LF		
0113	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	25 EA		
0114	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	15 EA		
0115	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	22 EA		
0116	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	15 EA		
0117	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	21 EA		
0118	3347000000-E	864	REMOVE & RESET EXISTING GUIDE-RAIL	230 LF		
0119	3360000000-E	863	REMOVE EXISTING GUARDRAIL	750 LF		
0120	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	125 LF		
0121	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0122	3389400000-E	865	DOUBLE FACED CABLE GUIDERAIL	11,000 LF		
0123	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	16 EA		
0124	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	26,630 LF		
0125	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	1,800 EA		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	360 EA		
0127	3557000000-E	866	ADDITIONAL BARBED WIRE	1,320 LF		
0128	3595000000-E	869	RELAPPING GUARDRAIL	2,206.25 LF		
0129	3628000000-E	876	RIP RAP, CLASS I	2,680 TON		
0130	3635000000-E	876	RIP RAP, CLASS II	420 TON		
0131	3642000000-E	876	RIP RAP, CLASS A	25 TON		
0132	3649000000-E	876	RIP RAP, CLASS B	905 TON		
0133	3651000000-E	SP	BOULDERS	155 TON		
0134	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	19,660 SY		
0135	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	8 CY		
0136	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	3 CY		
0137	4057000000-E	SP	OVERHEAD FOOTING	84 CY		
0138	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	3,533 LB		
0139	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	3,956 LB		
0140	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	2,545 LF		
0141	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (545+00)	Lump Sum	L.S.	
0142	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (595+40)	Lump Sum	L.S.	
0143	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (616+50)	Lump Sum	L.S.	



County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0144	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (632+00)	Lump Sum	L.S.	
0145	4096000000-N	904	SIGN ERECTION, TYPE D	6 EA		
0146	4102000000-N	904	SIGN ERECTION, TYPE E	45 EA		
0147	4108000000-N	904	SIGN ERECTION, TYPE F	66 EA		
0148	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	13 EA		
0149	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	8 EA		
0150	4115000000-N	904	SIGN ERECTION, OVERLAY (OVERHEAD)	2 EA		
0151	4116000000-N	904	SIGN ERECTION, OVERLAY (GROUND MOUNTED)	3 EA		
0152	4116200000-N	904	SIGN ERECTION, REPOSITION OVERHEAD	1 EA		
0153	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	4 EA		
0154	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	19 EA		
0155	4234000000-N	907	DISPOSAL OF SIGN, A OR B (OVERHEAD)	12 EA		
0156	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	12 EA		
0157	4360000000-N	SP	GENERIC SIGNING ITEM DISPOSAL OF SIGN SYSTEM ON SPAN WIRE	1 EA		
0158	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	320 SF		
0159	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	352 SF		
0160	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	574 SF		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0161	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0162	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0163	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	60 DAY		
0164	4430000000-N	1130	DRUMS	1,000 EA		
0165	4435000000-N	1135	CONES	220 EA		
0166	4445000000-E	1145	BARRICADES (TYPE III)	368 LF		
0167	4450000000-N	1150	FLAGGER	10,000 HR		
0168	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	6 EA		
0169	4480000000-N	1165	TMIA	2 EA		
0170	4485000000-E	1170	PORTABLE CONCRETE BARRIER	2,060 LF		
0171	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	800 LF		
0172	4510000000-N	SP	LAW ENFORCEMENT	100 HR		
0173	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	2,778 EA		
0174	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	177,100 LF		
0175	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	59,390 LF		
0176	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	8,828 LF		
0177	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	570 LF		
0178	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	22 EA		
0179	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	190 EA		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0180	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	3,125 LF		
0181	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	9 EA		
0182	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	328,751 LF		
0183	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	7,452 LF		
0184	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,184 LF		
0185	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	304 EA		
0186	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	424 EA		
0187	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	116,331 LF		
0188	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,930 LF		
0189	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	381 LF		
0190	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	186 EA		
0191	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	2,210 EA		
0192	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	60 EA		
0193	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	17 EA		
0194	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	10 EA		
0195	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	10 EA		
0196	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0197	5325800000-E	1510	8" WATER LINE	235 LF		
0198	5326200000-E	1510	12" WATER LINE	7,669 LF		
0199	5558000000-E	1515	12" VALVE	7 EA		
0200	5648000000-N	1515	RELOCATE WATER METER	5 EA		
0201	5649000000-N	1515	RECONNECT WATER METER	4 EA		
0202	5666000000-E	1515	FIRE HYDRANT	2 EA		
0203	5672000000-N	1515	RELOCATE FIRE HYDRANT	8 EA		
0204	5691300000-E	1520	8" SANITARY GRAVITY SEWER	3,557.2 LF		
0205	5691500000-E	1520	12" SANITARY GRAVITY SEWER	1,969.7 LF		
0206	5709200000-E	1520	4" FORCE MAIN SEWER	10 LF		
0207	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	1 EA		
0208	5775000000-E	1525	4' DIA UTILITY MANHOLE	25 EA		
0209	5776000000-E	1525	5' DIA UTILITY MANHOLE	3 EA		
0210	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	121.5 LF		
0211	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	23.6 LF		
0212	5801000000-E	1530	ABANDON 8" UTILITY PIPE	5,507.5 LF		
0213	5804000000-E	1530	ABANDON 12" UTILITY PIPE	3,882 LF		
0214	5815000000-N	1530	REMOVE WATER METER	19 EA		
0215	5815500000-N	1530	REMOVE FIRE HYDRANT	4 EA		
0216	5816000000-N	1530	ABANDON UTILITY MANHOLE	17 EA		
0217	5828000000-N	1530	REMOVE UTILITY MANHOLE	1 EA		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0218	5836000000-E	1540	24" ENCASEMENT PIPE	750 LF		
0219	5836200000-E	1540	30" ENCASEMENT PIPE	375 LF		
0220	6000000000-E	1605	TEMPORARY SILT FENCE	63,700 LF		
0221	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	3,750 TON		
0222	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	6,675 TON		
0223	6012000000-E	1610	SEDIMENT CONTROL STONE	5,315 TON		
0224	6015000000-E	1615	TEMPORARY MULCHING	475 ACR		
0225	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	9,050 LB		
0226	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	37.75 TON		
0227	6024000000-E	1622	TEMPORARY SLOPE DRAINS	14,300 LF		
0228	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	65 EA		
0229	6029000000-E	SP	SAFETY FENCE	15,500 LF		
0230	6030000000-E	1630	SILT EXCAVATION	36,600 CY		
0231	6036000000-E	1631	MATting FOR EROSION CONTROL	97,000 SY		
0232	6037000000-E	SP	COIR FIBER MAT	600 SY		
0233	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	20,500 SY		
0234	6042000000-E	1632	1/4" HARDWARE CLOTH	2,750 LF		
0235	6045000000-E	SP	*** TEMPORARY PIPE (15")	400 LF		
0236	6045000000-E	SP	*** TEMPORARY PIPE (24")	475 LF		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0237	6069000000-E	1638	STILLING BASINS	1,100 CY		
0238	6070000000-N	SP	SPECIAL STILLING BASINS	10 EA		
0239	6071010000-E	SP	WATTLE	4,750 LF		
0240	6071020000-E	SP	POLYACRYLAMIDE (PAM)	2,370 LB		
0241	6071030000-E	SP	COIR FIBER BAFFLES	11,000 LF		
0242	6071050000-E	SP	*** SKIMMER (1-1/2")	48 EA		
0243	6084000000-E	1660	SEEDING & MULCHING	255 ACR		
0244	6087000000-E	1660	MOWING	288.5 ACR		
0245	6090000000-E	1661	SEED FOR REPAIR SEEDING	4,000 LB		
0246	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	9.5 TON		
0247	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	5,775 LB		
0248	6108000000-E	1665	FERTILIZER TOPDRESSING	173.25 TON		
0249	6111000000-E	SP	IMPERVIOUS DIKE	200 LF		
0250	6114500000-N	SP	SPECIALIZED HAND MOWING	200 MHR		
0251	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
0252	6120000000-E	SP	CULVERT DIVERSION CHANNEL	1,175 CY		
0253	6123000000-E	1670	REFORESTATION	10 ACR		
0254	7060000000-E	1705	SIGNAL CABLE	7,805 LF		
0255	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	39 EA		
0256	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	5 EA		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0257	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	12 EA		
0258	7264000000-E	1710	MESSENGER CABLE (3/8")	2,255 LF		
0259	7279000000-E	1715	TRACER WIRE	915 LF		
0260	7288000000-E	1715	PAVED TRENCHING (***** (1, 2"))	500 LF		
0261	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2"))	1,680 LF		
0262	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2"))	250 LF		
0263	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	13 EA		
0264	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	2 EA		
0265	7360000000-N	1720	WOOD POLE	5 EA		
0266	7372000000-N	1721	GUY ASSEMBLY	13 EA		
0267	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0268	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0269	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	2 EA		
0270	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,115 LF		
0271	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	9,655 LF		
0272	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	1,150 LF		
0273	7540000000-N	1731	SPLICE ENCLOSURE	1 EA		
0274	7552000000-N	1731	INTERCONNECT CENTER	1 EA		
0275	7564100000-N	1732	FIBER-OPTIC TRANSCEIVER, SELF- HEALING RING	1 EA		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0276	7566000000-N	1733	DELINEATOR MARKER	1 EA		
0277	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIVER	1 EA		
0278	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	600 LF		
0279	7576000000-N	SP	METAL STRAIN SIGNAL POLE	8 EA		
0280	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	1 EA		
0281	7613000000-N	SP	SOIL TEST	9 EA		
0282	7614100000-E	SP	DRILLED PIER FOUNDATION	54 CY		
0283	7630000000-N	SP	METAL STRAIN POLE DESIGN	8 EA		
0284	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	1 EA		
0285	7636000000-N	1745	SIGN FOR SIGNALS	17 EA		
0286	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0287	7686000000-N	SP	CONDUIT ENTRANCE INTO EXISTING FOUNDATION	1 EA		
0288	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
0289	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	18 EA		
0290	7901000000-N	1753	CABINET BASE EXTENDER	2 EA		
0291	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	1 EA		
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
0292	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	64 LF		
AA1						



County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0293 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,844 LF		
0294 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,720 LF		
0295 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	3,892 LF		
0296 AA1	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	4,208 LF		
*** OR ***						
0297 AA2	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	36 LF		
0298 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,496 LF		
0299 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,672 LF		
0300 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,292 LF		
0301 AA2	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,804 LF		
0302 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (12")	28 LF		
0303 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	1,348 LF		
0304 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	48 LF		
0305 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	1,600 LF		
0306 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	2,404 LF		
*** OR ***						
0307 AA3	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	36 LF		
0308 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,496 LF		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0309 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,672	LF	
0310 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,292	LF	
0311 AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,804	LF	
0312 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (12", 0.064")	28	LF	
0313 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	1,348	LF	
0314 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	48	LF	
0315 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")	1,600	LF	
0316 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (30", 0.079")	2,404	LF	
***** END SCHEDULE AA *****						
0346	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (84")	140	LF	
0347	0986000000-E	SP	GENERIC PIPE ITEM 84" RC PIPE CULVERTS, CLASS IV IN SOIL (TRENCHLESS INSTALLATION)	230	LF	
0348	0986000000-E	SP	GENERIC PIPE ITEM 84" RC PIPE CULVERTS, CLASS IV NOT IN SOIL (TRENCHLESS INSTALLATION)	230	LF	

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>CULVERT ITEMS</b>						
0317	8126000000-N	414	CULVERT EXCAVATION, STA ***** (12+96.00-YRPC-)	Lump Sum	L.S.	
0318	8126000000-N	414	CULVERT EXCAVATION, STA ***** (13+63.00-FRONT-)	Lump Sum	L.S.	
0319	8126000000-N	414	CULVERT EXCAVATION, STA ***** (19+18.00-YRPB-)	Lump Sum	L.S.	
0320	8126000000-N	414	CULVERT EXCAVATION, STA ***** (19+93.70-Y-)	Lump Sum	L.S.	
0321	8126000000-N	414	CULVERT EXCAVATION, STA ***** (612+27.00-LREV-)	Lump Sum	L.S.	
0322	8126000000-N	414	CULVERT EXCAVATION, STA ***** (680+39.00-LREV-)	Lump Sum	L.S.	
0323	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	1,640 TON		
0324	8196000000-E	420	CLASS A CONCRETE (CULVERT)	4,013.1 CY		
0325	8245000000-E	425	REINFORCING STEEL (CULVERT)	509,403 LB		
<b>STRUCTURE ITEMS</b>						
0326	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,615+26.51-LREV-NBL)	Lump Sum	L.S.	
0327	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,615+26.51-LREV-SBL)	Lump Sum	L.S.	
0328	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,665+35.34-LREV-)	Lump Sum	L.S.	
0329	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	29,465.3 SF		
0330	8161000000-E	420	GROOVING BRIDGE FLOORS	30,406.7 SF		
0331	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	533.4 CY		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0332	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (615+26.51-LREV-NBL)	Lump Sum	L.S.	
0333	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (615+26.51-LREV-SBL)	Lump Sum	L.S.	
0334	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (665+35.34-LREV-)	Lump Sum	L.S.	
0335	8217000000-E	425	REINFORCING STEEL (BRIDGE)	74,653 LB		
0336	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,228 LB		
0337	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	2,119.8 LF		
0338	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	524,000 LS		
0339	8364000000-E	SP	HP12X53 STEEL PILES	3,800 LF		
0340	8384000000-E	SP	HP14X73 STEEL PILES	2,830 LF		
0341	8503000000-E	460	CONCRETE BARRIER RAIL	1,353.03 LF		
0342	8531000000-E	462	4" SLOPE PROTECTION	2,540 SY		
0343	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0344	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0345	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1043/Dec07/Q4831569.417/D1373685070000/E348			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202128**

**County (ies):**   **Lee**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General