






See Sheet 1-A For Index of Sheets
See Sheet 1-B For Conventional Symbols

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

WAKE COUNTY


**LOCATION: BRIDGE NO. 448 OVER AUSTIN CREEK AND
BRIDGE NO. 140 OVER SMITHS CREEK AND
APPROACHES ON SR 2053 (JONES DAIRY RD.)**
TYPE OF WORK: GRADING, PAVING, DRAINAGE AND STRUCTURES

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	B-3919	1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
33353.1.1	BRZ-2053(1)	P.E.	
33353.2.1	BRZ-2053(1)	RW & UTIL.	
33353.3.1	BRZ-2053(1)	CONST.	



**DESIGN EXCEPTION REQUIRED FOR VERTICAL ALIGNMENT AND VERTICAL STOPPING SIGHT DISTANCE.

GRAPHIC SCALES



DESIGN DATA

ADT 2009 = 8,530
ADT 2030 = 16,600
DHV = 11 %
D = 63 %
T = 4 % *
V = 55 MPH**
FUNC CLASS=RURAL LOCAL
* (TTST 2% + DUAL 2%)

PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT B-3919 = 0.251 MI
LENGTH STRUCTURES TIP PROJECT B-3919 = 0.035 MI
TOTAL LENGTH TIP PROJECT B-3919 = 0.286 MI

Prepared In the Office of:
DIVISION OF HIGHWAYS
1000 Birch Ridge Dr., Raleigh NC, 27610

2006 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
NOVEMBER 24, 2008

LETTING DATE:
DECEMBER 15, 2009

GLENN W. MUMFORD, PE
PROJECT ENGINEER

SUSAN C. LANCASTER, PE
PROJECT DESIGN ENGINEER

HYDRAULICS ENGINEER




SIGNATURE: *Steven M. Bondor* P.E. 9-29-09

ROADWAY DESIGN ENGINEER



SIGNATURE: *Susan C. Lancaster* 9/29/09

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA



Art McMillan
STATE HIGHWAY DESIGN ENGINEER P.E.

TIP PROJECT: B-3919


CONTRACT: C202232

25-SEP-2009 07:28
F:\Roadway\proj\p3919_rdy_tsh.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$

REVISIONS

09/28/09

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS



8/17/99

INDEX OF SHEETS

1	TITLE SHEET
1-A	"INDEX OF SHEETS, GENERAL NOTES AND LIST OF STANDARDS (2006 SPECIFICATIONS)"
1-B	CONVENTIONAL SYMBOLS
1-C	SURVEY CONTROL SHEET
2 THROUGH 2-B	"PAVEMENT SCHEDULE, TYPICAL SECTIONS, AND WEDGING DETAIL"
2-C THROUGH 2-D	DRAINAGE DETAILS
2-E	DETAIL OF ANCHORAGE FOR FRAMES
2-F THROUGH 2-G	METHOD OF PIPE INSTALLATION
3	SUMMARY OF QUANTITIES
3-A	SUMMARY OF DRAINAGE QUANTITIES
3-B	"SUMMARY OF EARTHWORK, 2'-6" CURB AND GUTTER, BREAKING OF EXISTING ASPHALT PAVEMENT, REMOVAL OF EXISTING ASPHALT PAVEMENT, AND MILLING OF ASPHALT PAVEMENT"
3-C	PARCEL INDEX SHEET
4 THROUGH 5	PLAN SHEETS
6	PROFILE SHEETS
TCP-1 THROUGH TCP-4	TRAFFIC CONTROL PLANS
PMP-1 THROUGH PMP-4	PAVEMENT MARKING PLANS
EC-1 THROUGH EC-7	EROSION CONTROL PLANS
RF-1	REFORESTATION PLANS
SIGN-1 THROUGH SIGN-4	SIGNING PLANS
UC-1 THROUGH UC-5	UTILITY CONSTRUCTION PLANS
UO-1 THROUGH UO-3	UTILITIES BY OTHERS PLANS
X-1	CROSS-SECTION INDEX
X-1A	CROSS-SECTION SUMMARY SHEET
X-2 THROUGH X-12	CROSS-SECTIONS
S-1 THROUGH S-51	STRUCTURE PLANS

2006 ROADWAY ENGLISH STANDARD DRAWINGS
EFF. 07-18-06
REV. 01-02-07

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated July 18, 2006 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.03	Method of Clearing - Method III
225.02	Guide for Grading Subgrade - Secondary and Local
225.04	Method of Obtaining Superelevation - Two Lane Pavement
DIVISION 3 - PIPE CULVERTS	
310.10	Driveway Pipe Construction
DIVISION 4 - MAJOR STRUCTURES	
422.10	Reinforced Bridge Approach Fills
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS	
560.01	Method of Shoulder Construction - High Side of Superelevated Curve - Method I
DIVISION 6 - ASPHALT BASES AND PAVEMENTS	
654.01	Pavement Repairs
DIVISION 8 - INCIDENTALS	
806.01	Concrete Right-of-Way Marker
806.02	Granite Right-of-Way Marker
840.00	Concrete Base Pad for Drainage Structures
840.01	Brick Catch Basin - 12" thru 54" Pipe
840.02	Concrete Catch Basin - 12" thru 54" Pipe
840.03	Frame, Grates and Hood - for Use on Standard Catch Basin
840.13	Concrete Bridge Approach Drop Inlet - 12" thru 24" Pipe
840.29	Frames and Narrow Slot Flat Grates
840.31	Concrete Junction Box - 12" thru 66" Pipe
840.32	Brick Junction Box - 12" thru 66" Pipe
840.45	Precast Drainage Structure
840.54	Manhole Frame and Cover
840.66	Drainage Structure Steps
846.01	Concrete Curb, Gutter and Curb & Gutter
848.01	Concrete Sidewalk
848.04	Street Turnout
848.05	Wheelchair Ramp - Curb Cut
850.01	Concrete Paved Ditches
862.01	Guardrail Placement
862.02	Guardrail Installation
862.03	Structure Anchor Units
876.02	Guide for Rip Rap at Pipe Outlets
876.04	Drainage Ditches with Class 'B' Rip Rap

GENERAL NOTES: 2006 SPECIFICATIONS EFFECTIVE: 07-18-06
REVISED: 07-30-08

GRADING AND SURFACING OR RESURFACING AND WIDENING:
THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:
CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

SUPERELEVATION:
ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:
ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

SIDE ROADS:
THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

DRIVEWAYS:
STREET TURNOUT:
STREET RETURNS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 848.04 USING THE RADII NOTED ON PLANS.

GUARDRAIL:
THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

TEMPORARY SHORING:
SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC WILL BE PAID FOR AS "EXTRA WORK" IN ACCORDANCE WITH SECTION 104-7.

SUBSURFACE PLANS:
NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

END BENTS:
THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:
UTILITY OWNERS ON THIS PROJECT ARE
City of Raleigh (Water & Sanitary Sewer) PSNC Energy (Gas)
Wake EMC (Power) Embarq (Telephone) Time Warner (CATV)

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS, EXCEPT AS SHOWN ON THE PLANS.

RIGHT-OF-WAY MARKERS:
ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

WHEELCHAIR RAMPS:
WHEELCHAIR RAMPS ARE SHOWN ON THE PLANS AT APPROXIMATE LOCATIONS. THE CONSTRUCTION OF ALL WHEELCHAIR RAMPS SHALL BE IN ACCORDANCE WITH STD. NO. 848.05

25-SEP-2009 12:09 r:\work\proj\p3919_rdy_tsh.dgn

Note: Not to Scale

*S.U.E. = Subsurface Utility Engineering

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CONVENTIONAL PLAN SHEET SYMBOLS

BOUNDARIES AND PROPERTY:

State Line	-----
County Line	-----
Township Line	-----
City Line	-----
Reservation Line	-----
Property Line	-----
Existing Iron Pin	○ EIP
Property Corner	⊠
Property Monument	□ ECM
Parcel/Sequence Number	① 23
Existing Fence Line	× × ×
Proposed Woven Wire Fence	○
Proposed Chain Link Fence	□
Proposed Barbed Wire Fence	◇
Existing Wetland Boundary	----- WLB
Proposed Wetland Boundary	----- WLB
Existing Endangered Animal Boundary	----- EAB
Existing Endangered Plant Boundary	----- EPB

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	○
Sign	⊙
Well	⊙ W
Small Mine	⊗
Foundation	▭
Area Outline	▭
Cemetery	⊕
Building	▭
School	▭
Church	⊕
Dam	▭

HYDROLOGY:

Stream or Body of Water	~~~~~
Hydro, Pool or Reservoir	▭
Jurisdictional Stream	----- JS
Buffer Zone 1	----- BZ 1
Buffer Zone 2	----- BZ 2
Flow Arrow	←
Disappearing Stream	→
Spring	○
Swamp Marsh	⊕
Proposed Lateral, Tail, Head Ditch	▭
False Sump	▽

RAILROADS:

Standard Gauge	-----
RR Signal Milepost	○ MILEPOST 35
Switch	□ SWITCH
RR Abandoned	-----
RR Dismantled	-----

RIGHT OF WAY:

Baseline Control Point	◆
Existing Right of Way Marker	△
Existing Right of Way Line	-----
Proposed Right of Way Line	-----
Proposed Right of Way Line with Iron Pin and Cap Marker	○
Proposed Right of Way Line with Concrete or Granite Marker	⊕
Existing Control of Access	⊕
Proposed Control of Access	⊕
Existing Easement Line	----- E
Proposed Temporary Construction Easement	----- E
Proposed Temporary Drainage Easement	----- TDE
Proposed Permanent Drainage Easement	----- PDE
Proposed Permanent Utility Easement	----- PUE

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	-----
Existing Curb	-----
Proposed Slope Stakes Cut	----- C
Proposed Slope Stakes Fill	----- F
Proposed Wheel Chair Ramp	⊕ WCR
Proposed Wheel Chair Ramp Curb Cut	⊕ WCC
Curb Cut for Future Wheel Chair Ramp	⊕ CCFR
Existing Metal Guardrail	-----
Proposed Guardrail	-----
Existing Cable Guiderail	-----
Proposed Cable Guiderail	-----
Equality Symbol	⊕
Pavement Removal	▭

VEGETATION:

Single Tree	⊕
Single Shrub	⊕
Hedge	~~~~~
Woods Line	~~~~~
Orchard	⊕
Vineyard	▭ Vineyard

EXISTING STRUCTURES:

MAJOR:	
Bridge, Tunnel or Box Culvert	▭ CONC
Bridge Wing Wall, Head Wall and End Wall	▭ CONC WW
MINOR:	
Head and End Wall	▭ CONC HW
Pipe Culvert	-----
Footbridge	-----
Drainage Box: Catch Basin, DI or JB	□ CB
Paved Ditch Gutter	-----
Storm Sewer Manhole	⊕
Storm Sewer	----- S

UTILITIES:

POWER:	
Existing Power Pole	●
Proposed Power Pole	○
Existing Joint Use Pole	●
Proposed Joint Use Pole	○
Power Manhole	⊕
Power Line Tower	⊕
Power Transformer	⊕
U/G Power Cable Hand Hole	⊕
H-Frame Pole	●
Recorded U/G Power Line	----- P
Designated U/G Power Line (S.U.E.*)	----- P

TELEPHONE:

Existing Telephone Pole	●
Proposed Telephone Pole	○
Telephone Manhole	⊕
Telephone Booth	⊕
Telephone Pedestal	⊕
Telephone Cell Tower	⊕
U/G Telephone Cable Hand Hole	⊕
Recorded U/G Telephone Cable	----- T
Designated U/G Telephone Cable (S.U.E.*)	----- T
Recorded U/G Telephone Conduit	----- TC
Designated U/G Telephone Conduit (S.U.E.*)	----- TC
Recorded U/G Fiber Optics Cable	----- T FO
Designated U/G Fiber Optics Cable (S.U.E.*)	----- T FO

WATER:

Water Manhole	⊕
Water Meter	⊕
Water Valve	⊕
Water Hydrant	⊕
Recorded U/G Water Line	----- W
Designated U/G Water Line (S.U.E.*)	----- W
Above Ground Water Line	----- A/G Water

TV:

TV Satellite Dish	⊕
TV Pedestal	⊕
TV Tower	⊕
U/G TV Cable Hand Hole	⊕
Recorded U/G TV Cable	----- TV
Designated U/G TV Cable (S.U.E.*)	----- TV
Recorded U/G Fiber Optic Cable	----- TV FO
Designated U/G Fiber Optic Cable (S.U.E.*)	----- TV FO

GAS:

Gas Valve	◇
Gas Meter	⊕
Recorded U/G Gas Line	----- G
Designated U/G Gas Line (S.U.E.*)	----- G
Above Ground Gas Line	----- A/G Gas

SANITARY SEWER:

Sanitary Sewer Manhole	⊕
Sanitary Sewer Cleanout	⊕
U/G Sanitary Sewer Line	----- SS
Above Ground Sanitary Sewer	----- A/G Sanitary Sewer
Recorded SS Forced Main Line	----- FSS
Designated SS Forced Main Line (S.U.E.*)	----- FSS

MISCELLANEOUS:


Utility Pole	●
Utility Pole with Base	⊕
Utility Located Object	○
Utility Traffic Signal Box	⊕
Utility Unknown U/G Line	----- UTIL
U/G Tank; Water, Gas, Oil	▭
A/G Tank; Water, Gas, Oil	▭
U/G Test Hole (S.U.E.*)	⊕
Abandoned According to Utility Records	AATUR
End of Information	E.O.I.

SURVEY CONTROL SHEET B-3919

WAKE COUNTY


**LOCATION: BRIDGE NO. 448 OVER AUSTIN CREEK AND
BRIDGE NO. 140 OVER SMITHS CREEK AND APPROACHES
ON SR 2053 (JONES DAIRY RD.)**

B-3919



NCGS MONUMENT "JIMWILL"
STATE PLANE COORDINATES

N=807009.9574
E=2142735.9407



CONTROL DATA

BASELINE POINT	DESC.	NORTH	EAST	ELEVATION	L STATION	OFFSET
1	BL-1	804713.8278	2152474.6658	279.94	10+78.95	13.63 LT
2	BL-2	805056.8917	2152162.1761	259.47	15+41.20	29.31 LT
3	BL-3	805208.7756	2152064.9442	256.43	17+20.62	12.69 LT
4	BL-4	805481.3413	2151852.9061	263.07	20+65.95	12.64 LT
5	BL-5	805875.2103	2151547.3365	284.51	25+64.30	12.49 LT
6	BL-6	806307.3661	2151244.8532	292.50	30+90.69	13.22 LT
7	BL-7	806667.6417	2151053.1422	271.04	34+97.87	13.08 LT
8	BL-8	806969.3517	2150896.3300	266.47	38+39.00	14.38 LT
9	BL-9 = (BY9-53 R-2809C)	807125.2296	2150812.0501	269.91	40+15.26	16.51 LT
10	BL-10 = (BY9-52 R-2809C)	807498.6585	2150616.5252	296.42	OUTSIDE PROJECT LIMITS	

BY POINT	DESC.	NORTH	EAST	ELEVATION	Y STATION	OFFSET
15	BY-15	804730.1690	2151999.5086	270.74	11+26.42	18.06 RT
2	BL-2	805056.8917	2152162.1761	259.47	15+04.55	31.97 RT

BENCHMARK DATA

BENCHMARK	ELEVATION	DESCRIPTION
BM1	279.55	N 804689 E 2152461 L STATION 10+70 40 LEFT R/R SPIKE SET IN A 16" OAK TREE
BM2	260.43	N 805162 E 2152043 L STATION 16+97 58 LEFT R/R SPIKE SET IN A 30" OAK TREE
BM3	263.02	N 806908 E 2150998 L STATION 37+36 48 RIGHT R/R SPIKE SET IN A 32" PINE TREE
BM4	294.32	N 807478 E 2150699 L STATION 43+62 N 41° 14' 00.2" E DIST 51.23 R/R SPIKE SET IN A 16" HICKORY TREE

DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NC GS FOR MONUMENT "JIMWILL" WITH NAD 83 STATE PLANE GRID COORDINATES OF NORTHING: 807009.9574(±) EASTING: 2142735.9407(±) THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.99993779 THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "JIMWILL" TO -L- STATION 15+42.50 IS S 78°25'56.7" E 9644.35'

ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES VERTICAL DATUM USED IS NAVD 88

NOTES:

THE CONTROL DATA FOR THIS PROJECT CAN BE FOUND ELECTRONICALLY BY SELECTING PROJECT CONTROL DATA AT:
[HTTP://WWW.DO H.DOT.STATE.NC.US/PRECONSTRUCT/HIGHWAY/LOCATION/PROJECT/](http://www.doh.dot.state.nc.us/preconstruct/highway/location/project/)
B3919_ls_control_071018.txt

SITE CALIBRATION INFORMATION HAS NOT BEEN PROVIDED FOR THIS PROJECT. IF FURTHER INFORMATION IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

▲ INDICATES GEODETIC CONTROL MONUMENTS USED OR SET FOR HORIZONTAL PROJECT CONTROL BY THE NCDOT LOCATION AND SURVEYS UNIT.



NETWORK ESTABLISHED FROM NC GS COORDINATES FROM PROJECT R2809C


NOTE: DRAWING NOT TO SCALE

6/2/99


FINAL PAVEMENT SCHEDULE

C1	PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD
C2	PROP. APPROX. 2.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 140 LBS. PER SQ. YD IN EACH OF TWO LAYERS
C3	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD IN EACH OF TWO LAYERS
C4	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 2" IN DEPTH
D1	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD
D2	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 2½" IN DEPTH OR GREATER THAN 4" IN DEPTH
E1	PROP. APPROX. 4.5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 513 LBS. PER SQ. YD
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH
J	8" AGGREGATE BASE COURSE
R	2'-6" CONCRETE CURB AND GUTTER
S	4" CONCRETE SIDEWALK
T	EARTH MATERIAL
U	EXISTING PAVEMENT
V	MILLING ASPHALT PAVEMENT. 3" DEPTH.
W1	VARIABLE DEPTH ASPHALT PAVEMENT (SEE DETAIL SHOWING METHOD OF WEDGING)

PROJECT REFERENCE NO. B-3919	SHEET NO. 2
ROADWAY DESIGN ENGINEER <i>Susan C. Lancia</i>	PAVEMENT DESIGN ENGINEER <i>Clark S. Morrison</i>
	



Detail Showing Method of Wedging



TYPICAL SECTION NO. 1

USE TYPICAL SECTION NO. 1
AT THE FOLLOWING LOCATIONS:

TRANSITION FROM EXISTING AT -L- STA. 15+42.50
TO TYPICAL SECTION NO. 1 AT -L- STA. 16+25.00

-L- STA. 16+25.00 TO -L- STA. 16+54.00


-L- STA. 40+50.00 TO -L- STA. 41+80.00**

* 14' FUTURE OUTSIDE LANES FOR BICYCLE ACCOMMODATION


** TIE TO EXISTING 40+56.00 TO 41+80.00 RT.

25-SEP-2009 07:28
C:\Roadway\Proj\B3919_rdy_tjpdgn
\$\$\$\$\$USERNAME\$\$\$\$\$


PAVEMENT SCHEDULE	
C1	1½" S9.5B
C2	2.5" S9.5B
C3	3" S9.5B
C4	VAR. DEPTH S9.5B
D1	4" I19.0B
D2	VAR. DEPTH I19.0B
E1	4.5" B25.0B
E2	VAR. DEPTH B25.0B
J	8" ABC
R	2'-6" C & G
S	4" CONC. SIDEWALK
T	EARTH MATERIAL
U	EXIST. PAVEMENT
V	MILLING PAVEMENT
W1	WEDGING DETAIL



USE TYPICAL SECTION NO. 2
AT THE FOLLOWING LOCATIONS:
-L- STA. 16+54.00 TO -L- STA. 17+12.58 (BEGIN BRIDGE NO. 448)
-L- STA. 38+62.60 (END BRIDGE NO. 140) TO -L- STA. 40+50.00



USE TYPICAL SECTION NO. 3
AT THE FOLLOWING LOCATIONS:
-L- STA. 18+57.00 TO 19+25.00
TRANSITION FROM TYPICAL SECTION NO. 3 AT -L- STA. 19+25.00 TO EXISTING AT -L- STA. 20+00.00
TRANSITION FROM EXISTING AT -L- STA. 32+50.00 TO TYPICAL SECTION NO. 3 AT -L- STA. 33+25.00
-L- STA. 33+25.00 TO 34+00.00
OVERLAY EXISTING PAVEMENT AND TRANSITION SHOULDERS AT AN 8:1 TAPER AT THE FOLLOWING LOCATIONS:
-L- STA. 20+00.00 TO -L- 21+25.00
* WIDEN SHOULDERS AN ADDITIONAL 3' WHERE GUARDRAIL IS PROPOSED







USE TYPICAL SECTION NO. 4
AT THE FOLLOWING LOCATIONS:
-L- STA. 17+97.83 (END BRIDGE NO. 448) TO -L- STA. 18+57.00
-L- STA. 34+00.00 TO -L- STA. 37+62.60 (BEGIN BRIDGE NO. 140)
* WIDEN SHOULDERS AN ADDITIONAL 3' WHERE GUARDRAIL IS PROPOSED

PROJECT REFERENCE NO. B-3919	SHEET NO. 2-A
ROADWAY DESIGN ENGINEER SEAL 027373 BUSTIN C. LANCASTER	PAVEMENT DESIGN ENGINEER SEAL 22896 CLARK S. MORRISON

25-SEP-2009 07:28
C:\p\code\proj\3919_rdy_tj.p.dgn

PAVEMENT SCHEDULE	
C1	1½" S9.5B
C2	2.5" S9.5B
C3	3" S9.5B
C4	VAR. DEPTH S9.5B
D1	4" I19.0B
D2	VAR. DEPTH I19.0B
E1	4.5" B25.0B
E2	VAR. DEPTH B25.0B
J	8" ABC
R	2'-6" C & G
S	4" CONC. SIDEWALK
T	EARTH MATERIAL
U	EXIST. PAVEMENT
V	MILLING PAVEMENT
W1	WEDGING DETAIL



PROJECT REFERENCE NO.	SHEET NO.
B-3919	2-B

ROADWAY DESIGN ENGINEER

Susan C. Lancaster

PAVEMENT DESIGN ENGINEER

Clark S. Morrison

USE TYPICAL SECTION NO. 5
AT THE FOLLOWING LOCATIONS:

-L- STA. 17+12.58 (BEGIN BRIDGE NO. 448)
TO -L- STA. 17+97.83 (END BRIDGE NO. 448)

-L- STA. 37+62.60 (BEGIN BRIDGE NO. 140)
TO -L- STA. 38+62.60 (END BRIDGE NO. 140)

USE TYPICAL SECTION NO. 6
AT THE FOLLOWING LOCATIONS:

-Y1- STA. 12+18.00 TO -Y1- STA. 12+68.26

USE TYPICAL SECTION NO. 7
AT THE FOLLOWING LOCATION:



-Y1- STA. 11+90.00 TO -Y1- STA. 12+18.00 LT

USE TYPICAL SECTION NO. 8
AT THE FOLLOWING LOCATION:


-DR- STA. 10+12.00 TO -DR- STA. 10+66.00

REVISIONS


25-SEP-2009 07:28:39 3919_rdy_typ.dgn




Type of Liner= PSRM
 STA. -L- 18+20 TO STA. -L- 18+92 LT
 STA. -L- 19+63 TO STA. -L- 20+50 LT




Type of Liner= PSRM
 STA. -L- 35+00 TO STA. -L- 37+25 RT
 STA. -L- 37+90 TO STA. -L- 38+90 LT




Type of Liner= PSRM
 STA. -L- 37+25 TO STA. -L- 37+66 RT




Type of Liner= CL.1 Rip-Rap
 STA. -L- 18+10 TO STA. -L- 18+20 LT
 STA. -L- 37+80 TO STA. -L- 37+90 LT
 STA. -L- 38+10 TO STA. -L- 38+40 RT



STA. -L- 35+80 LT




8/17/99




LEVEL SPREADER WITH BYPASS -L- STA 18+90 LT

(NOT TO SCALE)




PLAN VIEW



PROFILE VIEW


CONCRETE PAVED DITCH LEVEL SPREADER




SECTION-AA

LEVEL SPREADER WITH BYPASS -L- STA 39+00 LT

(NOT TO SCALE)




PLAN VIEW



PROFILE VIEW

CONCRETE PAVED DITCH LEVEL SPREADER



SECTION-AA

10-SEP-2009 15:24:19 hyd_detail.dgn

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ENGLISH DETAIL DRAWING FOR
ANCHORAGE FOR FRAMES
BRICK/CONCRETE/PRECAST CONCRETE

SHEET 1 OF 1
840D25


STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ENGLISH DETAIL DRAWING FOR
ANCHORAGE FOR FRAMES
BRICK/CONCRETE/PRECAST CONCRETE


SHEET 1 OF 1
840D25



BRICK MASONRY CONSTRUCTION




CONCRETE CONSTRUCTION




PRECAST CONCRETE CONSTRUCTION

DETAIL SHOWING ANCHORAGE OF FRAME FOR GRATED DROP INLET


NOTE:
CONSTRUCT GRATED DROP INLET TO COINCIDE WITH NORMAL OR SUPERELEVATED SHOULDER OR PAVEMENT SLOPE.




MASONRY ANCHOR
3/8" DIA. BOLT WITH PLATE




CONCRETE ANCHOR
3/8" DIA. BENT BAR



PRECAST CONCRETE ANCHOR
3/8" DIA. BENT BAR



FRAME AND GRATE INSTALLATION FOR NORMAL CROWN AND SUPERELEVATED SECTIONS



PROJECT SERVICES UNIT
STANDARDS AND SPECIAL DESIGN
Office 919-250-4128 FAX 919-250-4119

SEE PLATE FOR TITLE

ORIGINAL BY: 2006 STD 840.25 DATE: 07/18/06
 MODIFIED BY: E. E. WARD DATE: 9/25/06
 CHECKED BY: *[Signature]* DATE: 11/13/06
 FILE SPEC.: *[Signature]*


\$\$\$\$\$SYTIME\$\$\$\$\$
\$\$\$\$\$USERNAME\$\$\$\$\$

30-JUL-2009 08:48
 s:\contracts\corporate\special details\enrward\stds\06\stds to special details\300001\03000d01.dgn
 Jrower-ton At 13:23:50

5/14/99


STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

7-06



ENGLISH DETAIL DRAWING FOR
METHOD OF PIPE INSTALLATION
 FLEXIBLE PIPE

7-06



GENERAL NOTES:

- I.D. = THE MAXIMUM HORIZONTAL INSIDE DIAMETER DIMENSION.
- O.D. = THE MAXIMUM HORIZONTAL OUTSIDE DIAMETER DIMENSION.
- H = THE FILL HEIGHT MEASURED VERTICALLY AT ANY POINT ALONG THE PIPE FROM THE TOP OF THE PIPE TO THE TOP OF THE EMBANKMENT AT THAT POINT.

- TAKE CARE TO FULLY COMPACT HAUNCH ZONE OF PIPE BACKFILL.
- LOOSELY PLACED SELECT MATERIAL CLASS III OR CLASS II, TYPE 1 FOR PIPE BEDDING & LEAVE SECTION DIRECTLY BENEATH PIPE UNCOMPACTED AS PIPE SEATING AND BACKFILL WILL ACCOMPLISH COMPACTION.

SHEET 1 OF 3
300D01

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.


7-06

ENGLISH DETAIL DRAWING FOR
METHOD OF PIPE INSTALLATION
 FLEXIBLE PIPE

SHEET 1 OF 3
300D01


STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

7-06



ENGLISH DETAIL DRAWING FOR
METHOD OF PIPE INSTALLATION
 RIGID PIPE

7-06



GENERAL NOTES:

- I.D. = THE MAXIMUM HORIZONTAL INSIDE DIAMETER DIMENSION.
- O.D. = THE MAXIMUM HORIZONTAL OUTSIDE DIAMETER DIMENSION.
- H = THE FILL HEIGHT MEASURED VERTICALLY AT ANY POINT ALONG THE PIPE FROM THE TOP OF THE PIPE TO THE TOP OF THE EMBANKMENT AT THAT POINT.

- TAKE CARE TO FULLY COMPACT HAUNCH ZONE OF PIPE BACKFILL.
- LOOSELY PLACED SELECT MATERIAL CLASS III OR CLASS II, TYPE 1 FOR PIPE BEDDING & LEAVE SECTION DIRECTLY BENEATH PIPE UNCOMPACTED AS PIPE SEATING AND BACKFILL WILL ACCOMPLISH COMPACTION.

SHEET 2 OF 3
300D01

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

7-06


ENGLISH DETAIL DRAWING FOR
METHOD OF PIPE INSTALLATION
 RIGID PIPE

SHEET 2 OF 3
300D01

PROJECT SERVICES UNIT
 STANDARDS AND SPECIAL DESIGN
 Office 919-250-4128 FAX 919-250-4119

SEE PLATE FOR TITLE

ORIGINAL BY: K Kempf DATE: 5-15-09
 MODIFIED BY: DATE:
 CHECKED BY: DATE: 7/20/09
 FILE SPEC: enrward/stds/stdstodetails/30001/0300d01.dgn



STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

7-06

ENGLISH DETAIL DRAWING FOR
METHOD OF PIPE INSTALLATION

FILL HEIGHT TABLES

SHEET 3 OF 3
300D01

FLEXIBLE PIPE

Round Corrugated Steel Pipe 2 2/3 x 1/2 corrugation **					
Diameter (inches)	Minimum cover (inches)	Maximum Height of Cover (feet)		Round Corrugated Aluminum Pipe 2 2/3 x 1/2 corrugation **	
		(Ga) 16	(Ga) 14	12	10
12	12	204	256	12	8
15	12	162	204	12	8
18	12	135	169	12	8
21	12	115	145	12	8
24	12	100	126	12	8
30	12	79	100	12	8
36	12	65	83	12	8
42	12	55	70	12	8
48	12	48	61	12	8
54	12	42	54	12	8
60	12	37	48	12	8
66	12	32	42	12	8
72	12	27	37	12	8
78	12	22	32	12	8
84	12	17	27	12	8

Round Corrugated Aluminum Pipe 2 2/3 x 1/2 corrugation **					
Diameter (inches)	Minimum cover (inches)	Maximum Height of Cover (feet)		Round Corrugated Aluminum Pipe 2 2/3 x 1/2 corrugation **	
		(Ga) 16	(Ga) 14	12	10
12	12	123	155	12	8
15	12	98	123	12	8
18	12	81	102	12	8
21	12	69	87	12	8
24	12	60	76	12	8
27	12	53	67	12	8
30	12	47	60	12	8
36	12	40	50	12	8
42	12	35	44	12	8
48	12	30	38	12	8
54	12	26	33	12	8
60	12	22	29	12	8
66	12	18	25	12	8
72	12	15	21	12	8

** FOR DIFFERENT CORRUGATIONS AND ARCH PIPES REFER TO ROADWAY DESIGN MANUAL OR MANUFACTURERS SPECIFICATION.

REFER TO THE FOLLOWING FOR PIPE SPECIFICATIONS

- CSP - AASHTO M36
- CAAP - AASHTO M196
- HDPE - AASHTO M294
- PVC - ASTM F949 or AASHTO M304

NOTES: FILL HEIGHTS SHOWN WERE CALCULATED USING AASHTO LFRD BRIDGE DESIGN SPECIFICATIONS

1' MINIMUM COVER FOR ALL SIDE DRAIN PIPE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS

RIGID PIPE

- RCP - * (Minimum fill) 1' for Class IV & CLASS V
 2' for Class III & Class II
- * (Maximum fill) 10' - Class II pipe
 20' - Class III pipe
 30' - Class IV pipe
 40' - Class V pipe

(For fills > 40' & < 80' use LFRD Direct Design Method)

* FILL HEIGHT IS MEASURED FROM THE TOP OF THE PIPE TO THE BOTTOM OF THE PAVEMENT STRUCTURE

REFER TO THE FOLLOWING FOR PIPE SPECIFICATIONS

- RCP - AASHTO M170

NOTES: FILL HEIGHTS SHOWN WERE CALCULATED USING AASHTO LFRD BRIDGE DESIGN SPECIFICATIONS

1' MINIMUM COVER FOR ALL SIDE DRAIN PIPE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

7-06

ENGLISH DETAIL DRAWING FOR
METHOD OF PIPE INSTALLATION


FILL HEIGHT TABLES

SHEET 3 OF 3
300D01

**PROJECT SERVICES UNIT
 STANDARDS AND SPECIAL DESIGN**
 Office 919-250-4128 FAX 919-250-4119

SEE PLATE FOR TITLE

ORIGINAL BY: KKempf DATE: 5-15-09
 MODIFIED BY: *[Signature]* DATE: *[Signature]*
 CHECKED BY: *[Signature]* DATE: 7/30/09
 FILE SPEC: c:\entoward\stds\stdstodetails\30001\0300d01.dgn



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES


STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C202232

Table with columns: ItemNumber, Sec #, Quantity, Unit, Description. Contains items 0000100000-N through 151900000-E.


Main summary table with columns: ItemNumber, Sec #, Quantity, Unit, Description. Contains items 1560000000-E through 5872200000-E.

Table with columns: ItemNumber, Sec #, Quantity, Unit, Description. Contains items 5872210000-E through 0540000000-E.

*** DESIGN EXCEPTION REQUIRED FOR VERTICAL ALIGNMENT AND VERTICAL STOPPING SIGHT DISTANCE.**



REVISIONS



SR 2054 CHALK RD.	2215 4800	2009 2030	ADT
	515 1000	1777 4200	8523 16600
	7262 13400		SR 2053 JONES DAIRY RD.


-L-
 PI Sta 13+23.38
 $\Delta = 4' 45'' 41.9''$ (RT)
 $D = 0' 57'' 17.7''$
 $L = 498.64'$
 $T = 249.46'$
 $R = 6,000.00'$
 $INC = 25'$
 $RO = \text{SEE PLANS}$

-Y-
 PI Sta 14+80.27
 $\Delta = 24' 08'' 30.6''$ (RT)
 $D = 43' 40'' 51.2''$
 $L = 55.27'$
 $T = 28.05'$
 $R = 131.7'$

NOTES:
 1) SEE SHEET 6 FOR -L- PROFILE
 2) SEE SHEETS S1 - S25 FOR STRUCTURE PLANS
 3) DRIVEWAY RADII ARE 10' UNLESS OTHERWISE NOTED


25-SEP-2009 11:04 P:\PROJECTS\B3919_rdy_psh4.dgn

* DESIGN EXCEPTION REQUIRED FOR VERTICAL ALIGNMENT AND VERTICAL STOPPING SIGHT DISTANCE.



HERITAGE WAKE FOREST
 PIN 1850.06 7806
 DB 1158, PG. 1401
 BM 1992, PG. 839
 BM 2005 PG 2323

BEGIN CONSTRUCTION
 -YI- STA. 11+90.00



- NOTES:**
- 1) SEE SHEET 6 FOR -L- PROFILE
 - 2) SEE SHEET 6 FOR -DR- PROFILE
 - 3) SEE SHEET 6 FOR -YI- PROFILE
 - 4) SEE SHEETS S26 - S51 FOR STRUCTURE PLANS
 - 5) SEE SHEET PMP-4 FOR WHEELCHAIR RAMP LOCATIONS
 - 6) DRIVEWAY RADII ARE 10' UNLESS OTHERWISE NOTED

REVISIONS

8/17/99

28-SEP-2009 15:24:46 0919_rdy_psh5.dgn

HENRY EDWARD JOYNER & WIFE CAROL P. JOYNER
 PIN 1850.016 5402
 DB 2695, PG. 227
 P.B. 1978, PG. 911

HENRY EDWARD JOYNER & WIFE CAROL P. JOYNER
 PIN 1850.01 16 2883
 DB 8386, PG. 93
 BM 1978, PG. 911
 BM 1980, PG. 653

DOROTHY M. AYCOCK PEARCE
 PIN 1850.016 0955
 DB 7332, PG. 771
 BM 1978, PG. 911
 BM 1980, PG. 653

GATEWAY FOREST, LLC
 DB 9440 PG 378
 BM 2001 PG 1555
 BM 2002 PG 876
 * SANITARY SEWER EASEMENT
 INSUFFICIENT INFORMATION ON PLAT
 TO DETERMINE LOCATION
 N.C.D.O.T.
 PSD 222-00-L
 BM 2008 PG 912-918

-BL- 10 POT 38+62.58 =
 -BY9-52- (TIP NO. R-2809C)
 DESTROYED
 REMOVE EXISTING C&G
 -YI- 11+90 TO 12+18 LT.
 AND ADJUST EXISTING CB
 SITE UNDER CONSTRUCTION

QUAIL CROSSING RETAIL
 INVESTORS, LLC
 DB 13418 PG 1794
 BM 2001 PG 1555
 BM 2004 PG 626
 BM 2004 PG 1789
 N.C.D.O.T.
 PSD 222-00-L

-L-
 PI Sta 31+29.48
 Δ = 6° 38' 47.8" (RT)
 D = 2° 51' 53.2"
 L = 232.01'
 T = 116.14'
 R = 2,000.00'

-L-
 PI Sta 38+32.70
 Δ = 0° 35' 42.1" (LT)
 D = 0° 17' 11.3"
 L = 207.70'
 T = 103.85'
 R = 20,000.00'
 INC = 25'
 RO = SEE PLANS

5/28/09

BRIDGE HYDRAULIC DATA

320	DESIGN DISCHARGE = 1180	CFS
	DESIGN FREQUENCY = 25	YR
	DESIGN HW ELEVATION = 252.0	FT
	BASE DISCHARGE = 2325	CFS
310	BASE FREQUENCY = 100	YR
	BASE HW ELEVATION = 254.1	FT
	OVERTOPPING DISCHARGE = 4320	CFS
	OVERTOPPING FREQUENCY = 500++	YR
	OVERTOPPING ELEVATION = 256.2	FT
300	DATE OF SURVEY = 3/11/08	
	NORMAL W.S.ELEVATION = 245.0	FT

-L-

* DESIGN EXCEPTION REQUIRED FOR VERTICAL ALIGNMENT AND VERTICAL STOPPING SIGHT DISTANCE.

PROPOSED 33" BOX BEAM BRIDGE
 1 SPAN @ 85'
 CL -L- STA. 17+55.20
 SKEW = 90°

END GRADE
 BEGIN RESURFACING
 -L- STA. 20+00.00
 ELEV. = 261.37'

END RESURFACING
 -L- STA. 21+25.00


DITCH LEGEND

LEFT DITCH - - - - -
 RIGHT DITCH - - - - -

-Y1-

PI = 12+35.50
 EL = 276.43'
 VC = 35.00'
 K = 32

PI = 12+60.00
 EL = 275.91'
 VC = 14.00'
 K = 5



BEGIN GRADE
 -L- STA. 15+42.50
 ELEV. = 259.37'

BM# 2 RAILROAD SPIKE SET IN A 30" OAK TREE
 -L- STA. 16+97.19 58.16' LT
 ELEV. = 260.43' N 805162 E 2152043

SEE SHEET 4 FOR -L- PLAN

SEE SHEET 5 FOR -Y1- PLAN

REVISIONS

BEGIN GRADE
 -L- STA. 32+50.00
 ELEV. = 287.80'

-L-

END GRADE
 -L- STA. 41+80.00
 ELEV. = 279.73'


-DR-

PI = 35+50.00
 EL = 268.81'
 VC = 432'
 * K = 64
 V = 40 MPH

PROPOSED 39" BOX BEAM BRIDGE
 1 SPAN @ 100'
 CL -L- STA. 38+12.60
 SKEW = 60°

PI = 40+25.00
 EL = 271.10'
 VC = 310'
 * K = 63
 V = 40 MPH

PI = 10+25.00
 EL = 269.00'
 VC = 26'
 K = 5



BRIDGE HYDRAULIC DATA

320	DESIGN DISCHARGE = 1040	CFS
	DESIGN FREQUENCY = 25	YR
	DESIGN HW ELEVATION = 261.2	FT
	BASE DISCHARGE = 1750	CFS
310	BASE FREQUENCY = 100	YR
	BASE HW ELEVATION = 262.4	FT
	OVERTOPPING DISCHARGE = 9000	CFS
	OVERTOPPING FREQUENCY = 500++	YR
	OVERTOPPING ELEVATION = 269.9	FT
300	DATE OF SURVEY = 3/11/08	
	NORMAL W.S.ELEVATION = 253.8	FT

SEE SHEET 5 FOR -L- PLAN

PI = 10+60.00
 EL = 265.13'
 VC = 12'
 K = 1

SEE SHEET 5 FOR -DR- PLAN

11-SEP-2009 13:12 \\fs3919_rdu-pl.dgn