

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	2,100 CY		
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	50 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,500 SY		
0008	0255000000-E	SP	GENERIC GRADING ITEM CLASS IV SELECT MATERIAL	450 TON		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	70 SY		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
0012	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	76 LF		
0013	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	20 LF		
0014	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	80 LF		
0015	0938000000-E	320	*** X *** CS STRUCTURAL PLATE PIPE ARCH, ** GAUGE (142" X 91", 10)	96 LF		
0016	1077000000-E	SP	#57 STONE	10 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	185	SY	
001S	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,580	TON	
002C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,400	TON	
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	815	TON	
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	230	TON	
0023	2022000000-E	815	SUBDRAIN EXCAVATION	40	CY	
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	30	CY	
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	175	LF	
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6	EA	
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
002S	2253000000-E	840	PIPE COLLARS	1.2	CY	
003C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
0031	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.4	LF	
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	1	EA	
003E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	150	LF	
0034	2591000000-E	848	4" CONCRETE SIDEWALK	70	SY	
003E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	2	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3030000000-E	862	STEEL BM GUARDRAIL	487.5	LF	
0037	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50	LF	
0038	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	3	EA	
0039	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0040	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
0041	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2	EA	
0042	3628000000-E	876	RIP RAP, CLASS I	26	TON	
0043	3635000000-E	876	RIP RAP, CLASS II	475	TON	
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	795	SY	
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48	SF	
0046	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	80	SF	
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20	SF	
0048	4435000000-N	1135	CONES	60	EA	
0049	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
0050	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	317	LF	
0051	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8	EA	
0052	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	4	EA	
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,944	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	25 LF		
005E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	2 EA		
005E	5691500000-E	1520	12" SANITARY GRAVITY SEWER	554 LF		
0057	5775000000-E	1525	4' DIA UTILITY MANHOLE	2 EA		
005E	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	4.7 LF		
005E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	556 LF		
006C	5816000000-N	1530	ABANDON UTILITY MANHOLE	1 EA		
0061	6000000000-E	1605	TEMPORARY SILT FENCE	1,700 LF		
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	135 TON		
006E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	305 TON		
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	135 TON		
006E	6015000000-E	1615	TEMPORARY MULCHING	11 ACR		
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300 LB		
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.25 TON		
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
006E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
007C	6029000000-E	SP	SAFETY FENCE	1,200 LF		
0071	6030000000-E	1630	SILT EXCAVATION	1,600 CY		
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,150 SY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6037000000-E	SP	COIR FIBER MAT	50 SY		
0074	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	3,005 SY		
0075	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0076	6046000000-E	SP	TEMPORARY PIPE FOR STREAM CROSSING	20 LF		
0077	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0078	6071030000-E	SP	COIR FIBER BAFFLES	650 LF		
0079	6071050000-E	SP	*** SKIMMER (1-1/2")	8 EA		
0080	6084000000-E	1660	SEEDING & MULCHING	12 ACR		
0081	6087000000-E	1660	MOWING	5 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	5.5 TON		
0086	6114500000-N	SP	SPECIALIZED HAND MOWING	5 MHR		
0087	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0088	6123000000-E	1670	REFORESTATION	0.25 ACR		
0089	8070000000-E	410	FOUNDATION EXCAVATION	25 CY		
0090	8196000000-E	420	CLASS A CONCRETE (CULVERT)	32 CY		
0091	8245000000-E	425	REINFORCING STEEL (CULVERT)	2,581 LB		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8594000000-E	876	RIP RAP, CLASS B	20		
				TON		

1145/Nov09/Q46297.05/D354950180000/E92

Total Amount Of Bid For Entire Project :

Contract No **C202461**

County (ies): **Wake**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General