

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM BUILDING SURVEYS	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	6,900 CY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+47.50)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0009	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	180 SY		
0010	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITION MATE- RIAL, MINOR STRS	60 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	180 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0013	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	76 LF		
0014	0762000000-E	310	66" BIT COAT CS PIPE CULVERTS, TYPE B 0.138" THICK	172 LF		
0015	0986000000-E	SP	GENERIC PIPE ITEM 16" DUCTILE IRON PIPE	48 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	570 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	380 TON		
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	50 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2209000000-E	838	ENDWALLS	1 CY		
0029	2220000000-E	838	REINFORCED ENDWALLS	6.6 CY		
0030	2253000000-E	840	PIPE COLLARS	0.45 CY		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0032	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	11.834 CY		
0033	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.5 LF		
0034	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	7 EA		
0035	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0036	2556000000-E	846	SHOULDER BERM GUTTER	410 LF		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3030000000-E	862	STEEL BM GUARDRAIL	537.5		
					LF	
0038	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		
					EA	
0039	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4		
					EA	
0040	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		
					EA	
0041	3649000000-E	876	RIP RAP, CLASS B	2		
					TON	
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,760		
					SY	
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	152		
					SF	
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96		
					SF	
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20		
					SF	
0046	4430000000-N	1130	DRUMS	30		
					EA	
0047	4435000000-N	1135	CONES	20		
					EA	
0048	4445000000-E	1145	BARRICADES (TYPE III)	48		
					LF	
0049	4450000000-N	1150	FLAGGER	6,400		
					HR	
0050	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1		
					EA	
0051	4480000000-N	1165	TMIA	1		
					EA	
0052	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	60		
					LF	
0053	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	5,185		
					LF	
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,000		
					LF	
0055	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	32		
					EA	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6000000000-E	1605	TEMPORARY SILT FENCE	2,300 LF		
0057	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	430 TON		
0058	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	280 TON		
0059	6012000000-E	1610	SEDIMENT CONTROL STONE	900 TON		
0060	6015000000-E	1615	TEMPORARY MULCHING	7.5 ACR		
0061	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0062	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.75 TON		
0063	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0064	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0065	6029000000-E	SP	SAFETY FENCE	2,000 LF		
0066	6030000000-E	1630	SILT EXCAVATION	600 CY		
0067	6036000000-E	1631	MATTING FOR EROSION CONTROL	12,000 SY		
0068	6037000000-E	SP	COIR FIBER MAT	400 SY		
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	2,100 LF		
0070	6070000000-N	SP	SPECIAL STILLING BASINS	15 EA		
0071	6071010000-E	SP	WATTLE	150 LF		
0072	6071020000-E	SP	POLYACRYLAMIDE (PAM)	40 LB		
0073	6071030000-E	SP	COIR FIBER BAFFLES	150 LF		
0074	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0075	6084000000-E	1660	SEEDING & MULCHING	5 ACR		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6087000000-E	1660	MOWING	4.5	ACR	
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0078	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0079	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125	LB	
0080	6108000000-E	1665	FERTILIZER TOPDRESSING	3.25	TON	
0081	6114500000-N	SP	SPECIALIZED HAND MOWING	10	MHR	
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27	EA	
0083	6123000000-E	1670	REFORESTATION	0.5	ACR	

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
 \*\*\*\*\* ( 3 ALTERNATES ) \*\*\*\*\*

0084	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	22	LF	
<b>AA1</b>						
*** OR ***						
0085	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	10	LF	
<b>AA2</b>						
0086	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	12	LF	
<b>AA2</b>						
*** OR ***						
0087	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	10	LF	
<b>AA3</b>						
0088	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	12	LF	
<b>AA3</b>						

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

WALL ITEMS

0089	8077000000-E	410	FOUNDATION EXCAVATION (RETAINING WALL)	60	CY	
------	--------------	-----	--	----	----	--

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8203000000-E	420	CLASS A CONCRETE (RETAINING WALL)	14.5 CY		
0091	8252000000-E	425	REINFORCING STEEL (RETAINING WALL)	1,080 LB		
<b>STRUCTURE ITEMS</b>						
0092	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+47.50-L-)	Lump Sum	L.S.	
0093	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+47.50-L-)	Lump Sum	L.S.	
0094	8070000000-E	410	FOUNDATION EXCAVATION	330 CY		
0095	8105500000-E	SP	***_*** DIA DRILLED PIERS IN SOIL (6'-0")	29.9 LF		
0096	8105600000-E	SP	***_*** DIA DRILLED PIERS NOT IN SOIL (6'-0")	51 LF		
0097	8111000000-E	SP	PERMANENT STEEL CASING FOR ***_*** DIA DRILLED PIER (6'-0")	14.9 LF		
0098	8113000000-N	SP	SID INSPECTION	2 EA		
0099	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0100	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+47.50-L-)	Lump Sum	L.S.	
0101	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	13,764 SF		
0102	8161000000-E	420	GROOVING BRIDGE FLOORS	11,970 SF		
0103	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	301.7 CY		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+47.50-L-)	Lump Sum	L.S.	
0105	8217000000-E	425	REINFORCING STEEL (BRIDGE)	59,748 LB		
0106	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	7,290 LB		
0107	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	1,351.5 LF		
0108	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0109	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0110	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (17+47.50-L-)	Lump Sum	L.S.	
0111	8867000000-E	SP	GENERIC STRUCTURE ITEM CLASSIC CONCRETE BRIDGE RAIL	907.33 LF		

1204/Dec04/Q154940.464/D487558710000/E111

Total Amount Of Bid For Entire Project :

**Contract No**     **C202165**

**County (ies):**   **Ashe**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General