

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13+48.95)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	100 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	70 SY		
0010	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS	40 TON		
0011	0335200000-E	SP	15" DRAINAGE PIPE	16 LF		
0012	0986000000-E	SP	GENERIC PIPE ITEM 18" CS PIPE CULVERTS 0.064" THICK	94 LF		
0013	0986000000-E	SP	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	72 LF		
0014	0992000000-E	SP	GENERIC PIPE ITEM CS PIPE TEES (18" X 18" X 18", 0.064")	2 EA		
0015	0995000000-E	340	PIPE REMOVAL	238 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	150 TON		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	40 TON		
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	80 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	15 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	65 TON		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2253000000-E	840	PIPE COLLARS	0.45 CY		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0031	3435000000-N	SP	GENERIC GUARDRAIL ITEM IMPACT ATTENUATOR UNIT, TYPE 350 (TL-2)	2 EA		
0032	3628000000-E	876	RIP RAP, CLASS I	30 TON		
0033	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	705 SY		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	410 SF		
0036	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	100 SF		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	90 SF		
0038	4430000000-N	1130	DRUMS	20 EA		
0039	4435000000-N	1135	CONES	25 EA		
0040	4445000000-E	1145	BARRICADES (TYPE III)	40 LF		
0041	4450000000-N	1150	FLAGGER	200 HR		
0042	4507000000-E	SP	WATER FILLED BARRIER	250 LF		
0043	4508000000-E	SP	RESET WATER FILLED BARRIER	850 LF		
0044	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	2,600 LF		
0045	4795000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (24") (IV)	50 LF		
0046	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,600 LF		
0047	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,200 LF		
0048	5325800000-E	1510	8" WATER LINE	180 LF		
0049	5546000000-E	1515	8" VALVE	1 EA		
0050	5571800000-E	1515	8" TAPPING VALVE	1 EA		
0051	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0052	5801000000-E	1530	ABANDON 8" UTILITY PIPE	180 LF		
0053	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	20 LF		
0054	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	20 LF		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6000000000-E	1605	TEMPORARY SILT FENCE	100 LF		
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	300 TON		
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	150 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0062	6024000000-E	1622	TEMPORARY SLOPE DRAINS	225 LF		
0063	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0064	6029000000-E	SP	SAFETY FENCE	650 LF		
0065	6030000000-E	1630	SILT EXCAVATION	250 CY		
0066	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,800 SY		
0067	6037000000-E	SP	COIR FIBER MAT	20 SY		
0068	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200 SY		
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	625 LF		
0070	6071010000-E	SP	WATTLE	100 LF		
0071	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
0072	6071030000-E	SP	COIR FIBER BAFFLES	150 LF		
0073	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0075	6087000000-E	1660	MOWING	0.5 ACR		
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0078	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0080	6114500000-N	SP	SPECIALIZED HAND MOWING	20 MHR		
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0082	6123000000-E	1670	REFORESTATION	0.1 ACR		
0083	7993000000-N	SP	GENERIC SIGNAL ITEM PORTABLE TRAFFIC SIGNAL SYSTEM	20 DAY		
STRUCTURE ITEMS						
0084	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+48.95-L-)	Lump Sum	L.S.	
0085	8096000000-E	SP	PILE EXCAVATION IN SOIL	145 LF		
0086	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	45 LF		
0087	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (13+48.95-L-)	Lump Sum	L.S.	
0088	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	36.9 CY		
0089	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+48.95-L-)	Lump Sum	L.S.	
0090	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,938 LB		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8364000000-E	SP	HP12X53 STEEL PILES	150 LF		
0092	8365000000-E	SP	HP12X53 GALVANIZED STEEL PILES	225 LF		
0093	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	121.5 LF		
0094	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	141 TON		
0095	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	157 SY		
0096	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0097	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	607.5 LF		
0098	8892000000-E	SP	GENERIC STRUCTURE ITEM 18" GALVANIZED STEEL SHEET PILES	955 SF		

0750/Dec08/Q28522.15/D450258520000/E98

Total Amount Of Bid For Entire Project :

Contract No **C202269**

County (ies): **Buncombe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General