

County : Chowan

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0001000000-E | 200 | CLEARING & GRUBBING .. ACRE(S) | Lump Sum | L.S. | |
| 0003 | 0008000000-E | 200 | SUPPLEMENTARY CLEARING & GRUBBING | 1 ACR | | |
| 0004 | 0022000000-E | 225 | UNCLASSIFIED EXCAVATION | 1,550 CY | | |
| 0005 | 0030000000-N | SP | BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (22+92) | Lump Sum | L.S. | |
| 0006 | 0036000000-E | 225 | UNDERCUT EXCAVATION | 450 CY | | |
| 0007 | 0106000000-E | 230 | BORROW EXCAVATION | 5,200 CY | | |
| 0008 | 0127000000-N | SP | EMBANKMENT SETTLEMENT GAUGES | 12 EA | | |
| 0009 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 11 CY | | |
| 0010 | 0177000000-E | 250 | BREAKING OF EXISTING ASPHALT PAVEMENT | 2,040 SY | | |
| 0011 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 4,100 SY | | |
| 0012 | 0234000000-E | SP | GENERIC GRADING ITEM SELECT GRANULAR MATERIAL, CLASS III | 400 CY | | |
| 0013 | 0241000000-E | SP | GENERIC GRADING ITEM FABRIC FOR EMBANKMENT STABILIZATION | 4,500 SY | | |
| 0014 | 0255000000-E | SP | GENERIC GRADING ITEM LIGHTWEIGHT AGGREGATE | 3,300 TON | | |
| 0015 | 0320000000-E | SP | FOUNDATION CONDITIONING FABRIC | 150 SY | | |
| 0016 | 0330000000-E | SP | GENERIC DRAINAGE ITEM FOUNDATION COND MATERIAL, MINOR STRS | 28 TON | | |
| 0017 | 0335200000-E | SP | 15" DRAINAGE PIPE | 44 LF | | |

County : Chowan

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 001E | 0986000000-E | SP | GENERIC PIPE ITEM 15" SIDE DRAIN PIPE | 20 LF | | |
| 001E | 0995000000-E | 340 | PIPE REMOVAL | 20 LF | | |
| 002C | 1011000000-N | 500 | FINE GRADING | Lump Sum | L.S. | |
| 0021 | 1121000000-E | 520 | AGGREGATE BASE COURSE | 1,136 TON | | |
| 0022 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 10 TON | | |
| 0023 | 1275000000-E | 600 | PRIME COAT | 823 GAL | | |
| 0024 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 70 TON | | |
| 002E | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 380 TON | | |
| 002E | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 30 TON | | |
| 0027 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 23 CY | | |
| 002E | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 17 CY | | |
| 002E | 2044000000-E | 815 | 6" PERFORATED SUBDRAIN PIPE | 100 LF | | |
| 003C | 2055000000-E | 815 | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 3 EA | | |
| 0031 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 1 EA | | |
| 0032 | 2077000000-E | 815 | 6" OUTLET PIPE (SUBDRAINS) | 6 LF | | |
| 0033 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 2 EA | | |
| 0034 | 2473000000-N | SP | GENERIC DRAINAGE ITEM BICYCLE SAFE STEEL GRATE & FRAME | 2 EA | | |
| 003E | 2556000000-E | 846 | SHOULDER BERM GUTTER | 28 LF | | |

County : Chowan

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 003E | 3030000000-E | 862 | STEEL BM GUARDRAIL | 350 LF | | |
| 0037 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 003E | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 4 EA | | |
| 003E | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 004C | 3649000000-E | 876 | RIP RAP, CLASS B | 5 TON | | |
| 0041 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 510 SY | | |
| 0042 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 231 SF | | |
| 0043 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 94 SF | | |
| 0044 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 96 LF | | |
| 004E | 5325600000-E | 1510 | 6" WATER LINE | 1,292 LF | | |
| 004E | 5540000000-E | 1515 | 6" VALVE | 2 EA | | |
| 0047 | 5649000000-N | 1515 | RECONNECT WATER METER | 1 EA | | |
| 004E | 5672000000-N | 1515 | RELOCATE FIRE HYDRANT | 1 EA | | |
| 004E | 5800000000-E | 1530 | ABANDON 6" UTILITY PIPE | 1,275 LF | | |
| 005C | 5871400000-E | 1550 | TRENCHLESS INSTALLATION OF 6" IN SOIL | 482 LF | | |
| 0051 | 5871410000-E | 1550 | TRENCHLESS INSTALLATION OF 6" NOT IN SOIL | 482 LF | | |
| 0052 | 5882000000-N | SP | GENERIC UTILITY ITEM 6" INSERT GATE VALVE & VALVE BOX, 150#WP | 2 EA | | |
| 0053 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 2,900 LF | | |

County : Chowan

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0054 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 225 TON | | |
| 005E | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 165 TON | | |
| 005E | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 225 TON | | |
| 0057 | 6015000000-E | 1615 | TEMPORARY MULCHING | 3.5 ACR | | |
| 005E | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 100 LB | | |
| 005E | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.5 TON | | |
| 006C | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 200 LF | | |
| 0061 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 4 EA | | |
| 0062 | 6029000000-E | SP | SAFETY FENCE | 5,750 LF | | |
| 0063 | 6030000000-E | 1630 | SILT EXCAVATION | 150 CY | | |
| 0064 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 6,300 SY | | |
| 006E | 6037000000-E | SP | COIR FIBER MAT | 10 SY | | |
| 006E | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 220 SY | | |
| 0067 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 850 LF | | |
| 006E | 6048000000-E | SP | FLOATING TURBIDITY CURTAIN | 50 SY | | |
| 006E | 6071010000-E | SP | WATTLE | 60 LF | | |
| 007C | 6071020000-E | SP | POLYACRYLAMIDE (PAM) | 15 LB | | |
| 0071 | 6071030000-E | SP | COIR FIBER BAFFLES | 200 LF | | |
| 0072 | 6084000000-E | 1660 | SEEDING & MULCHING | 5 ACR | | |

County : Chowan

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|-------------------------------|----------|-----------|--------|
| 0073 | 6087000000-E | 1660 | MOWING | 1.5 | ACR | |
| 0074 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 | LB | |
| 0075 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 | TON | |
| 0076 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 75 | LB | |
| 0077 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 2 | TON | |
| 0078 | 6114500000-N | SP | SPECIALIZED HAND MOWING | 12 | MHR | |
| 0079 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 12 | EA | |

STRUCTURE ITEMS

| | | | | | | |
|------|--------------|-----|--|----------|------|--|
| 008C | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+92.00-L-) | Lump Sum | L.S. | |
| 0081 | 8119000000-E | 412 | UNCLASSIFIED STRUCTURE EXCAVATION | 619 | CY | |
| 0082 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 87.1 | CY | |
| 0083 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (22+92.00-L-) | Lump Sum | L.S. | |
| 0084 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 13,748 | LB | |
| 008E | 8364000000-E | SP | HP12X53 STEEL PILES | 725 | LF | |
| 008E | 8365000000-E | SP | HP12X53 GALVANIZED STEEL PILES | 2,660 | LF | |
| 0087 | 8384200000-E | SP | HP14X73 GALVANIZED STEEL PILES | 570 | LF | |
| 008E | 8393000000-N | SP | PILE REDRIVES | 44 | EA | |
| 0089 | 8475000000-E | 460 | TWO BAR METAL RAIL | 459.42 | LF | |

County : Chowan

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|---|--------------|-------|--|---|-----------|--------|
| 009C | 8517000000-E | 460 | 1'-***"X *****" CONCRETE PARA- PET (1'-2" X 2'-7 1/2") | 479.75 LF | | |
| 0091 | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 253 TON | | |
| 0092 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 281 SY | | |
| 0093 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0094 | 8755000000-E | 430 | 3'-0" X 1'-6" PRESTRESSED CONC CORED SLABS | 2,631.75 LF | | |
| 0855/Dec10/Q69444.07/D401480470000/E94 | | | | Total Amount Of Bid For Entire Project : | | |

Contract No **C202270**

County (ies): **Chowan**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General