

County : Pender, Duplin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	17,299 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	3,000 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	88.24 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	62,406 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1/2" TO 1-1/4")	612,877 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	5,908 SY		
0008	1539000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S12.5C	135,804 TON		
0009	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	7,561 TON		
001C	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	2,006 TON		
0011	1662000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1 MODIFIED	1,129 TON		
0012	1663000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED	32,223 TON		
0013	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	424,302 LF		
0014	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S12.5C (LEVELING COURSE)	1,680 TON		
0015	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	443 TON		
0016	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	4,420 TON		

County : Pender, Duplin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1880000000-E	SP	GENERIC PAVING ITEM WEDGING EXISTING PAVEMENT	60 TON		
001E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	40 EA		
001E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
002C	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0021	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	800 LF		
0022	3420000000-E	SP	GENERIC GUARDRAIL ITEM REPAIR STEEL BEAM GUARDRAIL	800 LF		
002E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0024	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
002E	4480000000-N	1165	TMIA	3 EA		
002E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	199 EA		
0027	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	60 LF		
002E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	39 EA		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	31 EA		
003C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	954,678 LF		
0031	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	9,342 LF		
0032	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	60 LF		
003E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	18 EA		

County : Pender, Duplin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	31	EA	
0035	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	525,914	LF	
0036	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)	12,142	LF	
0037	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM SHOULDER MARKER FOR DRAINS 90 MILS	51	EA	
0038	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	5,105	EA	
0039	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	3,307	EA	
0040	6000000000-E	1605	TEMPORARY SILT FENCE	4,018	LF	
0041	6015000000-E	1615	TEMPORARY MULCHING	40.18	ACR	
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,004.5	LB	
0043	6036000000-E	1631	MATTING FOR EROSION CONTROL	200	SY	
0044	6084000000-E	1660	SEEDING & MULCHING	66.19	ACR	
0045	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	120	LF	
0046	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	400	LF	

0938/Nov30/Q2829699.11/D166085320000/E46

Total Amount Of Bid For Entire Project :

**Contract No**     **C202491**

**County (ies):**   **Pender, Duplin**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General