

County : Vance, Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	991 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	635 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	49.52 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	62,452 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	10,500 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	2,739 SY		
0008	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	640 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	12,368 TON		
0010	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	19,729 TON		
0011	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,051 TON		
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	2,860 TON		
0013	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	3 EA		
0014	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0015	2830000000-N	858	ADJUSTMENT OF MANHOLES	27 EA		
0016	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	35 EA		
0017	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	272,748 LF		
0018	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	241,716 LF		

County : Vance, Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	670 LF		
0020	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	250 LF		
0021	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,193 LF		
0022	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	10 EA		
0023	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	135 EA		
0024	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	94,244 LF		
0025	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	50 LF		
0026	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,896 EA		
0027	6084000000-E	1660	SEEDING & MULCHING	29.5 ACR		
0028	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,670 LF		
0029	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	800 LF		

1320/Dec09/Q734493.02/D9385410000/E29

Total Amount Of Bid For Entire Project :

Contract No **C202511**

County (ies): **Vance & Warren**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General