

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	522 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	665 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	26.1 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	146,884 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	16,916 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	778 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3")	118,691 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	3,381 SY		
0010	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	651 TON		
0011	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,500 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	40,739 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,588 TON		
0014	1704000000-E	SP	PATCHING EXISTING PAVEMENT	9,264 TON		
0015	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	6 EA		
0016	2830000000-N	858	ADJUSTMENT OF MANHOLES	38 EA		
0017	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	42 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	141,536 LF		
0019	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	232,077 LF		
0020	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	5,070 LF		
0021	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	200 LF		
0022	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	4,070 LF		
0023	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	80 EA		
0024	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	544 EA		
0025	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	2,015 LF		
0026	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	117,759 LF		
0027	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	4,810 LF		
0028	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	150 LF		
0029	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	3,978 LF		
0030	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	64 EA		
0031	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	481 EA		
0032	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,015 LF		
0033	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3,232 EA		
0034	6084000000-E	1660	SEEDING & MULCHING	19.1 ACR		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	20,178 LF		
0928/Dec14/Q881970.2/D115118100000/E35			Total Amount Of Bid For Entire Project :			

Contract No **C202513**

County (ies): **Wake**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General