

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+45.50)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	100 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	60 SY		
0010	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0011	0335200000-E	SP	15" DRAINAGE PIPE	124 LF		
0012	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0013	0986000000-E	SP	GENERIC PIPE ITEM 18" CS PIPE CULVERTS 0.064" THICK	52 LF		
0014	0995000000-E	340	PIPE REMOVAL	48 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	318 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	250 TON		

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	532 TON		
001S	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	58 TON		
002C	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	14 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	25 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	90 CY		
002S	2033000000-E	815	SUBDRAIN FINE AGGREGATE	70 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	400 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	12 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002S	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
003C	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0032	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
003S	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77, SHOP CURVED)	1 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	3	EA	
0037	3563000000-E	SP	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (48")	150	LF	
0038	3628000000-E	876	RIP RAP, CLASS I	50	TON	
0039	3649000000-E	876	RIP RAP, CLASS B	10	TON	
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,145	SY	
0041	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	675	SF	
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	112	SF	
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	223	SF	
0045	4430000000-N	1130	DRUMS	50	EA	
0046	4435000000-N	1135	CONES	50	EA	
0047	4445000000-E	1145	BARRICADES (TYPE III)	160	LF	
0048	4450000000-N	1150	FLAGGER	960	HR	
0049	4480000000-N	1165	TMIA	1	EA	
0050	4507000000-E	SP	WATER FILLED BARRIER	208	LF	
0051	4508000000-E	SP	RESET WATER FILLED BARRIER	208	LF	
0052	4516000000-N	1180	SKINNY DRUM	50	EA	
0053	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	30	EA	

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,028	LF	
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,952	LF	
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,400	LF	
0057	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	22	LF	
005E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	20	EA	
005E	6000000000-E	1605	TEMPORARY SILT FENCE	1,600	LF	
006C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	300	TON	
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200	TON	
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	300	TON	
006E	6015000000-E	1615	TEMPORARY MULCHING	3.5	ACR	
0064	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5	TON	
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	250	LF	
0067	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
006E	6029000000-E	SP	SAFETY FENCE	700	LF	
006E	6030000000-E	1630	SILT EXCAVATION	420	CY	
007C	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,000	SY	
0071	6037000000-E	SP	COIR FIBER MAT	100	SY	

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	440 SY		
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
0074	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0075	6071010000-E	SP	WATTLE	200 LF		
0076	6071020000-E	SP	POLYACRYLAMIDE (PAM)	50 LB		
0077	6071030000-E	SP	COIR FIBER BAFFLES	300 LF		
0078	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0079	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0080	6087000000-E	1660	MOWING	2 ACR		
0081	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0082	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0083	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0084	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0085	6114500000-N	SP	SPECIALIZED HAND MOWING	20 MHR		
0086	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0087	6123000000-E	1670	REFORESTATION	0.2 ACR		
<b>STRUCTURE ITEMS</b>						
0088	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14 + 45.50-L-)	Lump Sum	L.S.	

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+45.50-L-)	Lump Sum	L.S.	
009C	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	93.6 LF		
0091	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	24 LF		
0092	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	30.6 LF		
009E	8113000000-N	SP	SID INSPECTION	1 EA		
0094	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
009E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+45.50-L-)	Lump Sum	L.S.	
009E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	60.5 CY		
0097	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+45.50-L-)	Lump Sum	L.S.	
009E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	18,587 LB		
009E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,661 LB		
010C	8364000000-E	SP	HP12X53 STEEL PILES	330 LF		
0101	8391000000-N	SP	STEEL PILE POINTS	12 EA		
0102	8503000000-E	460	CONCRETE BARRIER RAIL	248.94 LF		
010E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	180 TON		
0104	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	200 SY		
010E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010€	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	1,493.63 LF		

1605/Jan08/Q56602.72/D482209100000/E106

Total Amount Of Bid For Entire Project :

**Contract No**     **C202324**

**County (ies):**   **Avery**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General