

January 12, 2010

PROJECT: R-5202

COUNTY: Jackson

PROJECT SPECIAL PROVISIONS

Utility

The Utility Companies that have facilities on this project that will be in conflict with the construction of the project are:

1. Duke Power
2. Verizon Telephone

The conflicting facilities will be adjusted prior to availability date unless otherwise noted. All utilities shown on the plans are from the best available information.

Contractor's attention is directed to Article 105.8 of the *2006 Standard Specifications*.

The contractor shall submit a Progress Schedule for review and approval no later than 7 days prior to the date of the project preconstruction conference as required by the Contract Special Provisions. The Utility Companies will be provided a copy of this by the Resident Engineer prior to the preconstruction meeting so that phasing and construction around the areas of conflict can be discussed and understood by all parties involved. A separate utility preconstruction conference shall be scheduled, to be held on the project, prior to beginning construction and subsequent meetings shall be held as need to facilitate timely relocation of facilities while minimizing delays to the contractor's planned phasing of work.

Utilities Requiring Adjustment

Rough grading shall be completed in areas of conflict and a 14 day notice provided to both Duke Power and Verizon Telephone. The utility companies shall be given 30 days to clear conflicts as listed below:

- 30 ft. Service pole on drive RT. Of Sta. 14+70
- Double circuit pole and anchor at Sta. 18+75. Anchor relocation will be necessary. Span Guy will need to be installed across road.
- 30 ft. Span Guy pole at Sta. 28+10. Verizon may have vertical clearance issue and require relocation
- School Warning signal Sta. 34+21. Relocation of sign will be necessary and shall be coordinated with NCDOT.

- Culvert extension Sta. 44+00. Relocation of pole necessary to allow construction of wingwall. Contractor may be able to begin culvert extension while avoiding existing pole, but should be aware of time needed to relocate prior to excavation and construction of wingwall.

Contractor's attention also directed to fact that blasting will be necessary in and around existing utilities. Preblast meetings with Utilities shall be held to discuss contractor's methods to protect all utilities from damage due to blasting.