

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+50)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
000E	0063000000-N	SP	GRADING	Lump Sum	L.S.	
000E	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	350 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
000E	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	40 SY		
001C	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	15 TON		
0011	0335200000-E	SP	15" DRAINAGE PIPE	52 LF		
0012	0986000000-E	SP	GENERIC PIPE ITEM 15" RC PIPE CULVERTS, CLASS IV	64 LF		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	560 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	410 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	55 TON		
001E	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42		CY
001E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250		LF
002C	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9		EA
0021	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1		EA
0022	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6		LF
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4		EA
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4		EA
002E	2556000000-E	846	SHOULDER BERM GUTTER	96		LF
002E	3030000000-E	862	STEEL BM GUARDRAIL	600		LF
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3		EA
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4		EA
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		EA
003C	3628000000-E	876	RIP RAP, CLASS I	5		TON
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	465		SY
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	574		SF
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119		SF
0034	4445000000-E	1145	BARRICADES (TYPE III)	96		LF
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,480		LF

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,480	LF	
0037	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	9	EA	
0038	6000000000-E	1605	TEMPORARY SILT FENCE	1,850	LF	
0039	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0040	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50	TON	
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	140	TON	
0042	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0043	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0045	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0046	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0047	6029000000-E	SP	SAFETY FENCE	400	LF	
0048	6030000000-E	1630	SILT EXCAVATION	100	CY	
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,575	SY	
0050	6042000000-E	1632	1/4" HARDWARE CLOTH	550	LF	
0051	6071030000-E	SP	COIR FIBER BAFFLES	30	LF	
0052	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0053	6087000000-E	1660	MOWING	1	ACR	
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75	TON	
005E	6114500000-N	SP	SPECIALIZED HAND MOWING	10	MHR	
005E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
STRUCTURE ITEMS						
006C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 50.00-L-)	Lump Sum	L.S.	
0061	8112730000-N	SP	PDA TESTING	5	EA	
0062	8112740000-N	SP	PDA ASSISTANCE	5	EA	
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	55	CY	
0064	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 50.00-L-)	Lump Sum	L.S.	
006E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,564	LB	
006E	8336000000-E	SP	20" PRESTRESSED CONC PILES	840	LF	
0067	8364000000-E	SP	HP12X53 STEEL PILES	850	LF	
006E	8393000000-N	SP	PILE REDRIVES	5	EA	
006E	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	255.5	LF	
007C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	205	TON	
0071	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	225	SY	

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0073	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,402.5 LF		

0756/Jan06/Q32084.75/D326443300000/E73

Total Amount Of Bid For Entire Project :

Contract No **C202329**

County (ies): **Scotland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General