

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+27.50)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	500 CY		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	8,500 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	60 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	80 SY		
0010	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS	30 TON		
0011	0335200000-E	SP	15" DRAINAGE PIPE	144 LF		
0012	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	76 LF		
0014	0995000000-E	340	PIPE REMOVAL	86 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	170 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	870 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	450 TON		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	70 TON		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	8 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0028	2556000000-E	846	SHOULDER BERM GUTTER	41 LF		
0029	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0033	3649000000-E	876	RIP RAP, CLASS B	544 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,815 SY		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	192 SF		
0036	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0037	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6000000000-E	1605	TEMPORARY SILT FENCE	1,350 LF		
0039	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	300 TON		
0040	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	300 TON		
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	350 TON		
0042	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0043	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2 TON		
0045	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0046	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0047	6029000000-E	SP	SAFETY FENCE	1,000 LF		
0048	6030000000-E	1630	SILT EXCAVATION	715 CY		
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,700 SY		
0050	6037000000-E	SP	COIR FIBER MAT	65 SY		
0051	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	350 SY		
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	460 LF		
0053	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0054	6071010000-E	SP	WATTLE	425 LF		
0055	6071020000-E	SP	POLYACRYLAMIDE (PAM)	110 LB		
0056	6071030000-E	SP	COIR FIBER BAFFLES	625 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0058	6084000000-E	1660	SEEDING & MULCHING	8 ACR		
0059	6087000000-E	1660	MOWING	2 ACR		
0060	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0064	6114500000-N	SP	SPECIALIZED HAND MOWING	15 MHR		
0065	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0066	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+27.50-L-)	Lump Sum	L.S.	
0067	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+27.50-L-)	Lump Sum	L.S.	
0068	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	14.8 LF		
0069	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	40 LF		
0070	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	17.8 LF		
0071	8113000000-N	SP	SID INSPECTION	1 EA		
0072	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15+27.50-L-)	Lump Sum	L.S.	
0074	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	7,722 SF		
0075	8161000000-E	420	GROOVING BRIDGE FLOORS	6,459 SF		
0076	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	67.2 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+27.50-L-)	Lump Sum	L.S.	
0078	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,460 LB		
0079	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,636 LB		
0080	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	1,042.01 LF		
0081	8364000000-E	SP	HP12X53 STEEL PILES	175 LF		
0082	8503000000-E	460	CONCRETE BARRIER RAIL	524.67 LF		
0083	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	385 TON		
0084	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	428 SY		
0085	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0086	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1427/Jan11/Q63213.73/D40611410000/E86

Total Amount Of Bid For Entire Project :

Contract No **C202166**

County (ies): **Stanly**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General