

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+54.00 -L-)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	150 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
0009	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	10 SY		
0010	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0011	0335200000-E	SP	15" DRAINAGE PIPE	28 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	390 TON		
0014	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	230 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35 TON		
0016	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	7 EA		
0018	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0020	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0021	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0022	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0025	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0026	3030000000-E	862	STEEL BM GUARDRAIL	25 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	2 EA		
0028	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0029	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0030	3649000000-E	876	RIP RAP, CLASS B	22 TON		
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	540 SY		
0032	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0033	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	480 SF		
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	90 SF		
0035	4445000000-E	1145	BARRICADES (TYPE III)	40 LF		
0036	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,100 LF		
0037	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,100 LF		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	44,620	LF	
0039	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	90	LF	
0040	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	170	LF	
0041	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	16	EA	
0042	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	7	EA	
0043	6000000000-E	1605	TEMPORARY SILT FENCE	1,000	LF	
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	145	TON	
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	115	TON	
0047	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0049	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0051	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0052	6029000000-E	SP	SAFETY FENCE	950	LF	
0053	6030000000-E	1630	SILT EXCAVATION	320	CY	
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,650	SY	
0055	6037000000-E	SP	COIR FIBER MAT	50	SY	
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	400	LF	

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6071030000-E	SP	COIR FIBER BAFFLES	150 LF		
0058	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0059	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0060	6087000000-E	1660	MOWING	1 ACR		
0061	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0062	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0063	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0064	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0065	6114500000-N	SP	SPECIALIZED HAND MOWING	12 MHR		
0066	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0067	6123000000-E	1670	REFORESTATION	0.5 ACR		
STRUCTURE ITEMS						
0068	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+54.00-L-)	Lump Sum	L.S.	
0069	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+54.00-L-)	Lump Sum	L.S.	
0070	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	52.4 CY		
0071	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+54.00-L-)	Lump Sum	L.S.	
0072	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,048 LB		
0073	8364000000-E	SP	HP12X53 STEEL PILES	525 LF		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	770 LF		
0075	8393000000-N	SP	PILE REDRIVES	24 EA		
0076	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	235.34 LF		
0077	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	297 TON		
0078	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	329 SY		
0079	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0080	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,291.53 LF		

1017/Feb05/Q67323.47/D358988080000/E80

Total Amount Of Bid For Entire Project :

Contract No **C202272**

County (ies): **Wayne**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General