

County : Cleveland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0030000000-N | SP | BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16+97 -L-) | Lump Sum | L.S. | |
| 0003 | 0038000000-E | SP | SHALLOW UNDERCUT | 100 CY | | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0005 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB-BING | 1 ACR | | |
| 0006 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 250 CY | | |
| 0007 | 0080000000-E | SP | CLASS IV SUBGRADE STABILIZATION | 200 TON | | |
| 0008 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 550 SY | | |
| 0009 | 0223000000-E | SP | ROCK PLATING | 230 SY | | |
| 0010 | 0320000000-E | SP | FOUNDATION CONDITIONING FABRIC | 20 SY | | |
| 0011 | 0330000000-E | SP | GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 20 TON | | |
| 0012 | 0335200000-E | SP | 15" DRAINAGE PIPE | 52 LF | | |
| 0013 | 0335850000-E | SP | *** DRAINAGE PIPE ELBOWS (15") | 4 EA | | |
| 0014 | 0986000000-E | SP | GENERIC PIPE ITEM 15" SIDE DRAIN PIPE | 8 LF | | |
| 0015 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 25 TON | | |
| 0016 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 120 TON | | |
| 0017 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 200 TON | | |
| 0018 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 20 TON | | |

County : Cleveland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0019 | 2253000000-E | 840 | PIPE COLLARS | 0.5 CY | | |
| 0020 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 2 EA | | |
| 0021 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 2 EA | | |
| 0022 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 40 LF | | |
| 0023 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 112.5 LF | | |
| 0024 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0025 | 3165000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2) | 4 EA | | |
| 0026 | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 4 EA | | |
| 0027 | 3557000000-E | 866 | ADDITIONAL BARBED WIRE | 50 LF | | |
| 0028 | 3559000000-E | 866 | ** STRAND BARBED WIRE FENCE WITH POSTS (5) | 504 LF | | |
| 0029 | 3565000000-E | 866 | DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (48" X 9-8" X 19'-4") | 1 EA | | |
| 0030 | 3649000000-E | 876 | RIP RAP, CLASS B | 2 TON | | |
| 0031 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 1,360 SY | | |
| 0032 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 326 SF | | |
| 0033 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 94 SF | | |
| 0034 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 96 LF | | |
| 0035 | 5325600000-E | 1510 | 6" WATER LINE | 352 LF | | |
| 0036 | 5540000000-E | 1515 | 6" VALVE | 2 EA | | |

County : Cleveland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0037 | 5800000000-E | 1530 | ABANDON 6" UTILITY PIPE | 310 LF | | |
| 0038 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 550 LF | | |
| 0039 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 250 TON | | |
| 0040 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 50 TON | | |
| 0041 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 375 TON | | |
| 0042 | 6015000000-E | 1615 | TEMPORARY MULCHING | 1 ACR | | |
| 0043 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 50 LB | | |
| 0044 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 1.25 TON | | |
| 0045 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 250 LF | | |
| 0046 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 4 EA | | |
| 0047 | 6029000000-E | SP | SAFETY FENCE | 900 LF | | |
| 0048 | 6030000000-E | 1630 | SILT EXCAVATION | 250 CY | | |
| 0049 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 7,800 SY | | |
| 0050 | 6037000000-E | SP | COIR FIBER MAT | 25 SY | | |
| 0051 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 150 SY | | |
| 0052 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 425 LF | | |
| 0053 | 6070000000-N | SP | SPECIAL STILLING BASINS | 12 EA | | |
| 0054 | 6071010000-E | SP | WATTLE | 25 LF | | |
| 0055 | 6071020000-E | SP | POLYACRYLAMIDE (PAM) | 5 LB | | |
| 0056 | 6071030000-E | SP | COIR FIBER BAFFLES | 150 LF | | |

County : Cleveland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|--|----------|-----------|--------|
| 0057 | 6071050000-E | SP | *** SKIMMER (1-1/2") | 2 | EA | |
| 0058 | 6084000000-E | 1660 | SEEDING & MULCHING | 5 | ACR | |
| 0059 | 6087000000-E | 1660 | MOWING | 0.5 | ACR | |
| 0060 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 | LB | |
| 0061 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 | TON | |
| 0062 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 | LB | |
| 0063 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 0.5 | TON | |
| 0064 | 6114500000-N | SP | SPECIALIZED HAND MOWING | 12 | MHR | |
| 0065 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 12 | EA | |
| STRUCTURE ITEMS | | | | | | |
| 0066 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+97.00-L-) | Lump Sum | L.S. | |
| 0067 | 8105540000-E | SP | 3'-6" DIA DRILLED PIERS IN SOIL | 81.75 | LF | |
| 0068 | 8105640000-E | SP | 3'-6" DIA DRILLED PIERS NOT IN SOIL | 36 | LF | |
| 0069 | 8111400000-E | SP | PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER | 19.64 | LF | |
| 0070 | 8113000000-N | SP | SID INSPECTION | 1 | EA | |
| 0071 | 8114000000-N | SP | SPT TESTING | 1 | EA | |
| 0072 | 8115000000-N | SP | CROSSHOLE SONIC LOGGING | 1 | EA | |
| 0073 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+97.00-L-) | Lump Sum | L.S. | |

County : Cleveland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0074 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 71.2 CY | | |
| 0075 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (16+97.00-L-) | Lump Sum | L.S. | |
| 0076 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 23,850 LB | | |
| 0077 | 8238000000-E | 425 | SPIRAL COLUMN REINFORCING STEEL (BRIDGE) | 4,544 LB | | |
| 0078 | 8364000000-E | SP | HP12X53 STEEL PILES | 330 LF | | |
| 0079 | 8505000000-E | SP | VERTICAL CONCRETE BARRIER RAIL | 285.5 LF | | |
| 0080 | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 330 TON | | |
| 0081 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 365 SY | | |
| 0082 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0083 | 8762000000-E | 430 | 3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS | 1,425 LF | | |

0937/Jan28/Q47820.59/D397515940000/E83

Total Amount Of Bid For Entire Project :

Contract No **C202336**

County (ies): **Cleveland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General