

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (14 + 82.50-L-)	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	85 CY		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	150 TON		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0008	0248000000-N	SP	GENERIC GRADING ITEM GRADING	Lump Sum	L.S.	
0009	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	30 SY		
0010	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0011	0335200000-E	SP	15" DRAINAGE PIPE	28 LF		
0012	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0013	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	36 LF		
0014	1121000000-E	520	AGGREGATE BASE COURSE	38 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	190 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	190 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2000000000-N	806	RIGHT OF WAY MARKERS	9 EA		
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
002C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	115 LF		
0022	3030000000-E	862	STEEL BM GUARDRAIL	225 LF		
002E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3 EA		
002E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
002E	3649000000-E	876	RIP RAP, CLASS B	2 TON		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	410 SY		
003C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	315 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0032	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	970 LF		
0034	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	970 LF		
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	6 EA		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6000000000-E	1605	TEMPORARY SILT FENCE	1,125 LF		
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	175 TON		
0038	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	25 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0044	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0045	6029000000-E	SP	SAFETY FENCE	300 LF		
0046	6030000000-E	1630	SILT EXCAVATION	35 CY		
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,400 SY		
0048	6042000000-E	1632	1/4" HARDWARE CLOTH	400 LF		
0049	6071030000-E	SP	COIR FIBER BAFFLES	45 LF		
0050	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0051	6087000000-E	1660	MOWING	0.5 ACR		
0052	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0053	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0054	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
005E	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0057	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	6 EA		
<b>STRUCTURE ITEMS</b>						
005E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+82.50-L-)	Lump Sum	L.S.	
005E	8112730000-N	SP	PDA TESTING	4 EA		
006C	8112740000-N	SP	PDA ASSISTANCE	4 EA		
0061	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	45.2 CY		
0062	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+82.50-L-)	Lump Sum	L.S.	
0063	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,048 LB		
0064	8364000000-E	SP	HP12X53 STEEL PILES	600 LF		
006E	8365000000-E	SP	HP12X53 GALVANIZED STEEL PILES	780 LF		
006E	8391000000-N	SP	STEEL PILE POINTS	16 EA		
0067	8393000000-N	SP	PILE REDRIVES	10 EA		
006E	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	265.5 LF		
006E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	257 TON		
007C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	285 SY		
0071	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,325 LF		

0649/Feb09/Q24182.95/D330312150000/E72

Total Amount Of Bid For Entire Project :

**Contract No**     **C202337**

**County (ies):**   **Moore**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General