

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	52,778 SY		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	378,515 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	133 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	9,846 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	2,272 SY		
0008	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	23 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,780 TON		
0010	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	83,710 TON		
0011	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	649 TON		
0012	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1 TON		
0013	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	4,604 TON		
0014	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	126,722 LF		
0015	2473000000-N	SP	GENERIC DRAINAGE ITEM ADJUSTMENT OF GRATES AND/OR FRAMES ON DROP INLETS	132 EA		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2473000000-N	SP	GENERIC DRAINAGE ITEM REPAIR OF DROP INLETS	14 EA		
0017	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
001E	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	145,999 LF		
001E	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	54,030 LF		
002C	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3,183 LF		
0021	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	8,834 LF		
0022	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	330 LF		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	48 EA		
0024	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	200,029 LF		
002E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	3,183 LF		
002E	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	8,834 LF		
0027	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	330 LF		
002E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	48 EA		
002E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	3,346 EA		
003C	4960000000-N	SP	GENERIC TRAFFIC CONTROL ITEM REPLACE EXISTING BARRIER DELINEATORS	1,750 EA		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0031	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
1317/Feb04/Q1100326.0/D95838300000/E31			Total Amount Of Bid For Entire Project :			

Contract No **C202564**

County (ies): **Orange**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General