

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	100 CY		
0005	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (18 + 46.50)	Lump Sum	L.S.	
0006	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
0007	0106000000-E	230	BORROW EXCAVATION	100 CY		
0008	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	300 SY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0010	0223000000-E	SP	ROCK PLATING	100 SY		
0011	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	200 CY		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	40 SY		
0013	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0014	0335200000-E	SP	15" DRAINAGE PIPE	96 LF		
0015	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0016	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	160 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	260 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
002C	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0022	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	125 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
002E	3649000000-E	876	RIP RAP, CLASS B	3 TON		
003C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	10 SY		
0031	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	114 SF		
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0034	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,322 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10	EA	
0037	5325000000-E	1510	*** WATER LINE (14")	320	LF	
0038	5326200000-E	1510	12" WATER LINE	120	LF	
0039	5558000000-E	1515	12" VALVE	1	EA	
0040	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	
0041	5804000000-E	1530	ABANDON 12" UTILITY PIPE	436	LF	
0042	5871800000-E	1550	TRENCHLESS INSTALLATION OF 14" IN SOIL	320	LF	
0043	6000000000-E	1605	TEMPORARY SILT FENCE	1,300	LF	
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150	TON	
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	100	TON	
0047	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0049	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0051	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5	EA	
0052	6029000000-E	SP	SAFETY FENCE	1,000	LF	
0053	6030000000-E	1630	SILT EXCAVATION	225	CY	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
005E	6037000000-E	SP	COIR FIBER MAT	250 SY		
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	225 LF		
005E	6071010000-E	SP	WATTLE	20 LF		
005E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	40 LB		
006C	6071030000-E	SP	COIR FIBER BAFFLES	10 LF		
0061	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0062	6087000000-E	1660	MOWING	0.5 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0067	6114500000-N	SP	SPECIALIZED HAND MOWING	15 MHR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		

**STRUCTURE ITEMS**

007C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 46.50-L-)	Lump Sum	L.S.	
0071	8112730000-N	SP	PDA TESTING	1 EA		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0073	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (18+46.50-L-)	Lump Sum	L.S.	
0074	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	58.1 CY		
007E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+46.50-L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	10,175 LB		
0077	8364000000-E	SP	HP12X53 STEEL PILES	300 LF		
007E	8387000000-E	SP	PP 18 X 0.50 GALVANIZED STEEL PILES	640 LF		
007E	8393000000-N	SP	PILE REDRIVES	15 EA		
008C	8503000000-E	460	CONCRETE BARRIER RAIL	365.75 LF		
0081	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	320 TON		
0082	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	356 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,006.13 LF		

0851/Mar03/Q28284.83/D388502180000/E84

Total Amount Of Bid For Entire Project :

**Contract No**     **C202469**

**County (ies):**    **Johnston**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General