

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+80.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
0008	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	300 CY		
0009	0312000000-E	300	SELECT MATERIAL, CLASS IV	1,500 TON		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	740 SY		
0011	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	230 TON		
0012	0335200000-E	SP	15" DRAINAGE PIPE	832 LF		
0013	0335300000-E	SP	18" DRAINAGE PIPE	376 LF		
0014	0995000000-E	340	PIPE REMOVAL	612 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0016	1245000000-E	SP	SHOULDER RECONSTRUCTION	3.7 SMI		
0017	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	680 SY		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	450 TON		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	390 TON		
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,680 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	199 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	45 TON		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	15 EA		
0030	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
0032	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	5 EA		
0033	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0034	2473000000-N	SP	GENERIC DRAINAGE ITEM BICYCLE SAFE STEEL GRATE & FRAME	2 EA		
0035	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,050 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2591000000-E	848	4" CONCRETE SIDEWALK	40 SY		
0037	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	4 EA		
0038	2612000000-E	848	6" CONCRETE DRIVEWAY	100 SY		
0039	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0040	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0041	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	11 EA		
0042	3030000000-E	862	STEEL BM GUARDRAIL	275 LF		
0043	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0044	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0045	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (TL-2)	1 EA		
0046	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0047	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0048	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	700 SY		
0050	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	507 SF		
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144 SF		
0053	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0054	4430000000-N	1130	DRUMS	50 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4435000000-N	1135	CONES	80 EA		
0056	4445000000-E	1145	BARRICADES (TYPE III)	144 LF		
0057	4450000000-N	1150	FLAGGER	1,032 HR		
0058	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,062 LF		
0059	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	12 EA		
0060	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	11 EA		
0061	5325800000-E	1510	8" WATER LINE	772 LF		
0063	5648000000-N	1515	RELOCATE WATER METER	3 EA		
0064	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0065	5691300000-E	1520	8" SANITARY GRAVITY SEWER	20 LF		
0066	5775000000-E	1525	4' DIA UTILITY MANHOLE	1 EA		
0067	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	2 LF		
0068	5801000000-E	1530	ABANDON 8" UTILITY PIPE	660 LF		
0069	5828000000-N	1530	REMOVE UTILITY MANHOLE	1 EA		
0070	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	152 LF		
0071	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	152 LF		
0072	6000000000-E	1605	TEMPORARY SILT FENCE	2,000 LF		
0073	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	425 TON		
0074	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	160 TON		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6012000000-E	1610	SEDIMENT CONTROL STONE	275	TON	
0076	6015000000-E	1615	TEMPORARY MULCHING	4.5	ACR	
0077	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150	LB	
0078	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5	TON	
0079	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0080	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0081	6029000000-E	SP	SAFETY FENCE	2,050	LF	
0082	6030000000-E	1630	SILT EXCAVATION	200	CY	
0083	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,700	SY	
0084	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	500	SY	
0085	6042000000-E	1632	1/4" HARDWARE CLOTH	1,150	LF	
0086	6071010000-E	SP	WATTLE	300	LF	
0087	6071020000-E	SP	POLYACRYLAMIDE (PAM)	85	LB	
0088	6084000000-E	1660	SEEDING & MULCHING	6	ACR	
0089	6087000000-E	1660	MOWING	2.5	ACR	
0090	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0091	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0092	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75	LB	
0093	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25	TON	
0094	6114500000-N	SP	SPECIALIZED HAND MOWING	10	MHR	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0095	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0096	6123000000-E	1670	REFORESTATION	0.15 ACR		
STRUCTURE ITEMS						
0097	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+80.50-L-)	Lump Sum	L.S.	
0098	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+80.50-L-)	Lump Sum	L.S.	
0099	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	63.5 CY		
0100	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	85.3 CY		
0101	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+80.50-L-)	Lump Sum	L.S.	
0102	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,086 LB		
0103	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,475 LB		
0104	8364000000-E	SP	HP12X53 STEEL PILES	920 LF		
0105	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	920 LF		
0106	8393000000-N	SP	PILE REDRIVES	16 EA		
0107	8482000000-E	460	THREE BAR METAL RAIL	250.5 LF		
0108	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	201 TON		
0109	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	222 SY		
0110	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,650 LF		

1014/Apr14/Q52559.15/D469152840000/E110

Total Amount Of Bid For Entire Project :

Contract No **C202375**

County (ies): **Pitt**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General