

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	36 TON		
0003	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2 TON		
0004	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0005	4430000000-N	1130	DRUMS	90 EA		
0006	4435000000-N	1135	CONES	10 EA		
0007	4455000000-N	1150	FLAGGER	80 MD		
0008	4480000000-N	1165	TMIA	1 EA		
0009	4516000000-N	1180	SKINNY DRUM	10 EA		
0010	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,200 LF		
0011	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE)	7,200 LF		
0012	8161000000-E	420	GROOVING BRIDGE FLOORS	56,916 SF		
0013	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0014	8881000000-E	SP	GENERIC STRUCTURE ITEM LATEX MOD CONC OVERLAY - VERY EARLY STRENGTH	351 CY		
0015	8893000000-E	SP	GENERIC STRUCTURE ITEM HYDRO-DEMOLITION OF BRIDGE DECK	6,324 SY		
0016	8893000000-E	SP	GENERIC STRUCTURE ITEM PLACING & FINISHING LATEX MOD CONC OVERLAY - VERY EARLY STRENGTH	6,324 SY		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	8893000000-E	SP	GENERIC STRUCTURE ITEM SCARIFYING BRIDGE DECK	6,635 SY		

1459/Apr06/Q91277.0/D91876100000/E17

Total Amount Of Bid For Entire Project :

Contract No **C202589**

County (ies): **Brunswick**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General