

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0015000000-N	205	SEALING ABANDONED WELLS	5 EA		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	125,400 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	4,900 CY		
0007	0038000000-E	SP	SHALLOW UNDERCUT	500 CY		
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	3,035 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	740 CY		
0010	0141000000-E	240	BERM DITCH CONSTRUCTION	920 LF		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	25,500 SY		
0012	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	5,510 SY		
0013	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	4,000 SY		
0014	0199000000-E	SP	TEMPORARY SHORING	1,058 SF		
0015	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	2,500 CY		
0016	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION AND STOCKPILING CONTAMINATED SOIL	150 TON		
0017	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	3,400 SY		
0018	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,080 TON		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0335200000-E	SP	15" DRAINAGE PIPE	2,324 LF		
0020	0335300000-E	SP	18" DRAINAGE PIPE	1,572 LF		
0021	0335400000-E	SP	24" DRAINAGE PIPE	1,048 LF		
0022	0335500000-E	SP	30" DRAINAGE PIPE	656 LF		
0023	0335600000-E	SP	36" DRAINAGE PIPE	940 LF		
0024	0335700000-E	SP	42" DRAINAGE PIPE	1,136 LF		
0025	0335800000-E	SP	48" DRAINAGE PIPE	134 LF		
0026	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	13 EA		
0027	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (18")	5 EA		
0028	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (24")	2 EA		
0029	0354000000-E	SP	**** RC PIPE CULVERTS, CLASS ***** (54", III)	72 LF		
0030	0354000000-E	SP	**** RC PIPE CULVERTS, CLASS ***** (72", III)	72 LF		
0031	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	108 LF		
0032	0448300000-E	SP	18" RC PIPE CULVERTS, CLASS IV	328 LF		
0033	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	404 LF		
0034	0448500000-E	SP	30" RC PIPE CULVERTS, CLASS IV	92 LF		
0035	0453000000-E	310	*** PIPE END SECTION (15")	20 EA		
0036	0453000000-E	310	*** PIPE END SECTION (18")	3 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	0453000000-E	310	*** PIPE END SECTION (24")	1 EA		
0038	0973100000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** IN SOIL (36", 0.5", B)	222 LF		
0039	0973100000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** IN SOIL (48", 0.625", B)	53 LF		
0040	0973300000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** NOT IN SOIL (36", 0.5", B)	222 LF		
0041	0973300000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** NOT IN SOIL (48", 0.625", B)	53 LF		
0042	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	716 LF		
0043	0986000000-E	SP	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	72 LF		
0044	0995000000-E	340	PIPE REMOVAL	1,596 LF		
0045	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0046	1077000000-E	SP	#57 STONE	137 TON		
0047	1110000000-E	510	STABILIZER AGGREGATE	1,500 TON		
0048	1121000000-E	520	AGGREGATE BASE COURSE	35,700 TON		
0049	1220000000-E	545	INCIDENTAL STONE BASE	3,600 TON		
0050	1231000000-E	560	SHOULDER BORROW	6,500 CY		
0051	1275000000-E	600	PRIME COAT	8,575 GAL		
0052	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***** DEPTH (3")	5,900 SY		
0053	1308000000-E	607	MILLING ASPHALT PAVEMENT, ***** TO ***** DEPTH (0" TO 5")	500 SY		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	10,100 TON		
0055	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	10,600 TON		
0056	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	15,200 TON		
0057	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	1,100 TON		
0058	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,920 TON		
0059	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	420 TON		
0060	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0061	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0062	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0063	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0064	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0065	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0066	2209000000-E	838	ENDWALLS	9.1 CY		
0067	2220000000-E	838	REINFORCED ENDWALLS	14.2 CY		
0068	2264000000-E	840	PIPE PLUGS	1.509 CY		
0069	2275000000-E	SP	FLOWABLE FILL	18.8 CY		
0070	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	74 EA		
0071	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	20.05 LF		
0072	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	5 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	13 EA		
0074	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	36 EA		
0075	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0076	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0077	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0078	2473000000-N	SP	GENERIC DRAINAGE ITEM BICYCLE SAFE STEEL GRATE AND FRAME	3 EA		
0079	2535000000-E	846	***X *** CONCRETE CURB (8" X 12")	170 LF		
0080	2556000000-E	846	SHOULDER BERM GUTTER	1,370 LF		
0081	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	1,370 LF		
0082	2619000000-E	850	4" CONCRETE PAVED DITCH	70 SY		
0083	2738000000-E	SP	GENERIC PAVING ITEM 6" CONCRETE DRIVEWAY	2,910 SY		
0084	3030000000-E	862	STEEL BM GUARDRAIL	4,600 LF		
0085	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	487.5 LF		
0086	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	6 EA		
0087	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0088	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	16 EA		
0089	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,275 LF		
0090	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	50 LF		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	1 EA		
0092	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	11 EA		
0093	3572000000-E	867	CHAIN LINK FENCE RESET	70 LF		
0094	3628000000-E	876	RIP RAP, CLASS I	160 TON		
0095	3635000000-E	876	RIP RAP, CLASS II	50 TON		
0096	3649000000-E	876	RIP RAP, CLASS B	556 TON		
0097	3651000000-E	SP	BOULDERS	235 TON		
0098	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	5,565 SY		
0099	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	808 LF		
0100	4096000000-N	904	SIGN ERECTION, TYPE D	3 EA		
0101	4102000000-N	904	SIGN ERECTION, TYPE E	38 EA		
0102	4108000000-N	904	SIGN ERECTION, TYPE F	3 EA		
0103	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	2 EA		
0104	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0105	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	43 EA		
0106	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	3,225 SF		
0107	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	368 SF		
0108	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	628 SF		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	16 DAY		
0110	4430000000-N	1130	DRUMS	520 EA		
0111	4435000000-N	1135	CONES	100 EA		
0112	4445000000-E	1145	BARRICADES (TYPE III)	488 LF		
0113	4455000000-N	1150	FLAGGER	2,700 MD		
0114	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0115	4480000000-N	1165	TMIA	1 EA		
0116	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	390 LF		
0117	4510000000-N	SP	LAW ENFORCEMENT	108 HR		
0118	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM WARNING FLAGS	8 EA		
0119	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	34,158 LF		
0120	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	35,751 LF		
0121	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	440 LF		
0122	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	256 LF		
0123	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	29 EA		
0124	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	280,814 LF		
0125	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	480 LF		
0126	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	16 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	8,000 LF		
0128	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	388 EA		
0129	6000000000-E	1605	TEMPORARY SILT FENCE	21,000 LF		
0130	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	4,000 TON		
0131	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5,600 TON		
0132	6012000000-E	1610	SEDIMENT CONTROL STONE	3,500 TON		
0133	6015000000-E	1615	TEMPORARY MULCHING	80 ACR		
0134	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,450 LB		
0135	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	7.75 TON		
0136	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,800 LF		
0137	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	20 EA		
0138	6029000000-E	SP	SAFETY FENCE	6,000 LF		
0139	6030000000-E	1630	SILT EXCAVATION	16,200 CY		
0140	6036000000-E	1631	MATTING FOR EROSION CONTROL	125,000 SY		
0141	6037000000-E	SP	COIR FIBER MAT	685 SY		
0142	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	4,000 SY		
0143	6042000000-E	1632	1/4" HARDWARE CLOTH	3,000 LF		
0144	6045000000-E	SP	*** TEMPORARY PIPE (54")	245 LF		
0145	6070000000-N	SP	SPECIAL STILLING BASINS	5 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0146	6071012000-E	SP	COIR FIBER WATTLE	1,675 LF		
0147	6071020000-E	SP	POLYACRYLAMIDE (PAM)	580 LB		
0148	6071030000-E	SP	COIR FIBER BAFFLES	9,100 LF		
0149	6071050000-E	SP	*** SKIMMER (1-1/2")	7 EA		
0150	6084000000-E	1660	SEEDING & MULCHING	45 ACR		
0151	6087000000-E	1660	MOWING	54 ACR		
0152	6090000000-E	1661	SEED FOR REPAIR SEEDING	600 LB		
0153	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.75 TON		
0154	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,050 LB		
0155	6108000000-E	1665	FERTILIZER TOPDRESSING	31.25 TON		
0156	6111000000-E	SP	IMPERVIOUS DIKE	35 LF		
0157	6114500000-N	SP	SPECIALIZED HAND MOWING	30 MHR		
0158	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
0159	6123000000-E	1670	REFORESTATION	10 ACR		
0160	6126000000-E	SP	STREAMBANK REFORESTATION	0.95 ACR		
0161	7060000000-E	1705	SIGNAL CABLE	1,010 LF		
0162	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	8 EA		
0163	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	4 EA		
0164	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	1,280 LF		
0165	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2")	370 LF		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0166	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	11 EA		
0167	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,040 LF		
0168	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	1,740 LF		
0169	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	2 EA		
0170	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	2 EA		
0171	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	2 EA		
0172	7613000000-N	SP	SOIL TEST	4 EA		
0173	7614100000-E	SP	DRILLED PIER FOUNDATION	20 CY		
0174	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	4 EA		
0175	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0176	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
0177	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	6 EA		
0178	7901000000-N	1753	CABINET BASE EXTENDER	2 EA		
0179	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS LIGHTNING AR- RESTOR	1 EA		
0180	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEM	1 EA		
<b>CULVERT ITEMS</b>						
0181	8196000000-E	420	CLASS A CONCRETE (CULVERT)	45.9 CY		
0182	8590000000-E	876	RIP RAP, CLASS ** (I)	9 TON		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0183	8804000000-N	SP	GENERIC CULVERT ITEM PRECAST REINF CONC 3-SIDED CULVERT @ STA 109+00.28-L-	Lump Sum	L.S.	
0184	8804000000-N	SP	GENERIC CULVERT ITEM REMOVAL OF EXISTING STRUCTURES @ STA 109+00.28-L-	Lump Sum	L.S.	
1000/Apr13/Q894138.859/D656583704000/E184			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202240**

**County (ies):**   **Macon**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General